

**DIVISION 23: HEATING, VENTILATING, AND AIR-CONDITIONING**

**23 0000 HEATING, VENTILATING, AND AIR-CONDITIONING**

23 0501 COMMON HVAC REQUIREMENTS  
23 0502 DEMOLITION AND REPAIR  
23 0553 IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT  
23 0593 TESTING, ADJUSTING, AND BALANCING  
23 0800 FIRE STOPPING

**23 2000 HVAC PIPING AND PUMPS**

23 2113 HYDRONIC PIPING  
23 2118 BACKFLOW PREVENTER VALVE  
23 2123 CIRCULATING PUMPS AND ACCESSORIES  
23 2125 CLEANING AND FLUSHING STEAM AND WATER CIRCULATING SYSTEMS  
23 2510 GLYCOL SYSTEM & GLYCOL FEED PUMP

**23 5000 CENTRAL HEATING EQUIPMENT**

23 5719 PLATE AND FRAME HEAT EXCHANGERS

## SECTION 23 0501 – COMMON HVAC REQUIREMENTS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and General Provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Furnish labor, materials, and equipment necessary for completion of work as described in Contract Documents.
- B. It is the intent of these specifications that the systems specified herein are to be complete and operational before being turned over to the owner. During the bidding process, the contractor is to ask questions or call to the engineer's attention any items that are not shown or may be required to make the system complete and operational. Once the project is bid and the contractor has accepted the contract, it is his responsibility to furnish and install all equipment and parts necessary to provide a complete and operational system without additional cost to the owner.
- C. Furnish and install fire stopping materials to seal penetrations through fire rated structures and draft stops.
- D. Includes But Not Limited To:
  - 1. General procedures and requirements for HVAC.
- E. Related Sections:
  - 1. Section 23 0593: Testing, Adjusting, and Balancing for HVAC.

#### 1.3 SUBMITTALS

- A. Substitutions: By specific designation and description, standards are established for specialties and equipment. Other makes of specialties and equipment of equal quality will be considered provided such proposed substitutions are submitted to the Architect for his approval, complete with specification data showing how it meets the specifications, at least 5 working days prior to bid opening. A list of approved substitutions will be published as an addendum.
  - 1. Submit a single copy of Manufacturer's catalog data including Manufacturer's complete specification for each proposed substitution.
  - 2. The Architect or Engineer is to be the sole judge as to the quality of any material offered as an equal.
- B. Product Data, Shop Drawings: Within 30 days after award of contract, submit 10 sets of Manufacturer's catalog data for each manufactured item.
  - 1. Literature shall include enough information to show complete compliance with Contract Document requirements.
  - 2. Mark literature to indicate specific item with applicable data underlined.
  - 3. Information shall include but not be limited to capacities, ratings, type of material used, guarantee, and such dimensions as are necessary to check space requirements.
  - 4. When accepted, submittal shall be an addition to Contract Documents and shall be in equal force. No variation shall be permitted.
  - 5. Even though the submittals have been accepted by the Engineer, it does not relieve the contractor from meeting all of the requirements of the plans and specifications and providing a complete and operational system.
- C. Drawings of Record: One complete sets of blue line mechanical drawings shall be provided for the purpose of showing a complete picture of the work as actually installed.

1. These drawings shall serve as work progress report sheets. Contractor shall make notations neat and legible therein daily as the work proceeds.
2. The drawings shall be kept at the job at a location designated by the Mechanical Engineer.
3. At completion of the project these "as-built" drawings shall be signed by the Contractor, dated, and returned to the Architect.

D. Operating Instructions and Service Manual: The Mechanical Contractor shall prepare 2 copies of an Operation and Maintenance Manual for all mechanical systems and equipment used in this project. Manuals shall be bound in hard-backed binders and the front cover and spine of each binder shall indicate the name and location of the project. Use plastic tab indexes for all sections. Provide a section for each different type of equipment item. The following items shall be included in the manual, together with any other pertinent data. This list is not complete and is to be used as a guide.

1. Provide a master index at the beginning of the manual showing all items included.
2. The first section of the manual shall contain:
  - a. Names, addresses, and telephone numbers of Architect, Mechanical Engineer, Electrical Engineer, General Contractor, Plumbing Contractor, Sheet Metal Contractor, and Temperature Control Contractor.
  - b. List of Suppliers which shall include a complete list of each piece of equipment used with the name, address, and telephone number of vendor.
  - c. General Description of Systems including –
    - 1) Location of all major equipment
    - 2) Description of the various mechanical systems
    - 3) Description of operation and control of the mechanical systems
    - 4) Suggested maintenance schedule
  - d. Copy of contractor's written warranty
3. Provide a copy of approved submittal literature for each piece of equipment.
4. Provide maintenance and operation literature published by the manufacturer for each piece of equipment which includes: oiling, lubrication and greasing data; belt sizes, types and lengths; wiring diagrams; step-by-step procedure to follow in putting each piece of mechanical equipment in operation.
5. Include parts numbers of all replaceable items.
6. Provide control diagram and operation sequence, along with labeling of control piping and instruments to match diagram.
7. Include a valve chart indicating valve locations.

E. Include air balance and/or water balance reports.

#### 1.4 SUBMITTALS FOR COMMON HVAC REQUIREMENTS

- A. Samples: Sealer and gauze proposed for sealing ductwork.
- B. Quality Assurance / Control:
  1. Manufacturer's installation manuals providing detailed instructions on assembly, joint sealing, and system pressure testing for leaks.
  2. Specification data on sealer and gauze proposed for sealing ductwork.
- C. Quality Assurance
  1. Requirements: Construction details not specifically called out in Contract Documents shall conform to applicable requirements of SMACNA HVAC Duct Construction Standards.
  2. Pre-Installation Conference: Schedule conference immediately before installation of ductwork.

#### 1.5 QUALITY ASSURANCE

- A. Requirements of Regulatory Agencies:

1. Perform work in accordance with applicable provisions of local and state Plumbing Code, Gas Ordinances, and adoptions thereof. Provide materials and labor necessary to comply with rules, regulations, and ordinances.
  2. In case of differences between building codes, state laws, local ordinances, utility company regulations, and Contract Documents, the most stringent shall govern. Promptly notify Architect in writing of such differences.
- B. Applicable Specifications: Referenced specifications, standards, and publications shall be of the issues in effect on date of Advertisement for Bid.
1. "Heating, Ventilating and Air Conditioning Guide" published by the American Society of Heating and Air Conditioning Engineers.
  2. "Engineering Standards" published by the Heating, Piping, and Air Conditioning Contractors National Association.
  3. "2015 International Building Code", "2015 International Mechanical Code", and "2015 International Fire Code" as published by the International Conference of Building Officials.
  4. "2017 Idaho Plumbing Code" as published by the International Association of Plumbing and Mechanical Officials.
  5. "National Electrical Code" as published by the National Fire Protection Association.
  6. "2015 International Energy Conservation Code".
- C. Identification: Motor and equipment name plates as well as applicable UL and AGA labels shall be in place when Project is turned over to Owner.

#### 1.6 INSPECTIONS AND PERMITS

- A. Pay for permits, fees, or charges for inspection or other services. Local and state codes and ordinances must be properly executed without expense to Owner and are considered as minimum requirements. Local and state codes and ordinances do not relieve the Contractor from work shown that exceeds minimum requirements.

#### 1.7 ADDITIONAL WORK:

- A. Design is based on equipment as described in the drawing equipment schedule. Any change in foundation bases, electrical wiring, conduit connections, piping, controls and openings required by alternate equipment submitted and approved shall be paid for by this division. All work shall be in accordance with the requirements of the applicable sections.

### **PART 2 - PRODUCTS FOR COMMON HVAC REQUIREMENTS**

- A. Finishes, Where Applicable: Colors as selected by Architect.
- B. Duct Hangers:
1. One inch 25 mm by 18 ga 1.27 mm galvanized steel straps or steel rods as shown on Drawings, and spaced not more than 96 inches 2 400 mm apart. Do not use wire hangers.
  2. Attaching screws at trusses shall be 2 inch 50 mm No. 10 round head wood screws. Nails not allowed.

### **PART 3 - EXECUTION**

#### 3.1 EXAMINATION

- A. Site Inspection:
1. Examine premises and understand the conditions which may affect performance of work of this Division before submitting proposals for this work.
  2. No subsequent allowance for time or money will be considered for any consequence related to failure to examine site conditions.

- B. Drawings:
1. Mechanical drawings show general arrangement of piping, ductwork, equipment, etc, and do not attempt to show complete details of building construction which affect installation. This Contractor shall refer to architectural, structural, and electrical drawings for additional building detail which affect installation of his work.
    - a. Follow mechanical drawings as closely as actual building construction and work of other trades will permit.
    - b. No extra payments will be allowed where piping and/or ductwork must be offset to avoid other work or where minor changes are necessary to facilitate installation.
    - c. Everything shown on the mechanical drawings shall be the responsibility of Mechanical Contractor unless specifically noted otherwise.
  2. Consider architectural and structural drawings part of this work insofar as these drawings furnish information relating to design and construction of building. These drawings take precedence over mechanical drawings.
  3. Because of small scale of mechanical drawings, it is not possible to indicate all offsets, fittings, and accessories which may be required. Investigate structural and finish conditions affecting this work and arrange work accordingly, providing such fittings, valves, and accessories required to meet conditions. Do not scale drawings for locations of equipment or piping. Refer to large scale dimensioned drawings for exact locations.
- C. Insure that items to be furnished fit space available. Make necessary field measurements to ascertain space requirements including those for connections and furnish and install equipment of size and shape so final installation shall suit true intent and meaning of Contract Documents.
1. If approval is received to use other than specified items, responsibility for specified capacities and insuring that items to be furnished will fit space available lies with this Division.
  2. If non-specified equipment is used and it will not fit job site conditions, this Contractor assumes responsibility for replacement with items named in Contract Documents.

### 3.2 PREPARATION

- A. Cut carefully to minimize necessity for repairs to existing work. Do not cut beams, columns, or trusses.
1. Patch and repair walls, floors, ceilings, and roofs with materials of same quality and appearance as adjacent surfaces unless otherwise shown. Surface finishes shall exactly match existing finishes of same materials.
  2. Each Section of this Division shall bear expense of cutting, patching, repairing, and replacing of work of other Sections required because of its fault, error, tardiness, or because of damage done by it.
  3. Cutting, patching, repairing, and replacing pavements, sidewalks, roads, and curbs to permit installation of work of this Division is responsibility of Section installing work.

### 3.3 INSTALLATION

- A. Arrange pipes, ducts, and equipment to permit ready access to valves, unions, traps, starters, motors, control components, and to clear openings of doors and access panels.

### 3.4 STORAGE AND PROTECTION OF MATERIALS:

- A. Provide storage space for storage of materials and assume complete responsibility for losses due to any cause whatsoever. Storage shall not interfere with traffic conditions in any public thoroughfare.
- B. Protect completed work, work underway, and materials against loss or damage.
- C. Close pipe openings with caps or plugs during installation. Cover fixtures and equipment and protect against dirt, or injury caused by water, chemical, or mechanical accident.

### 3.5 EXCAVATION AND BACKFILL

- A. Perform necessary excavation of whatever substance encountered for proper laying of all pipes and underground ducts.
  - 1. Excavated materials not required for fill shall be removed from site as directed by Engineer.
  - 2. Excavation shall be carried low enough to allow a minimum coverage over underground piping of 5'-0" or to be below local frost level.
  - 3. Excess excavation below required level shall be backfilled at Contractor's expense with earth, sand, or gravel as directed by Engineer. Tamp ground thoroughly.
  - 4. Ground adjacent to all excavations shall be graded to prevent water running into excavated areas.
- B. Backfill pipe trenches and allow for settlement.
  - 1. Backfill shall be mechanically compacted to same density as surrounding undisturbed earth.
  - 2. Cinders shall not be used in backfilling where steel or iron pipe is used.
  - 3. No backfilling shall be done until installation has been approved by the Engineer.

### 3.6 COOPERATION

- A. Cooperate with other crafts in coordination of work. Promptly respond when notified that construction is ready for installation of work under Division 23000. Contractor will be held responsible for any delays which might be caused by his negligence or failure to cooperate with the other Contractors or crafts.

### 3.7 SUPERVISION

- A. Provide a competent superintendent in charge of the work at all times. Anyone found incompetent shall be removed at once and replaced by someone satisfactory, when requested by the Architect.

### 3.8 INSTALLATION CHECK:

- A. An experienced, competent, and authorized representative of the manufacturer or supplier of each item of equipment indicated in the equipment schedule shall visit the project to inspect, check, adjust if necessary, and approve the equipment installation. In each case, the equipment supplier's representative shall be present when the equipment is placed in operation. The equipment supplier's representative shall revisit the project as often as necessary until all trouble is corrected and the equipment installation and operation is satisfactory to the Engineer.
- B. Each equipment supplier's representative shall furnish to the Owner, through the Engineer, a written report certifying the following:
  - 1. Equipment has been properly installed and lubricated.
  - 2. Equipment is in accurate alignment.
  - 3. Equipment is free from any undue stress imposed by connecting piping or anchor bolts.
  - 4. Equipment has been operated under full load conditions.
  - 5. Equipment operated satisfactorily.
- C. All costs for this installation check shall be included in the prices quoted by equipment suppliers.

### 3.9 CLEANING EQUIPMENT AND PREMISES

- A. Properly lubricate equipment before Owner's acceptance.
- B. Clean exposed piping, ductwork, equipment, and fixtures. Repair damaged finishes and leave everything in working order.
- C. Remove stickers from fixtures and adjust flush valves.

- D. At date of Substantial Completion, air filters shall be new, clean, and approved by Owner's representative.
- E. Trap elements shall be removed during cleaning and flushing period. Replace trap elements and adjust after cleaning and flushing period.

### 3.10 TESTS

- A. No piping work, fixtures, or equipment shall be concealed or covered until they have been inspected and approved by the inspector. Notify inspector when the work is ready for inspection.
- B. All work shall be completely installed, tested as required by Contract Documents and the city and county ordinances and shall be leak-tight before the inspection is requested.
- C. Tests shall be repeated to the satisfaction of those making the inspections.
- D. Water piping shall be flushed out, tested at 100 psi and left under pressure of supply main or a minimum of 40 psi for the balance of the construction period.

### 3.11 WARRANTY

- A. Contractor shall guarantee work under Division 23 to be free from inherent defects for a period of one year from acceptance.
  - 1. Contractor shall repair, revise or replace any and all such leaks, failure or inoperativeness due to defective work, materials, or parts free of charge for a period of one year from final acceptance, provided such defect is not due to carelessness in operation or maintenance.
  - 2. In addition, the Contractor shall furnish all refrigeration emergency repairs, emergency service and all refrigerant required due to defective workmanship, materials, or parts for a period of one year from final acceptance at no cost to the Owner, provided such repairs, service and refrigerant are not caused by lack of proper operation and maintenance.
- B. In addition to warranty specified in General Conditions, heating, cooling, and plumbing systems are to be free from noise in operation that may develop from failure to construct system in accordance with Contract Documents.

### 3.12 SYSTEM START-UP, OWNER'S INSTRUCTIONS

- A. Off-Season Start-up
  - 1. If Substantial Completion inspection occurs during heating season, schedule spring start-up of cooling systems. If inspection occurs during cooling season, schedule autumn start-up for heating systems.
  - 2. Notify Owner 7 days minimum before scheduled start-up.
  - 3. Time will be allowed to completely service, test, check, and off-season start systems. During allowed time, train Owner's representatives in operation and maintenance of system.
  - 4. At end of off-season start-up, furnish Owner with letter confirming that above work has been satisfactorily completed.
- B. Owner's Instructions
  - 1. Instruct building maintenance personnel and Owner Representative in operation and maintenance of mechanical systems utilizing Operation & Maintenance Manual when so doing.
  - 2. Minimum instruction periods shall be as follows –
    - a. Mechanical - Four hours.
    - b. Temperature Control - Four hours.
    - c. Refrigeration - Two hours.

3. Instruction periods shall occur after Substantial Completion inspection when systems are properly working and before final payment is made.
4. None of these instructional periods shall overlap another.

### 3.13 PROTECTION

- A. Do not run heat pump, air handling units, fan coil units, or other pieces of equipment used for moving supply air without proper air filters installed properly in system.
- B. The mechanical systems are not designed to be used for temporary construction heat. If any equipment is to be started prior to testing and substantial completion, such equipment will be returned to new condition with full one year warranties, from date of substantial completion after any construction use. This includes, but is not necessarily limited to: Equipment, filters, ductwork, fixtures, etc.

### 3.14 COMMON HVAC REQUIREMENTS:

#### A. INSTALLATION

1. During installation, protect open ends of ducts by covering with plastic sheet tied in place to prevent entrance of debris and dirt.
2. Make necessary allowances and provisions in installation of sheet metal ducts for structural conditions of building. Revisions in layout and configuration may be allowed, with prior written approval of Architect. Maintain required airflows in suggesting revisions.
3. Hangers And Supports:
  - a. Install pair of hangers close to each transverse joint and elsewhere as required by spacing indicated in table on Drawings.
  - b. Install upper ends of hanger securely to floor or roof construction above by method shown on Drawings.
  - c. Attach strap hangers to ducts with cadmium-plated screws. Use of pop rivets or other means will not be accepted.
  - d. Where hangers are secured to forms before concrete slabs are poured, cut off flush all nails, strap ends, and other projections after forms are removed.
  - e. Secure vertical ducts passing through floors by extending bracing angles to rest firmly on floors without loose blocking or shimming. Support vertical ducts, which do not pass through floors, by using bands bolted to walls, columns, etc. Size, spacing, and method of attachment to vertical ducts shall be same as specified for hanger bands on horizontal ducts.

#### B. CLEANING

1. Clean interior of duct systems before final completion.

END OF SECTION 23 0501



## **SECTION 23 0502 - DEMOLITION AND REPAIR**

### **PART 1 - GENERAL**

#### 1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

#### 1.2 SUMMARY

- A. Under this section remove obsolete piping and mechanical equipment and relocate, reconnect or replace existing piping affected by demolition or new construction. Remove concealed piping abandoned due to demolition or new construction, or cap piping flush with existing surfaces.

#### 1.3 DRAWINGS AND EXISTING CONDITIONS

- A. All relocations, reconnections and removals are not necessarily indicated on the drawings. As such, the Contractor shall make adequate allowance in his proposal for this work as no extra charges will be allowed for these items.

### **PART 2 - NOT USED**

### **PART 3 - EXECUTION**

#### 3.1 TEMPORARY CONNECTIONS

- A. Where existing piping must remain in service to supply occupied areas during construction, provide temporary piping, connections, and equipment to maintain service to such areas. All shall be performed in a neat and safe manner to prevent injury to the building or its occupants.

#### 3.2 EXISTING TO BE ABANDONED

- A. All required drilling, cutting, block-outs and demolition work required for the removal and/or installation of the mechanical system is the responsibility of this Contractor.
- B. No joists, beams, girders, trusses or columns shall be cut by any Contractor without written permission from the Architect.
- C. The patching, repair, and finishing to existing or new surfaces is the responsibility of this Contractor, unless specifically called for under sections of specifications covering these materials.
- D. Disconnect all equipment that is to be removed or relocated. Relocate any existing equipment that obstructs new construction.

#### 3.3 EXISTING TO REMAIN IN USE

- A. Where affected by demolition or new construction, relocate, replace, extend, or repair piping and equipment to allow continued use of same. Use methods and materials as specified for new construction.

#### 3.4 MATERIALS AND EQUIPMENT REMOVED

- A. All obsolete materials, piping, and equipment shall become the property of the Contractor and be removed from the site promptly.

END OF SECTION 23 0502

March 2020

1

23 0502  
DEMOLITION AND REPAIR

## **SECTION 23 0553 - IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 05 01 apply to this Section.

#### **1.2 SUMMARY**

- A. Furnish and install identification of equipment and piping as described in Contract Documents.
- B. Mechanical Contractor shall touch-up equipment where factory paint has been damaged. Repaint entire item where more than 20 percent of the surface is involved.
- C. Primary painting of walls, ceilings, ductwork, piping and plenums is covered in the general painting section of these Contract Documents.

### **PART 2 - PRODUCTS**

#### **2.1 PAINT**

- A. Benjamin Moore Impervo or equivalent by Paint Manufacturer approved in Section 09 900.
- B. Use appropriate primer.

#### **2.2 LABELS**

- A. Black Formica with white reveal on engraving.

#### **2.3 CODED BANDS**

- A. Using colored bands and arrows to indicate supply and return, with colored reflective tape, color code all piping installed in this contract at not more than 20-foot intervals, at equipment, at walls, etc., in accordance with ANSI Standards.
- B. Approved Manufacturers:
  - 1. Seton
  - 2. Craftmark

#### **2.4 PIPE IDENTIFICATION**

- A. In addition to the colored bands, stencil with black paint in 1/2 inch high letters a symbol and directional arrow for all fluids handled or use Seaton coded and colored pipe markers and arrows to meet ANSI Standards.

#### **2.5 EQUIPMENT IDENTIFICATION**

- A. Provide an engraved plastic plate for each piece of equipment stating the name of the item, symbol number, area served, and capacity. Label all control components with plastic embossed mechanically attached labels. Sample:
  - 1. Supply Fan SF-1 - North Classrooms
  - 2. 10,000 CFM @ 2.5"

2.6 VALVE IDENTIFICATION

- A. Make a list of and tag all valves installed in this work.
  - 1. Valve tags shall be of brass, not less than 1"x2" size, hung with brass chains.
  - 2. Tag shall indicate plumbing or heating service.

**PART 3 - EXECUTION**

3.1 APPLICATION

- A. Engraved Plates:
  - 1. Identify thermostats and control panels in mechanical rooms, furnaces, boilers and hot water heating specialties, duct furnaces, air handling units, electric duct heaters, and condensing units with following data engraved and fastened to equipment with screws –
    - a. Equipment mark noted on Drawings (i.e., SF-1)
    - b. Area served (i.e., North Classrooms)
    - c. Capacity (10,000 CFM @ 2.5)
- B. Stenciling:
  - 1. Locate identifying legends and directional arrows at following points on each piping system –
    - a. Adjacent to each item of equipment and special fitting.
    - b. At point of entry and exit where piping goes through wall.
    - c. On each riser and junction.
    - d. Every 50 feet on long continuous lines.
  - 2. Steam Pipe, Hot Water Heating, Chilled Water, Gas, & Valve Identification –
    - a. Identify specific pipe contents by stenciling pipe with written legend and placing of arrows to indicate direction of flow.
- C. Painting:
  - 1. Background Color - Provide by continuous painting of piping.

Symbol	Name	Color
CTS	Cooling Tower Supply	Green
CTR	Cooling Tower Return	Green

- 2. Identification stenciling and flow arrows shall be following colors for proper contrast:

<u>Arrows &amp; ID Stenciling</u>	<u>Color Shade of Pipe</u>
White	Red, Grays, & black
Black	Yellows, Oranges, Greens, & White

END OF SECTION 23 0553

## SECTION 23 0593 - TESTING, ADJUSTING, AND BALANCING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Division 23 - Common HVAC Requirements and Basic Mechanical Materials and Methods Sections apply to work of this section.

#### 1.2 SUMMARY SCOPE

- A. This Section includes TAB to produce design objectives for the following:
  - 1. Hydronic Piping Systems.
    - a. Cooling Tower
    - b. Pumps

#### 1.3 SUBMITTALS

- A. Agency Data:
  - 1. Submit proof that the proposed testing, adjusting, and balancing agency meets the qualifications specified below. The firm or individuals performing the work herein specified may not be the installing firm.
- B. Engineer and Technicians Data:
  - 1. Submit proof that the Test and Balance Engineer assigned to supervise the procedures, and the technicians proposed to perform the procedures meet the qualifications specified below.
- C. Procedures and Agenda: Submit a synopsis of the testing, adjusting, and balancing procedures and agenda proposed to be used for this project.
- D. Sample Forms: Submit sample forms, if other than those standard forms prepared by the AABC or NEBB are proposed.
- E. Certified Reports: Submit testing, adjusting, and balancing reports bearing the seal and signature of the Test and Balance Engineer. The reports shall be certified proof that the systems have been tested, adjusted, and balanced in accordance with the referenced standards; are an accurate representation of how the systems have been installed; are a true representation of how the systems are operating at the completion of the testing, adjusting, and balancing procedures; and are an accurate record of all final quantities measured, to establish normal operating values of the systems. Follow the procedures and format specified below.
  - 1. Draft Reports: Upon completion of testing, adjusting, and balancing procedures, prepare draft reports on the approved forms. Draft reports may be hand written, but must be complete, factual, accurate, and legible. Organize and format draft reports in the same manner specified for the final reports. Submit 2 complete sets of draft reports. Only 1 complete set of draft reports will be returned.
  - 2. Final Report: Upon verification and approval of draft reports, prepare final reports, type written, and organized and formatted as specified below. Submit 4 complete sets of final reports.
  - 3. Report Format: Report forms shall be those standard forms prepared by the referenced standard for each respective item and system to be tested, adjusted, and balanced. Bind report forms complete with schematic systems diagrams and other data. Divide the contents of the binder into the below listed divisions, separated by divider tabs:
    - a. General Information and Summary
    - b. Air Systems
    - c. Temperature Control System Verification.
- F. Report Contents: Provide the following minimum information, forms, and data:

1. General information and Summary: Inside cover sheet to identify testing, adjusting, balancing agency, Contractor, Owner, Engineer, and Project. Include addresses and contact names and telephone numbers. Also include a certification sheet containing the seal and name, address, telephone number, and signature of the Certified Test and Balance Engineer. Include in this division a listing of the instrumentation used for the procedures along with the instrument calibration sheet.
2. The remainder of the report shall contain the appropriate forms containing as a minimum, the information indicated on the standard report forms prepared by the AABC or NEBB, for each respective item and system. Prepare a schematic diagram for each item of equipment and system to accompany each respective report form. The report shall contain the following information, and all other data resulting from the testing, adjusting, and balancing work:
  - a. All nameplate and specification data for all air handling equipment and motors.
  - b. Actual metered running amperage for each phase of each motor on all pumps and air handling equipment.
  - c. Actual metered voltage at air handling equipment (phase-to-phase for all phases).
  - d. Fan RPM for each piece of air handling equipment.
  - e. Total actual CFM being handled by each piece of air handling equipment.
  - f. Actual CFM of systems by rooms.
3. Certify that all smoke and fire dampers operate properly and can be reset under actual system operating conditions.

G. Calibration Reports:

1. Submit proof that all required instrumentation has been calibrated to tolerances specified in the referenced standards, within a period of six months prior to starting the project.

#### 1.4 CERTIFICATION

A. Agency Qualifications:

1. Employ the services of a certified testing, adjusting, and balancing agency meeting the qualifications specified below, to be the single source of responsibility to test, adjust, and balance the building mechanical systems identified above, to produce the design objectives. Services shall include checking installations for conformity to design, measurement, and establishment of the fluid quantities of the mechanical systems as required to meet design specifications, recording and reporting the results, and operation of all systems to demonstrate satisfactory performance to the owner.
2. The testing, adjusting, and balancing agency certified by National Environmental Balancing Bureau (NEBB) or Associated Air Balance Council (AABC) in those testing and balancing disciplines required for this project, and having at least one person certified by NEBB or AABC as a Test and Balance supervisor, and a registered professional mechanical engineer, licensed in the state where the work will be performed.

B. Codes and Standard:

1. NEBB: "Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems."
2. AABC: "National Standards for Total System Balance."
3. ASHRAE: ASHRAE Handbook, 1984 Systems Volume, Chapter 37, Testing, Adjusting, and Balancing.

#### 1.5 PROJECT CONDITIONS

- A. Systems Operation: Systems shall be fully operation and clean prior to beginning procedures.

#### 1.6 SEQUENCING AND SCHEDULING

- A. Test, adjust, and balance the air systems before hydronic, steam, and refrigerant systems within +10% to -5% of contract requirements.

- B. The report shall be approved by the Engineer. Test and balance shall be performed prior to substantial completion.

## **PART 2 - NOT USED**

## **PART 3 - EXECUTION**

### **3.1 PROCEDURES FOR HYDRONIC SYSTEMS**

- A. Measure water flow at pumps. Use the following procedures, except for positive-displacement pumps:
  - 1. Verify impeller size by operating the pump with the discharge valve closed. Read pressure differential across the pump. Convert pressure to head and correct for differences in gage heights. Note the point on manufacturer's pump curve at zero flow and verify that the pump has the intended impeller size.
  - 2. Check system resistance. With all valves open, read pressure differential across the pump and mark pump manufacturer's head-capacity curve. Adjust pump discharge valve until indicated water flow is achieved.
  - 3. Verify pump-motor brake horsepower. Calculate the intended brake horsepower for the system based on pump manufacturer's performance data. Compare calculated brake horsepower with nameplate data on the pump motor. Report conditions where actual amperage exceeds motor nameplate amperage.
  - 4. Report flow rates that are not within plus or minus 5 percent of design.
- B. Set calibrated balancing valves, if installed, at calculated presettings.
- C. Measure flow at all stations and adjust, where necessary, to obtain first balance.
  - 1. System components that have Cv rating or an accurately cataloged flow-pressure-drop relationship may be used as a flow-indicating device.
- D. Measure flow at main balancing station and set main balancing device to achieve flow that is 5 percent greater than indicated flow.
- E. Adjust balancing stations to within specified tolerances of indicated flow rate as follows:
  - 1. Determine the balancing station with the highest percentage over indicated flow.
  - 2. Adjust each station in turn, beginning with the station with the highest percentage over indicated flow and proceeding to the station with the lowest percentage over indicated flow.
  - 3. Record settings and mark balancing devices.
- F. Measure pump flow rate and make final measurements of pump amperage, voltage, rpm, pump heads, and systems' pressures and temperatures including outdoor-air temperature.
- G. Measure the differential-pressure control valve settings existing at the conclusions of balancing.

### **3.2 MEASUREMENTS**

- A. Provide all required instrumentation to obtain proper measurements, calibrated to the tolerances specified in the referenced standards. Instruments shall be properly maintained and protected against damage.
- B. Provide instruments meeting the specifications of the referenced standards.
- C. Use only those instruments which have the maximum field measuring accuracy and are best suited to the function being measured.
- D. Apply instrument as recommended by the manufacturer.

- E. Use instruments with minimum scale and maximum subdivisions and with scale ranges proper for the value being measured.
- F. When averaging values, take a sufficient quantity of readings which will result in a repeatability error of less than 5%. When measuring a single point, repeat readings until 2 consecutive identical values are obtained.
- G. Take all readings with the eye at the level of the indicated value to prevent parallax.
- H. Use pulsation dampeners where necessary to eliminate error involved in estimating average of rapidly fluctuation readings.
- I. Take measurements in the system where best suited to the task.

### 3.3 PERFORMING TESTING, ADJUSTING, AND BALANCING

- A. Perform testing and balancing procedures on each system identified, in accordance with the detailed procedures outlined in the referenced standards. Balancing of the air systems and hydronic systems shall be achieved by adjusting the automatic controls, balancing valves, dampers, air terminal devices, and the fan/motor drives within each system.
- B. Cut insulation, ductwork, and piping for installation of test probes to the minimum extent necessary to allow adequate performance of procedures.
- C. Patch insulation, ductwork, and housings, using materials identical to those removed.
- D. Seal ducts and piping, and test for and repair leaks.
- E. Seal insulation to re-establish integrity of the vapor barrier.
- F. Adjust timing relays of environmental equipment motor reduced voltage starters to the optimum time period for the motor to come up to the maximum reduced voltage speed and then transition to the full voltage speed to prevent damage to motor, and to limit starting current spike to the lowest possible and practical.
- G. Mark equipment settings, including damper control positions, valve indicators, fan speed control levers, and similar controls and devices, to show final settings. Mark with paint or other suitable, permanent identification materials.
- H. Retest, adjust, and balance systems subsequent to significant system modifications, and resubmit test results.

### 3.4 RECORD AND REPORT DATA

- A. Record all data obtained during testing, adjusting, and balancing in accordance with, and on the forms recommended by the referenced standards, and as approved on the sample report forms.
- B. Prepare report of recommendations for correcting unsatisfactory mechanical performances when system cannot be successfully balanced.
- C. Report shall be certified and stamped by a registered professional mechanical engineer employed by the agency and licensed in the state where the work will be performed.
- D. Engineer is to provide a floor plan and test and balance contractor to include the plan in test and balance report and identify actual cfm on drawing or number the diffusers to match report.

### 3.5 DEMONSTRATION

- A. If requested, testing, adjusting, and balancing agency shall conduct any or all of the field tests in the presence of the engineer.

- B. Agency shall include a maximum of one (1) call back to the project within the one year warranty period to make additional adjustments if requested by the engineer.

END OF SECTION 23 0593



## **SECTION 23 0800 – FIRE STOPPING**

### **PART 1 - GENERAL**

#### 1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 05 01 apply to this Section.

#### 1.2 SUMMARY

- A. Furnish and install fire stopping as described in Contract Documents.

#### 1.3 QUALITY ASSURANCE

- A. Fire stopping material shall meet ASTM E814, E84 and be UL listed.

### **PART 2 - PRODUCTS**

#### 2.1 MANUFACTURED UNITS

- A. Material shall be flexible, long lasting, intumescent acrylic seal to accommodate vibration and building movement.
- B. Caulk simple penetrations with gaps of 1/4" or less with:
  - 1. Dow Corning Fire Stop Sealant
  - 2. Pensil 300
- C. Caulk multiple penetrations and/or penetrations with gaps in excess of 1/4" with:
  - 1. Dow Corning Fire Stop Foam
  - 2. Pensil 200
  - 3. IPC flame safe FS-1900
  - 4. Tremco "Tremstop 1A"

### **PART 3 - EXECUTION**

#### 3.1 INSTALLATION

- A. Follow manufacturer's installation instructions explicitly.
- B. Seal penetrations of ductwork, piping, and other mechanical equipment through one-hour and two-hour rated partitions as shown on Architectural and Mechanical Drawings.
- C. Install fire stopping material on clean surfaces to assure adherence.

END OF SECTION 23 0800

## SECTION 23 2113 - HYDRONIC PIPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 05 01 apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes piping, special-duty valves, makeup water for these systems; blowdown drain lines; and condensate drain piping.

#### 1.3 SUBMITTALS

- A. Product Data: For each type of special-duty valve indicated. Include flow and pressure drop curves based on manufacturer's testing for diverting fittings, calibrated balancing valves, and automatic flow-control valves.
- B. Shop Drawings: Detail fabrication of pipe anchors, hangers, special pipe support assemblies, alignment guides, expansion joints and loops, and their attachment to the building structure. Detail location of anchors, alignment guides, and expansion joints and loops.
- C. Welding Certificates: Copies of certificates for welding procedures and personnel.
- D. Field Test Reports: Written reports of tests specified in Part 3 of this Section. Include the following:
  - 1. Test procedures used.
  - 2. Test results that comply with requirements.
  - 3. Failed test results and corrective action taken to achieve requirements.
- E. Maintenance Data: For hydronic specialties and special-duty valves to include in maintenance manuals specified in Division 23.
- F. Water Analysis: Submit a copy of the water analysis to illustrate water quality available at Project site.

#### 1.4 QUALITY ASSURANCE

- A. Welding: Qualify processes and operators according to the ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications."
- B. ASME Compliance: Comply with ASME B31.9, "Building Services Piping," for materials, products, and installation. Safety valves and pressure vessels shall bear the appropriate ASME label. Fabricate and stamp air separators and expansion tanks to comply with the ASME Boiler and Pressure Vessel Code, Section VIII, Division 1.

#### 1.5 COORDINATION

- A. Coordinate layout and installation of hydronic piping and suspension system components with other construction, including light fixtures, HVAC equipment, fire-suppression-system components, and partition assemblies.
- B. Coordinate pipe sleeve installations for foundation wall penetrations.
- C. Coordinate piping installation with roof curbs, equipment supports, and roof penetrations.

- D. Coordinate pipe fitting pressure classes with products specified in related Sections.
- E. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into base. Concrete, reinforcement, and formwork requirements are specified in Division 3 Sections.
- F. Coordinate installation of pipe sleeves for penetrations through exterior walls and floor assemblies. Coordinate with requirements for firestopping specified in Division 7 Section "Through-Penetration Firestop Systems" for fire and smoke wall and floor assemblies.

#### 1.6 EXTRA MATERIALS

- A. Water Treatment Chemicals: Furnish sufficient chemicals for initial system startup and for preventive maintenance for one year from date of Substantial Completion.

### **PART 2 - PRODUCTS**

#### 2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Grooved Mechanical-Joint Fittings and Couplings:
    - a. Central Sprinkler Company; Central Grooved Piping Products.
    - b. Grinnell Mechanical Products.
    - c. Victaulic Company of America.
  - 2. Calibrated Balancing Valves:
    - a. Armstrong Pumps, Inc.
    - b. Flow Design, Inc.
    - c. Gerand Engineering Company.
    - d. Griswold Controls.
    - e. ITT Bell & Gossett; ITT Fluid Technology Corp.
    - f. Taco, Inc.
  - 3. Automatic Flow-Control Valves:
    - a. Flow Design, Inc.
    - b. Griswold Controls.

#### 2.2 PIPING MATERIALS

- A. General: Refer to Part 3 "Piping Applications" Article for applications of pipe and fitting materials.

#### 2.3 STEEL PIPE AND FITTINGS

- A. Steel Pipe, NPS 2 and Smaller: ASTM A 53, Type S (seamless) or Type F (furnace-butt welded), Grade B, Schedule 40, black steel, plain ends.
- B. Steel Pipe, NPS 2-1/2 through NPS 12: ASTM A 53, Type E (electric-resistance welded), Grade B, Schedule 40, black steel, plain ends.
- C. Steel Pipe, NPS 14 through NPS 18: ASTM A 53, Type E (electric-resistance welded) or Type S (seamless), Grade B, Schedule 30, black steel, plain ends.
- D. Steel Pipe, NPS 20: ASTM A 53, Type E (electric-resistance welded) or Type S (seamless), Grade B, Schedule 20, black steel, plain ends.
  - 1. Steel Pipe Nipples: ASTM A 733, made of ASTM A 53, Schedule 40, black steel; seamless for NPS 2 and smaller and electric-resistance welded for NPS 2-1/2 and larger.

- E. Cast-Iron Pipe Flanges and Flanged Fittings: ASME B16.1, Classes 25, 125, and 250; raised ground face, and bolt holes spot faced.
- F. Wrought-Steel Fittings: ASTM A 234/A 234M, wall thickness to match adjoining pipe.
- G. Wrought Cast- and Forged-Steel Flanges and Flanged Fittings: ASME B16.5, including bolts, nuts, and gaskets of the following material group, end connections, and facings:
  1. Material Group: 1.1.
  2. End Connections: Butt welding.
  3. Facings: Raised face.
- H. Grooved Mechanical-Joint Fittings: ASTM A 536, Grade 65-45-12 ductile iron; ASTM A 47, Grade 32510 malleable iron; ASTM A 53, Type F, E, or S, Grade B fabricated steel; or ASTM A 106, Grade B steel fittings with grooves or shoulders designed to accept grooved end couplings.
- I. Grooved Mechanical-Joint Couplings: Ductile- or malleable-iron housing and synthetic rubber gasket of central cavity pressure-responsive design; with nuts, bolts, locking pin, locking toggle, or lugs to secure grooved pipe and fittings.
- J. Flexible Connectors: Stainless-steel bellows with woven, flexible, bronze, wire-reinforcing protective jacket; 150-psig minimum working pressure and 250 deg F maximum operating temperature. Connectors shall have flanged or threaded-end connections to match equipment connected and shall be capable of 3/4-inch misalignment.
- K. Spherical, Rubber, Flexible Connectors: Fiber-reinforced rubber body with steel flanges drilled to align with Classes 150 and 300 steel flanges; operating temperatures up to 250 deg F and pressures up to 150 psig.
- L. Packed, Slip, Expansion Joints: 150-psig minimum working pressure, steel pipe fitting consisting of telescoping body and slip-pipe sections, packing ring, packing, limit rods, flanged ends, and chrome-plated finish on slip-pipe telescoping section.
- M. Welding Materials: Comply with Section II, Part C, of the ASME Boiler and Pressure Vessel Code for welding materials appropriate for wall thickness and for chemical analysis of pipe being welded.
- N. Gasket Material: Thickness, material, and type suitable for fluid to be handled; and design temperatures and pressures.

## 2.4 VALVES

- A. Gate, globe, check, ball, and butterfly valves are specified in Division 15 Section "Valves."
- B. Refer to Part 3 "Valve Applications" Article for applications of each valve.
- C. Calibrated Balancing Valves, NPS 2 and Smaller: Bronze body, ball type, 125-psig working pressure, 250 deg F maximum operating temperature, and having threaded ends. Valves shall have calibrated orifice or venturi, connections for portable differential pressure meter with integral seals, and be equipped with a memory stop to retain set position.
- D. Safety Valves: Diaphragm-operated, bronze or brass body with brass and rubber, wetted, internal working parts; shall suit system pressure and heat capacity and shall comply with the ASME Boiler and Pressure Vessel Code, Section IV.
- E. Automatic Flow-Control Valves: Gray-iron body, factory set to maintain constant flow with plus or minus 5 percent over system pressure fluctuations, and equipped with a readout kit including flow meter, probes, hoses, flow charts, and carrying case. Each valve shall have an

identification tag attached by chain, and be factory marked with the zone identification, valve number, and flow rate. Valve shall be line size and one of the following designs:

1. Gray-iron or brass body, designed for 175 psig at 200 deg F with stainless-steel piston and spring.
2. Brass or ferrous-metal body, designed for 300 psig at 250 deg F with corrosion-resistant, tamperproof, self-cleaning, piston-spring assembly easily removable for inspection or replacement.
3. Combination assemblies, including bronze ball valve and brass alloy control valve, with stainless-steel piston and spring, fitted with pressure and temperature test valves, and designed for 300 psig at 250 deg F.

## 2.5 HYDRONIC SPECIALTIES

- A. Manual Air Vent: Bronze body and nonferrous internal parts; 150-psig working pressure; 225 deg F operating temperature; manually operated with screwdriver or thumbscrew; with NPS 1/8 discharge connection and NPS 1/2 inlet connection.
- B. Automatic Air Vent: Designed to vent automatically with float principle; bronze body and nonferrous internal parts; 150-psig working pressure; 240 deg F operating temperature; with NPS 1/4 discharge connection and NPS 1/2 inlet connection.
- C. Expansion Tanks: Welded carbon steel, rated for 125-psig working pressure and 375 deg F maximum operating temperature. Separate air charge from system water to maintain design expansion capacity by a flexible bladder securely sealed into tank. Include drain fitting and taps for pressure gage and air-charging fitting. Support vertical tanks with steel legs or base; support horizontal tanks with steel saddles. Factory fabricate and test tank with taps and supports installed and labeled according to the ASME Boiler and Pressure Vessel Code, Section VIII, Division 1.
- D. In-Line Air Separators: One-piece cast iron with an integral weir designed to decelerate system flow to maximize air separation at a working pressure up to 175 psig and liquid temperature up to 300 deg F.
- E. Bypass Chemical Feeder: Welded steel construction; 125-psig working pressure; 5-gal. capacity; with fill funnel and inlet, outlet, and drain valves.
  1. Chemicals: Specially formulated, based on analysis of makeup water, to prevent accumulation of scale and corrosion in piping and connected equipment.
- F. Y-Pattern Strainers: 125-psig working pressure; cast-iron body (ASTM A 126, Class B), flanged ends for NPS 2-1/2 and larger, threaded connections for NPS 2 and smaller, bolted cover, perforated stainless-steel basket, and bottom drain connection.
- G. Basket Strainers: 125-psig working pressure; high-tensile cast-iron body (ASTM A 126, Class B), flanged-end connections, bolted cover, perforated stainless-steel basket, and bottom drain connection.
- H. T-Pattern Strainers: 750-psig working pressure; ductile-iron or malleable-iron body, grooved-end connections, stainless-steel basket with 57 percent free area; removable access coupling and end cap for strainer maintenance.
- I. Flexible Connectors: Stainless-steel bellows with woven, flexible, bronze, wire-reinforcing protective jacket; 150-psig minimum working pressure and 250 deg F maximum operating temperature. Connectors shall have flanged- or threaded-end connections to match equipment connected and shall be capable of 3/4-inch misalignment.
- J. Spherical, Rubber, Flexible Connectors: Fiber-reinforced rubber body with steel flanges drilled to align with Classes 150 and 300 steel flanges; operating temperatures up to 250 deg F and pressures up to 150 psig.

- K. Packed, Slip, Expansion Joints: 150-psig minimum working pressure, steel pipe fitting consisting of telescoping body and slip-pipe sections, packing ring, packing, limit rods, flanged ends, and chrome-plated finish on slip-pipe telescoping section.

### **PART 3 - EXECUTION**

#### **3.1 VALVE APPLICATIONS**

- A. General-Duty Valve Applications: Unless otherwise indicated, use the following valve types:
  - 1. Shutoff Duty: Gate, ball, and butterfly valves.
  - 2. Throttling Duty: Globe, ball, and butterfly valves.
- B. Install shutoff duty valves at each branch connection to supply mains, at supply connection to each piece of equipment, unless only one piece of equipment is connected in the branch line. Install throttling duty valves at each branch connection to return mains, at return connections to each piece of equipment, and elsewhere as indicated.
- C. Install calibrated balancing valves in the return water line of each heating or cooling element and elsewhere as required to facilitate system balancing.
- D. Install check valves at each pump discharge and elsewhere as required to control flow direction.

#### **3.2 PIPING INSTALLATIONS**

- A. Install groups of pipes parallel to each other, spaced to permit applying insulation and servicing of valves.
- B. Install drains, consisting of a tee fitting, NPS 3/4 ball valve, and short NPS 3/4 threaded nipple with cap, at low points in piping system mains and elsewhere as required for system drainage.
- C. Install piping at a uniform grade of 0.2 percent upward in direction of flow.
- D. Reduce pipe sizes using eccentric reducer fitting installed with level side up.
- E. Unless otherwise indicated, install branch connections to mains using tee fittings in main pipe, with the takeoff coming out the bottom of the main pipe. For up-feed risers, install the takeoff coming out the top of the main pipe.
- F. Install strainers on supply side of each control valve, pressure-reducing valve, solenoid valve, in-line pump, and elsewhere as indicated. Install NPS 3/4 nipple and ball valve in blowdown connection of strainers NPS 2 and larger. Match size of strainer blowoff connection for strainers smaller than NPS 2.
- G. Anchor piping for proper direction of expansion and contraction.

#### **3.3 HANGERS AND SUPPORTS**

- A. Hanger, support, and anchor devices are specified in Division 15 Section "Hangers and Supports." Comply with requirements below for maximum spacing of supports.
- B. Install the following pipe attachments:
  - 1. Adjustable steel clevis hangers for individual horizontal piping less than 20 feet long.
  - 2. Adjustable roller hangers and spring hangers for individual horizontal piping 20 feet or longer. cal runs at roof, at each floor, and at 10-foot intervals between floors.

### 3.4 PIPE JOINT CONSTRUCTION

- A. Refer to Division 15 Section "Basic Mechanical Materials and Methods" for joint construction requirements for soldered and brazed joints in copper tubing; threaded, welded, and flanged joints in steel piping; and solvent-welded joints for PVC and CPVC piping.

### 3.5 HYDRONIC SPECIALTIES INSTALLATION

- A. Install manual air vents at high points in piping, at heat-transfer coils, and elsewhere as required for system air venting.
- B. Install automatic air vents in mechanical equipment rooms only at high points of system piping, at heat-transfer coils, and elsewhere as required for system air venting.
- C. Install bypass chemical feeders in each hydronic system where indicated, in upright position with top of funnel not more than 48 inches above floor. Install feeder in bypass line, off main, using globe valves on each side of feeder and in the main between bypass connections. Pipe drain, with ball valve, to nearest equipment drain.
- D. Install expansion tanks on floor. Vent and purge air from hydronic system, and ensure tank is properly charged with air to suit system design requirements.

### 3.6 TERMINAL EQUIPMENT CONNECTIONS

- A. Size for supply and return piping connections shall be same as for equipment connections.
- B. Install control valves in accessible locations close to connected equipment.
- C. Install bypass piping with globe valve around control valve. If multiple, parallel control valves are installed, only one bypass is required.
- D. Install ports for pressure and temperature gages at coil inlet connections.

### 3.7 CHEMICAL TREATMENT

- A. Perform an analysis of supply water to determine the type and quantities of chemical treatment needed to keep system free of scale, corrosion, and fouling, and to sustain the following water characteristics:
- B. Fill system and perform initial chemical treatment.

### 3.8 FIELD QUALITY CONTROL

- A. Prepare hydronic piping according to ASME B31.9 and as follows:
  1. Leave joints, including welds, uninsulated and exposed for examination during test.
  2. Provide temporary restraints for expansion joints that cannot sustain reactions due to test pressure. If temporary restraints are impractical, isolate expansion joints from testing.
  3. Flush system with clean water. Clean strainers.
  4. Isolate equipment from piping. If a valve is used to isolate equipment, its closure shall be capable of sealing against test pressure without damage to valve. Install blinds in flanged joints to isolate equipment.
  5. Install safety valve, set at a pressure no more than one-third higher than test pressure, to protect against damage by expanding liquid or other source of overpressure during test.
- B. Perform the following tests on hydronic piping:
  1. Use ambient temperature water as a testing medium unless there is risk of damage due to freezing. Another liquid that is safe for workers and compatible with piping may be used.

2. While filling system, use vents installed at high points of system to release trapped air. Use drains installed at low points for complete draining of liquid.
3. Check expansion tanks to determine that they are not air bound and that system is full of water.
4. Subject piping system to hydrostatic test pressure that is not less than 1.5 times the design pressure. Test pressure shall not exceed maximum pressure for any vessel, pump, valve, or other component in system under test. Verify that stress due to pressure at bottom of vertical runs does not exceed either 90 percent of specified minimum yield strength or 1.7 times "SE" value in Appendix A of ASME B31.9, "Building Services Piping."
5. After hydrostatic test pressure has been applied for at least 10 minutes, examine piping, joints, and connections for leakage. Eliminate leaks by tightening, repairing, or replacing components and repeat hydrostatic test until there are no leaks.
6. Prepare written report of testing.

### 3.9 ADJUSTING

- A. Mark calibrated nameplates of pump discharge valves after hydronic system balancing has been completed, to permanently indicate final balanced position.
- B. Perform these adjustments before operating the system:
  1. Open valves to fully open position. Close coil bypass valves.
  2. Check pump for proper direction of rotation.
  3. Set automatic fill valves for required system pressure.
  4. Check air vents at high points of system and determine if all are installed and operating freely (automatic type), or bleed air completely (manual type).
  5. Set temperature controls so all coils are calling for full flow.
  6. Check operation of automatic bypass valves.
  7. Check and set operating temperatures of boilers, chillers, and cooling towers to design requirements.
  8. Lubricate motors and bearings.

### 3.10 CLEANING

- A. Flush hydronic piping systems with clean water. Remove and clean or replace strainer screens. After cleaning and flushing hydronic piping systems, but before balancing, remove disposable fine-mesh strainers in pump suction diffusers.

END OF SECTION 23 2113



**SECTION 23 2118 – BACKFLOW PREVENTER VALVE**

**PART 1 - GENERAL**

1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 05 01 apply to this Section.

1.2 SUMMARY

- A. Furnish and install a backflow preventer valve as described in Contract Documents.

**PART 2 - PRODUCTS**

2.1 MANUFACTURED UNITS

- A. Designed to provide separation of radiant hot water heating system water from domestic cold water supply in accordance with Code.
  - 1. Rated flow at 30 psi pressure drop rated for 175 psi inlet pressure and 140 deg. F maximum operating temperature.
  - 2. Brass body construction with 3/4 inch NPT connections.
- B. Approved Manufacturers:
  - 1. Beeco 12
  - 2. Watts 900
  - 3. Equal by Febco
  - 4. Equal by Conbraco

**PART 3 - EXECUTION**

3.1 INSTALLATION

- A. Furnish and install a drain cup and pipe the waste line to the nearest floor drain or floor sink.

END OF SECTION 23 2118

## **SECTION 23 2123 – CIRCULATING PUMPS AND ACCESSORIES**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 22 05 01 apply to this Section.

#### **1.2 SUMMARY**

- A. Furnish and install circulating water pumps and accessories as described in the Contract Documents.

### **PART 2 - PRODUCTS**

#### **2.1 TRIPLE DUTY VALVES**

- A. Place on each pump discharge. Valve serves as a non-slam check valve with spring loaded disk check, calibrated adjustable and lockable balance valve and full shutoff valve with memory stop. Valve shall be back-seated so as to allow repacking under full line pressure.
- B. Cast iron body
- C. Bronze disk and seat with stainless steel stems and springs.
- D. Teflon packing
- E. Maximum valve working pressure of 175 psig and a maximum operating temperature of 300 deg. F.
- F. Approved Manufacturers:
  - 1. Bell & Gossett
  - 2. Armstrong

#### **2.2 EXPANSION JOINT PUMP CONNECTORS**

- A. Precision machine molded neoprene and nylon construction internal reinforced by means of steel wire.
- B. Cadmium steel floating flanges tapped to mate with 150# ASA companion flanges.
- C. Capable of operating at a temperature of 20 deg. F. thru 220 deg. F. and at a pressure ranging from 10" HG vacuum thru 150 psi working pressure.
- D. Capable of 15 deg. angular deflection.
- E. Twin quiet-sphere design with control rods.
- F. Approved Manufacturers:
  - 1. Vibration Mountings & Controls, Inc.
  - 2. Metraflex

#### **2.3 IN-LINE CIRCULATORS**

- A. Steel fitted with ceramic seal, spring coupling, and 1750-rpm, drip-proof motor with overload protection.

- B. Substantially supported in piping with a full-size leg to floor.
- C. Pumps to be sized for 40% Glycol.
- D. Approved Manufacturers:
  - 1. Bell & Gossett
  - 2. Armstrong
  - 3. Taco

### **PART 3 - EXECUTION**

#### **3.1 INSTALLATION**

- A. Install equipment in accordance with manufacturers instructions.
- B. Align pump and motor shafts in accordance with manufacturers requirements before starting equipment. Provide report in the M&O manual regarding pump alignment.
- C. Remove start-up filter screen on suction diffuser after system has been cleaned and flushed. Leave main filter screen in place.

END OF SECTION 23 2123

## **SECTION 23 2125 - CLEANING AND FLUSHING WATER CIRCULATING SYSTEMS**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 05 01 apply to this Section.

#### **1.2 SUMMARY**

- A. Furnish labor and materials to thoroughly clean water circulating systems as described in Contract Documents.
- B. Mechanical contractor shall procure the services of an independent treatment contractor as described in this specification.

#### **1.3 QUALITY ASSURANCE**

- A. System Additives: This Contractor shall not add any water treatment chemicals or "stop-leak" compounds to the system.

### **PART 2 - EXECUTION**

#### **2.1 FIELD QUALITY ASSURANCE**

- A. Water circulating systems for project shall be thoroughly cleaned before placing in operation to rid system of dirt, piping compound, mill scale, oil, and other materials foreign to water being circulated.
- B. During construction extreme care shall be exercised to prevent dirt and other foreign matter from entering pipe or other parts of system. Pipe stored on project shall have open ends capped and equipment shall have openings fully protected. Before erection, each piece of pipe, fittings, or valve shall be visually examined and dirt removed.
- C. Hydronic Heat Pump Closed Loop Cleaning
  1. Prior to any introduction of fluids to the closed loop system the Mechanical Contractor shall close isolation valves at each heat pump and open the bypass valve to prevent flow through the strainer, flow control device and heat pump during the initial flushing and subsequent cleaning. The side stream filter bag shall be removed during the initial flushing process.
  2. The Mechanical Contractor shall fill each hydronic system with clean fresh water prior to cleaning and thoroughly leak check system piping. A cleaning and passivating agent supplied by the Chemical Treatment Contractor shall be added to the system at the direction of the Treatment Contractor during the leak check process to minimize initial corrosion. If the system is filled multiple times during the leak check and repair process the Mechanical Contractor shall coordinate with the Treatment Contractor to maintain this initial protection. The Treatment Contractor is responsible for providing chemical for up to two refills of the system. If additional chemical is required due to multiple refillings the Mechanical Contractor shall be responsible for the additional time and chemical.
  3. Following leak check the closed system shall be flushed by the Mechanical Contractor until the leaving water runs clear. All primary runs shall be flushed at their ends to obtain maximum sweep of debris from the system. The inlet screens on the circulating pumps must be kept clear during this initial cleaning process and inspected following cleaning. When flushing is complete the system is to be left full.

4. Prior to flushing the Mechanical Contractor shall coordinate with Treatment Contractor so that the Treatment Contractor can be available immediately following flush and final refill to add cleaning chemical within 4 hours to prevent initial corrosion.
5. Following initial flushing the Chemical Treatment Contractor shall refill all systems with cleaning and passivating agents raising the PH to a minimum of 10, circulate and flush until thoroughly clean. All primary piping runs shall be flushed at the ends during this cleaning process. When boiler operation is available the loop temperature should be raised to 110 to 120° to accelerate cleaning. Cleaning with availability of boiler operation should be anticipated to last 7 to 10 days or longer depending on initial loop conditions. If boiler operation is unavailable loop cleaning duration should be expected to double. The Chemical Treatment Contractor shall verify and adjust cleaning chemistry, and inspect side stream filter bags at a minimum of every two days, exception for weekends. Filter bags shall be changed as required during this cleaning process. Cleaning shall continue until these bags no longer show signs of debris.
6. Following cleaning process the Treatment Contractor shall close the bypass valves at each heat pump and open isolation valves for normal operation and check for leaks of local piping connections. Any leaks found shall be referred to the Mechanical Contractor for repair. The bypass valve handle shall be removed and tied to the valve. The system shall then be charged with final operating chemical to control long term corrosion and a clean bag filter shall be installed in the system.
7. The Treatment Contractor shall provide final inspection report for inclusion in the Operation and Maintenance Manual. Additionally the Treatment Contractor shall take loop samples approximately 12 months following completion, add or adjust chemical as required and provide a post construction report to the owner prior to warranty closeout. Chemical required is the responsibility of the Treatment Contractor.

END OF SECTION 23 2125

## **SECTION 23 2510 – GLYCOL SYSTEM & GLYCOL FEED PUMP**

### **PART 1 - GENERAL**

#### 1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 05 01 apply to this Section.

#### 1.2 SUMMARY

- A. Furnish and install glycol system as described in Contract Documents.

### **PART 2 - PRODUCTS**

#### 2.1 MATERIALS

- A. Hot water system shall be a 40% glycol and water system. Furnish and install a manual glycol pump and fill system and fill the chiller, coils and piping system with the solution.
- B. Heat Exchange, pumps, and piping have been sized to handle the 40% solution.
- C. Glycol shall be of a permanent type with rust inhibitors and shall have an identifying odor and color.
  - 1. Approved Manufacturer:
    - a. Dowtherm Type SR-1.

#### 2.2 HYDRONIC MINI SYSTEM FEEDER

- A. Hydronic system feeder shall be AXIOM INDUSTRIES LTD. Model MF200.
- B. System shall include 25 litre (6.6 U.S. gallon) storage/mixing tank with molded-in level gauge, 125 mm (5") fill/access opening and cover; pump suction hose with inlet strainer and check valve; pressure pump with fuse protection; low fluid level pump cut-out float switch; manual diverter valve for purging air and agitating contents of storage tank; pressure switch with snubber, each individually adjustable from 70 kPa (10 psig) to 170 kPa (25 psig) cut-out pressure; factory cut-out pressure set to 115 kPa (17psig); and liquid filled pressure gauge.
- C. Unit to be c/w UL listed and fused power supply adapter with LED power indicator light, 115/60/1 to 24 VDC 50 watts AC, supplied loose for field installation.
- D. Feeder shall be compatible with glycol solutions of up to 50% concentration. Pump shall be capable of running dry without damage. Unit shall be completely assembled.
- E. RIA10-1-SAA – Low level Alarm Panel c/w Remote Monitoring Dry Contacts and Selectable Audible Alarm

### **PART 3 - EXECUTION**

- 3.1 Provide warning stickers on equipment and piping indicating the solution in system.

END OF SECTION 23 2510

## **SECTION 23 5719 – PLATE AND FRAME HEAT EXCHANGERS**

### **PART 1 - GENERAL**

#### 1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 05 01 apply to this Section.

#### 1.2 SUMMARY

- A. Furnish and install heat exchanger as described in Contract Documents.

#### 1.3 QUALITY ASSURANCE

- A. Construction shall conform to latest ASME Code for unfired pressure vessels.

### **PART 2 - PRODUCTS**

#### 2.1 MANUFACTURED UNITS

- A. Plate type heat exchangers with maximum pressure drop through heat exchanger of 5 psi.
- B. Framework, pressure plate and fixed plate shall be of heavy carbon steel painted with epoxy enamel.
- C. The heat exchanger corrugated channel plates shall be Type 304 stainless steel with nitrile gaskets. The gasket pattern on each channel plate distributes the fluid flow to alternate plate flow channels in the plate pack creating 100% counterflow resulting in high transfer effectiveness.
- D. Approved Manufacturers:
  - 1. Bell & Gossett
  - 2. Alfa-Laval

END OF SECTION 23 5719

END OF DIVISION 23