DOCUMENT 00 91 13

Addendum Number Two

DATE: April 9, 2021

PROJECT: DPW #19227

Reed Gym HVAC Upgrade Idaho State University

Pocatello, ID

ARCHITECT'S

PROJECT NO.: 18467

OWNER: Division of Public Works

P.O. Box 83720 Boise, ID 83720-0072

ARCHITECT: Myers Anderson Architects, PLLC

122 South Main Street, Suite 1

Pocatello, Idaho 83204

TO: Prospective Bidders

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated March 2021.

Acknowledge receipt of this Addendum in the space provided in the Bid Form. Failure to do so may disqualify the Bidder.

This Addendum consists of two (2) pages plus attachments. Total: five (5) pages.

General

- 1. See attached Prebid Conference Attendance Sheet
- 2. See attached Plan Register.
- 3. Contractor staging will be provided in the Reed Gym parking area adjacent to the tennis courts. 2 Parking stalls at main entrance on north east side will also be provided for contractor staging.
- 4. Coordination with ISU will be required when accessing work areas. Phasing will be required to be coordinated with ISU as the entire facility will not be turned over tot the contractor all at one time.
- 5. Corridors shall remain accessible at all times.
- 6. Wall thickness at new door 102A is anticipated to be 12" thick based on the original building drawings.
- 7. Insulated Glass shall be as follows:
 - a. INSULATING GLASS PRODUCTS
 - i. Insulating Glass Manufacturers:
 - 1. AGC Flat Glass North America, Inc.
 - 2. Guardian Industries Corp.; SunGuard
 - 3. Oldcastle Building Envelope
 - 4. Pilkington North America

Architecture • Interiors • Planning • Preservation

PPG Industries, Inc

5.

- 6. Viracon, Inc
- 7. Substitutions: Section 01 60 00 - Product Requirements
 - ii. Insulating Glass: ASTM E2190 certified by Insulating Glass Certification Council and Insulating Glass Manufacturers Alliance; with glass elastomer, glass to mastic silicone, and sealant edge seal; place reflective film within unit; purge interpane space with dry hermetic air
 - 1. Total Unit Thickness: 1 inch
 - 2. Insulating Glass Unit Edge Seal Construction: Aluminum or Stainless steel, thermally broken, bent and soldered or bent and spot welded mitered and spigoted corners
 - 3. Insulating Glass Unit Edge Seal Material: clear color

Specifications

1. See attached Specification Section 23 21 85 Condensate Return Pump.

MECHANICAL DEHUMIDIFICATION UNITS: Seresco, Innovent.

Prior Approvals

| - 1-1- | |
|----------|--|
| 23 05 14 | VARIABLE FREQUENCY DRIVE SYSTEM: Danfoss. |
| 23 05 48 | SEISMIC AND VIBRATION: Kinectics. |
| 23 21 12 | STEAM AND CONDENSATE PIPE AND ACC: Spirax Sarco, Milioco. |
| 23 21 16 | HW HEATING SPEC: Armstrong, Engineered Flexible Prod., Weiss Inst., Nexus |
| 23 21 23 | CIRCULATING PUMPS AND ACC.: Taco, IMI Flow Design, Twin City Hose. |
| 23 21 85 | CONDENSATE RETURN PUMP: Skidmore Pumps, Armstrong Int. |
| 23 34 00 | EXHAUST FANS: Broan, Carnes. |
| 23 37 13 | AIR INLETS & OUTLETS: Potlorff, Twin City, Air-Rite Mfg., Tuttle & Bailey, Soler & Palau |
| 23 65 33 | FLUID COOLER: Guntner. |
| 23 81 29 | VARIABLE REFRIGERANT FLOW HVAC SYSTEMS: Daikin, Mitsubishi. |
| | |

Attachments

23 84 16

Prebid Conference Attendance Sheet Plan Register Specification Section 23 21 85 Condensate Return Pump

End of Addendum No. 2

PREBID CONFERENCE ATTENDANCE SHEET DPW #19227 Reed Gym HVAC Upgrade, Idaho State University, Pocatello, ID

| Name | Company | Address | Phone/Fax |
|-------------------|----------------|--|----------------|
| RICHARD COLFASON | Myers Anderson | 122 S. Main St., Suite 1 | 208-232-3741 |
| | Architects | Pocatello, ID 83204 | 208-232-3782 |
| Mason Lewis | Lewis Corp | 18336 W. HURLLINED | 2021-1882-1005 |
| Charles Anderson | Midgley-Hubor | 6230 S. Heritogo Lame Suite 3 Idaho Falls | 208-541-2400 |
| JASON Curbos | Harris | | 708-201-1341 |
| Bentley Gunderson | JM Mech | , | 435 770 9165 |
| SPENE ZAMBRIT | 12.0 | 7 2/7 | 208-631-8424 |
| Gart Clark | Cr Clark | | 298 681 1257 |
| Payle Roboils | Harper Coust. | | 204 360 525) |
| Camejon Cardan | YMCZNC. | | 208 871 4051 |
| Kyle Anderson | BSS Boilor Tue | | 208-524-1737 |
| Cowis Burnheem | | | 208 282-3555 |
| JEREMY FREEMAN | ISU-Facilities | 15h | 208 282-3555 |
| Took ADAMS | 1SU-FACILITIES | 180 | 208-540-0906 |
| Dwayne Sudweeks | B5A | 1355 E. Center 100.10 83201 | 208-233-0501 |
| | | | |
| | | , | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | , | |
| | | | |
| | | | |

PLAN REGISTER Project: DPW #19227 Reed Gym HVAC Upgrade, ISU

Location: Pocatello, ID

Project No. 18467 Plan Deposit: \$100 Prebid Date/Time: March 31, 2021 at 3:00 pm

Bid Date/Time: April 15, 2021 at 2:00 pm

| # | Plan Holder | Address | Phone | Role | Plan Given | Returned | Check |
|---|--------------------------------|---|--------------|------------|------------|----------|-------|
| 1 | Division of Public Works - FR | 611 Wilson Ave, Suite 1, Pocatello, ID 83201 | 208-417-9233 | Owner | | | |
| 2 | Idaho State University | Physical Plant Box 8137, Pocatello, ID 83209 | 208-282-1784 | Agency | 3/19/2021 | | |
| 3 | | | | | | | |
| 4 | J&S Construction | 739 North 3700 East, Rigby, ID 83442 | 208-754-8684 | General | 3/23/2021 | | Х |
| 5 | Allied Electrical Construction | 770 North Mink Creek Road, Pocatello, ID 83204 | 208-705-0240 | Sub | 3/19/2021 | | |
| | Myers Anderson Architects | 122 South Main, Ste. 1, Pocatello. ID 83204 | 208-232-3741 | Architect | 3/19/2021 | | |
| D | Engineered Systems Associates | 1355 East Center Street, Pocatello, ID 83201 | 208-233-0501 | Consultant | 3/19/2021 | | Х |
| D | Musgrove Engineering | 645 W 25th Street, Idaho Falls, ID 83402 | 208-523-2864 | Consultant | 3/19/2021 | | Х |
| D | Associated General Contractors | 1649 W Shoreline Dr, Suite 100, Boise, ID 83702 | 208-344-2531 | Plan Room | 3/19/2021 | | Х |
| D | ARC Document Solutions | 2700 W Idaho Street, Boise, ID 83702 | 208-342-4141 | Plan Room | 3/19/2021 | | |
| D | Blueprint Specialties | 6205 W Overland Road, Boise, ID 83709 | 208-377-0294 | Plan Room | 3/19/2021 | | Х |
| D | Dodge Data & Analytics | 2860 S State Hwy 161, Suite 160 #501, Grand Prairie, TX 75052 | 413-551-3196 | Plan Room | 3/19/2021 | | Х |
| D | Spokane Regional Plan Center | 209 N Havana, Spokane, WA 99202 | 509-328-9600 | Plan Room | 3/23/2021 | | Х |
| D | Harper Construction | 175 N 900 W, Blackfoot, ID 83221 | 208-684-5117 | General | 3/27/2021 | | Х |
| D | Idaho Electric | 750 Samuel Street, Pocatello, ID 83204 | 208-251-0373 | Sub | 4/5/2021 | | Х |
| D | | | | | | | |

SECTION 23 21 85

CONDENSATE RETURN PUMP

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, and Section 23 0501 apply to this Section.

1.2 SUMMARY

A. Furnish and install a condensate return pump as described in Contract Documents.

PART 2 - PRODUCTS

2.1 MANUFACTURED UNITS

- A. Duplex packaged unit with heavy cast iron receiver with supports and two pumps all piped on one base.
- B. Each pump shall have a capacity as shown and shall be operated from float switches, magnetic starter, and alternator provided with the pump and mounted on pump assembly.
- C. Approved Manufacturers:
 - 1. Federal
 - 2. Roth
 - 3. Pacific

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install check valve and gate valve on pump discharge.
- B. Run vent line from receivers and terminate as high as possible with return bends.

END OF SECTION 23 21 85