

COMPANY, INC. 431 W. McGregor Dr., Boise, ID 83705 P: 208.384.0800 I F: 208.345.5323 I www.cmcompany.com

June 3, 2021

#### ADDENDUM NO. 1

#### PROJECT:

Chubbuck Police H.Q. & Animal Shelter 5160 Yellowstone Avenue Chubbuck, ID 83202

#### Owner:

City of Chubbuck 5160 Yellowstone Chubbuck, ID 83202

#### **Architect:**

Lombard Conrad Architects 1221 Shoreline Ln. Boise, Idaho 83702

#### **Architect:**

Myers Anderson Architects, PLLC 122 South Main St., Suite 1 Pocatello, Idaho 83204

#### **Construction Manager:**

CM Company Inc. 431 West McGregor Drive Boise, Idaho 83705

#### **Notice to Bidders:**

The following addenda applies to the Project Specifications and/or Drawings for this project and shall be a part of the Contract Documents. Receipt of this Addendum must be acknowledged and dated on your bid proposals.

#### **BIDDING:**

Submit sealed bids to Chubbuck City Hall 5160 Yellowstone Avenue, Chubbuck, Idaho 83202 by **Tuesday**, **June 8**<sup>th</sup>. **2021 2:00 PM local time**.

#### **Bid Proposal Forms – Scope Clarifications:**

#### Remove the following to Bid Package #03 Building Demolition:

• Remove portion of perimeter walls as shown for new storefront is **NOT** included in this bid package.

#### Add the following to Bid Package #4 Earthwork:

- Excavation and removal of spoils for structural footings at Police H.Q. per 102 & 112/S3.0, including backfill and compaction is included in this bid package.
- Excavation, base and backfill for new window wells.

#### Add the following to Bid Package #08 Building Concrete & Foundations:

- Concrete wall infill at existing window wells.
- Window well base, top and retaining walls at new window wells including saw cutting of existing wall for new windows (coordinate with Glazing Contractor).

#### Remove the following to Bid Package #10 Masonry:

 Demolition of existing brick and stucco at exterior façade per A4/A2.11 (Police H.Q.) is <u>NOT</u> included in this bid package and will be covered by bid package #3 Building Demolition.

#### Add the following to Bid Package #11 Structural and Miscellaneous Steel:

- Ledger and steel grate at new window wells per A4/A1.30 (police H.Q.).
- Stainless Steel shower bench support steel per B4/A8.50 (Police H.Q.), (solid surface slats by others, coordinate with Architectural Woodwork Contractor).

#### Add the following to Bid Package #12 Rough Carpentry:

- All wall cutting and removal at existing perimeter walls for new openings per Keynote #1 sheet A2.10, including framing at these locations for new storefront systems.
- Plywood, OSB and framing at all infill locations at roof and perimeter wall locations.

#### Add the following to Bid Package #13 Architectural Woodwork:

Solid surface bench slats at shower bench per B4/A8.50 (Police H.Q.).

#### Add the following to Bid Package #20 Aluminum Storefront & Glazing:

• (Police H.Q.) Sheet A2.20 Key Note #19 Frameless Gym Mirrors is to be included in this bid package.

#### Add the following to Bid Package #22 Metal Stud Framing, Drywall, Acoustic Tile Ceiling:

• Pony wall including pre-manufactured wall supports with base plate.

#### Add the following to Bid Package #25 Painting:

Prep and paint interior exposed wood where indicated including open ceiling structure.

#### Add the following to Bid Package #29 Fire Suppression:

- Demolish and removal of existing fire riser.
- Demolition of existing fire sprinkler system if required.

#### Add the following to Bid Package #30 Plumbing:

 Maintain and keep existing Plumbing systems operational as required and throughout phased construction per "Special Note" P1.0 (Police H.Q.).

#### Add the following to Bid Package #31 Heating, Ventilation and Air Conditioning:

 Maintain and keep existing HVAC systems operational as required and throughout phased construction per "Special Note" M1.0 (Police H.Q.).

#### Add the following to Bid Package #32 Electrical:

- Include pricing to disconnect and relocate all radio tower, antenna and dispatch equipment. Equipment to be relocated by Day Wireless as indicated.
- Maintain and keep existing Electrical systems operational as required and throughout phased construction.

#### **SPECIFICATIONS:**

Updated Specifications 092900 - Gypsum Board - See attached RFI #5

#### **ATTACHMENTS:**

Pre-Bid RFI's (27 pages)
Pre-Bid Conference & Sign-In Sheet (3 pages)
Bid Schedule (10 pages)
Site Material Handling Plan (1 page)
Substitution Request (1 page)

END OF ADDENDUM NO. 1



COMPANY, INC. 431 W. McGregor Dr., Boise, ID 83705 P: 208.384.0800 | F: 208.345.5323 | www.cmcompany.com

## **Pre-Bid Request for Information**

To: CM Company Inc. RFI No.: 01

431 W McGregor Dr. Date: 05/28/2021 Boise Idaho

seans@cmcompany.com

Job: Chubbuck Police H.Q. & Animal

**Shelter** 

Job Phone: 208-384-0800

Cc:

**Subject: Bid Package Clarification** 

Drawing: See Below Spec Section:

Request: Date Required:

1. Animal shelter structural details 217 & 218 call out "sunshade *and connection by others*". Where is the dividing line between BP 11 and 26? If supplied by us, will they be installed by BP 26 (possibly complicated and expensive coordination issues if by BP 11)

2. On B4/A1.40 please confirm BP #11 to provide and attach TS frame and BP #15 to provide and install metal wall panels.

Submitted by: Sean Setterberg, CM Company, Inc.

#### Response:

- 1. Bid Package #11 has no work here, Key-Note #9 & 10 are furnished and installed by Bid Package #26.
- 2. Confirmed, B4/A1.40 CONCOD 074213.13A, Lap-Seam Metal Wall Panels are to be furnished and installed by Bid Package #15.

Answered by: Sean Setterberg Answered date: 5/28/2021



COMPANY, INC. 431 W. McGregor Dr., Boise, ID 83705 P: 208.384.0800 | F: 208.345.5323 | www.cmcompany.com

## **Pre-Bid Request for Information**

To: CM Company Inc.

431 W McGregor Dr.

**Boise Idaho** 

seans@cmcompany.com

**RFI No.: 02** 

Date: 05/28/2021

Job: Chubbuck Police H.Q. & Animal

**Shelter** 

Job Phone: 208-384-0800

Cc:

Subject: Steel

Drawing: See Below Spec Section:

Request: Date Required:

1. Conflict between details 217,218/S4.1 and D4/A5.4, please clarify

- 2. It's somewhat difficult to determine length of anchor bolts for the police parking canopy columns. These bolts are a costly item. Per foundation minimum bearing depth on S1.0, dimension note 8 on detail 101/S3.0will be at least 36". While the bolts will extend only 33" into that, another 6-8" will be required to penetrate the top of the pier, grout, and top nut with an allowance for adjustment making the bolt around 40". The specified Simpson PAB9H is available only up to 36". Please clarify 36" bolt being sufficient, use of a coupler to join an additional length of threaded rod, or a custom fabricated bolt? Please clarify.
- 3. Support posts for man gates per B3/A1.40 are not shown embedded (stem wall specified to run under posts), nor with base plates, nor attached to masonry wall (1/4" space specified). Please clarify.
- 4. detail B3/A1.40 "gate lock" is pretty non-descript. There is a substantial difference between a simple hasp for a padlock and a locking latch of various optional qualities. Please clarify.

Submitted by: Sean Setterberg, CM Company, Inc. for Sub-Contractor

#### Response:

- 1. Weld shear plate to steel beam as specified in details 217 & 218/S4.1 for the awning connection
- 2. These bolts can be special ordered in lengths greater than 36". This may also be done by assembling a 1.125" Ø ASTM A193 B7 or F1554 grade 105 rod with a 5/8"x3.5"X3.25 plate wash fastened between two hex nuts. The overall length of 40" for the anchor assembly should be sufficient.
- 3. Attach tube steel to wall with 3/4" x 5" headed stud @ 16" o.c. for the height of the wall.
- 4. Hasp to be King Architectural Metals model #30-21, Heavy Duty Gravity Gate latch, or similar.

Answered by: Ben Bernier Answered date: 6-2-2021



COMPANY, INC. 431 W. McGregor Dr., Boise, ID 83705
P: 208.384.0800 | F: 208.345.5323 | www.cmcompany.com

## **Pre-Bid Request for Information**

To: CM Company Inc. RFI No.: 03

431 W McGregor Dr. Date: 06/1/2021

Boise Idaho
seans@cmcompany.com

Job: Chubbuck Police H.Q. & Animal

**Shelter** 

Job Phone: 208-384-0800

Cc:

Subject: Electrical / MC Cable

Drawing: Spec Section: See Below

Request: Date Required:

1. Spec Section 260503.2.1.A.8 states, Type MC where concealed behind covered wall systems. Spec Section 260506.2.1.C states, Use of the following is prohibited on this project, 7. MC Cable. Please clarify if MC Cable is permitted.

Submitted by: Sean Setterberg, CM Company, Inc. for Sub-Contractor

#### Response:

MC Cable is allowed for use as consistent with the National Electrical Code.

Answered by: Matt Bradley Answered date: 6-1-2021

Rev 12-17-18 Page 1 of 1



COMPANY, INC. 431 W. McGregor Dr., Boise, ID 83705
P: 208.384.0800 | F: 208.345.5323 | www.cmcompany.com

## **Pre-Bid Request for Information**

To: CM Company Inc.

431 W McGregor Dr.

**Boise Idaho** 

seans@cmcompany.com

**RFI No.: 04** 

Date: 06/1/2021

Job: Chubbuck Police H.Q. & Animal

**Shelter** 

Job Phone: 208-384-0800

Cc:

**Subject: Fire Suppression** 

Drawing: See Below Spec Section:

Request: Date Required:


- 1. There is an existing fire riser and sprinkler system in the Police H.Q. building, sheet P1.0 does not show the existing as being demolished. Is the existing fire riser and sprinkler system to be demolished?
- 2. What is the location of the existing fire riser?
- 3. What size pipe is feeding the existing fire riser?

Submitted by: Sean Setterberg, CM Company, Inc.

Rev 12-17-18 Page 1 of 2

#### Response:

- 1. The existing Fire Riser in the Basement closet in Ammo Storage room will need to be demolished. We are getting a new Fire Riser in Basement Riser room 011. Fire Sprinkling is deferred submittal by the successful Fire Sprinkler Sub-contractor. It will be up to them whether to re-use or replace the existing sprinkler lines and heads.
- 2. See Sheet A2.11 Existing Lab. The existing Fire Riser is located in the closet at the South East corner of that room.
- 3. The Riser is fed from an existing 4" water main coming off Hwy Ave. It then necks down to a 2-1/2" Fire Riser, which also has a 2" domestic tee connected to this. See Attached Picture.
- 4. For now we would like to leave both the new Water Riser as shown on sheet P1.1 in Riser room 011, and the existing Water Riser in Mechanical 144, until we can begin demolition and determine if these two locations are tied together, or independent.



**Answered by: Dwayne Sudweeks P.E.** 

Answered date: 6/2/2021



MPANY, INC. 431 W. McGregor Dr., Boise, ID 83705
P: 208.384.0800 | F: 208.345.5323 | www.cmcompany.com

## **Pre-Bid Request for Information**

To: CM Company Inc.

431 W McGregor Dr.

**Boise Idaho** 

seans@cmcompany.com

**RFI No.: 05** 

Date: 06/1/2021

Job: Chubbuck Police H.Q. & Animal

**Shelter** 

Job Phone: 208-384-0800

Cc:

**Subject: Finishes** 

Drawing: See Below Spec Section: See Below

Request: Date Required:

- 1. Bullet Resistant Fiberglass Panels. These are noted as 092900 Fiberglass Ballistic Wall Panels on the interior wall types on A3.30. They are not included in the 092900 Gypsum Board Spec. Please provide specification.
- 2. Material Legend on A3.10 notes SAP Sound Absorbing Panels (098433 & 098436). These are not noted on the finish schedule, not shown on the plans, and there is no specification for these. Is SAP to be removed from the material legend?
- 3. A3.30 092900F3 notes acoustically enhanced gypsum board. The 092900 Gypsum Board Spec does not include it. Please provide specification.
- 4. 092900 Gyp Board Spec 2.6A.1. and 3.5D.2. notes a level 5 finish. This will add a significant cost to the project. Please confirm that indeed a Level 5 finish will be required.
- 5. Specifications include 093013 Ceramic Tiling but the plans do not show any elevations of ceramic tile nor does the finish schedule note any. Backer board is noted in the 092900 Gypsum Board Spec. Is there any ceramic tile required?
- 6. FRP is noted in the material legend on A3.10. It is not shown on plans or finish schedule. Please confirm that no FRP is required.
- 7. 095423 Linear Metal Ceilings are in the Police Headquarters Spec Book but are not shown in the finish schedule or plans. Please advise if the linear ceiling spec is not part of this project.
- 8. Are 20-gauge equal studs acceptable for the interior? 30 mil and heavier studs are currently a 12 week or more lead time and 20-gauge is should be readily available from the supply warehouses

Submitted by: Sean Setterberg, CM Company, Inc. for Sub-Contractor

#### Response:

- 1. Section 092900 has been updated to include the ballistic resistant fiberglass panels. See the attached section 092900.
- 2. No sound absorbing panels are required in the project.
- 3. I was unable to find reference to acoustically enhanced gyp board, no acoustically enhanced gyp board is required in the project.
- 4. Yes, a level five finish is required as indicated.
- 5. Ceramic Tile occurs in rooms 101, 102, 103, 148, 149. It is noted on the finish plan sheet A2.30, Room finish Schedule Sheet A3.10, and Interior Elevation sheet A6.02 and A6.04
- 6. FRP Occurs at the janitor sink. See finish schedule sheet A3.10 and D4/A8.00
- 7. Linear metal ceiling occurs at the entry canopy and vestibule and are listed as ACP3 in the finish schedule on sheet A3.30. See reflected ceiling plan A2.40.
- 8. 20-gauge studs are acceptable.

Answered by: Ben Bernier Answered date: 6/2/2021

Rev 12-17-18 Page 2 of 2

#### SECTION 092900 - GYPSUM BOARD

#### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

#### A. Section Includes:

- 1. Interior gypsum board.
- 2. Sound attenuation insulation.
- Ballistic Resistant Fiberglass Panels

#### B. Related Requirements:

- 1. Section 061600 "Sheathing" for gypsum sheathing for exterior walls.
- 2. Section 092216 "Non-Structural Metal Framing" for non-structural framing and suspension systems that support gypsum board panels.

#### 1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

#### 1.4 DELIVERY, STORAGE AND HANDLING

A. Store materials inside under cover and keep them dry and protected against weather, condensation, direct sunlight, construction traffic, and other potential causes of damage. Stack panels flat and supported on risers on a flat platform to prevent sagging.

#### 1.5 FIELD CONDITIONS

- A. Environmental Limitations: Comply with ASTM C 840 requirements or gypsum board manufacturer's written recommendations, whichever are more stringent.
- B. Do not install paper-faced gypsum panels until installation areas are enclosed and conditioned.
- C. Do not install panels that are wet, those that are moisture damaged, and those that are mold damaged.
  - 1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
  - 2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

#### PART 2 - PRODUCTS

#### 2.1 GYPSUM BOARD, GENERAL

A. Size: Provide maximum lengths and widths available that will minimize joints in each area and that correspond with support system indicated.

#### 2.2 INTERIOR GYPSUM BOARD

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. American Gypsum.
  - 2. CertainTeed Corp.
  - 3. Georgia-Pacific Gypsum LLC.
  - 4. Lafarge North America Inc.
  - 5. National Gypsum Company.
  - 6. PABCO Gypsum.
  - 7. Temple-Inland.
  - 8. USG Corporation.
- B. Gypsum Board, Type X: ASTM C 1396/C 1396M.
  - 1. Thickness: 5/8 inch.
  - 2. Long Edges: Tapered.
- C. Gypsum Ceiling Board Type X: ASTM C 1396/C 1396M.
  - 1. Thickness: 5/8" inch.
  - 2. Long Edges: Tapered.
- D. Moisture- and Mold-Resistant Gypsum Board: ASTM C 1396/C 1396M. With moisture- and mold-resistant core and paper surfaces.
  - 1. Core: 5/8 inch, Type X.
  - 2. Long Edges: Tapered.
  - 3. Mold Resistance: ASTM D 3273, score of 10 as rated according to ASTM D 3274.

#### 2.3 TRIM ACCESSORIES

- A. Interior Trim: ASTM C 1047.
  - 1. Material: Galvanized or aluminum-coated steel sheet, rolled zinc, plastic, or paper-faced galvanized steel sheet.
  - 2. Shapes:
    - a. Cornerbead.
    - b. LC-Bead: J-shaped; exposed long flange receives joint compound.
    - c. L-Bead: L-shaped; exposed long flange receives joint compound.
    - d. U-Bead: J-shaped; exposed short flange does not receive joint compound.
    - e. Expansion (control) joint.

#### 2.4 JOINT TREATMENT MATERIALS

- A. General: Comply with ASTM C 475/C 475M.
- B. Joint Tape:
  - 1. Interior Gypsum Board: Paper.
- C. Joint Compound for Interior Gypsum Board: For each coat use formulation that is compatible with other compounds applied on previous or for successive coats.
  - 1. Prefilling: At open joints and damaged surface areas, use setting-type taping compound.
  - 2. Embedding and First Coat: For embedding tape and first coat on joints, fasteners, and trim flanges, use drying-type, all-purpose compound.
    - a. Use setting-type compound for installing paper-faced metal trim accessories.
  - 3. Fill Coat: For second coat, use drying-type, all-purpose compound.
  - 4. Finish Coat: For third coat, use drying-type, all-purpose compound.
  - 5. Skim Coat: For final coat of Level 5 finish, use setting-type, sandable topping compound drying-type, all-purpose compound high-build interior coating product designed for application by airless sprayer and to be used instead of skim coat to produce Level 5 finish.

#### 2.5 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that comply with referenced installation standards and manufacturer's written recommendations.
  - 1. Laminating adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- B. Steel Drill Screws: ASTM C 1002, unless otherwise indicated.
  - 1. Use screws complying with ASTM C 954 for fastening panels to steel members from 0.033 to 0.112 inch thick.
- C. Sound Attenuation Blankets: ASTM C 665, Type I (blankets without membrane facing) produced by combining thermosetting resins with mineral fibers manufactured from glass, slag wool, or rock wool.
  - 1. Fire-Resistance-Rated Assemblies: Comply with mineral-fiber requirements of assembly.
- D. Thermal Insulation: As specified in Section 072100 "Thermal Insulation."
- E. Vapor Retarder: As specified in Section 072100 "Thermal Insulation."
- F. Ballistic Resistant Fiberglass Panels
  - 1. The panels shall be made of multiple layers of starch-oil woven roving ballistic grade fiberglass cloth impregnated with a thermoset polyester resin and compressed into flat rigid sheets. The production technique and materials used shall provide the controlled internal delamination to permit the encapture of a penetrating projectile. Bullet Resistant

Fiberglass Panels: ½" maximum thickness, and 5.45 pounds per square foot maximum weight. Materials shall be Armortex O.F.300 or equal.

- 2. Security Level:
  - a. The Ballistic Resistant Fiberglass must be U.L. listed, rated for Level 3, minimum.

#### 2.6 TEXTURE FINISHES

- A. Primer: As recommended by textured finish manufacturer.
  - 1. Texture: level 5 smooth.

#### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine areas and substrates including welded hollow-metal frames and framing, with Installer present, for compliance with requirements and other conditions affecting performance.
- B. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 APPLYING AND FINISHING PANELS, GENERAL

- A. Comply with ASTM C 840.
- B. Install ceiling panels across framing to minimize the number of abutting end joints and to avoid abutting end joints in central area of each ceiling. Stagger abutting end joints of adjacent panels not less than one framing member.
- C. Install panels with face side out. Butt panels together for a light contact at edges and ends with not more than 1/16 inch of open space between panels. Do not force into place.
- D. Locate edge and end joints over supports, except in ceiling applications where intermediate supports or gypsum board back-blocking is provided behind end joints. Do not place tapered edges against cut edges or ends. Stagger vertical joints on opposite sides of partitions. Do not make joints other than control joints at corners of framed openings.
- E. Form control and expansion joints with space between edges of adjoining gypsum panels.
- F. Cover both faces of support framing with gypsum panels in concealed spaces (above ceilings, etc.), except in chases braced internally.
  - 1. Unless concealed application is indicated or required for sound, fire, air, or smoke ratings, coverage may be accomplished with scraps of not less than 8 sq. ft. in area.
  - 2. Fit gypsum panels around ducts, pipes, and conduits.
  - 3. Where partitions intersect structural members projecting below underside of floor/roof slabs and decks, cut gypsum panels to fit profile formed by structural members; allow 1/4- to 3/8-inch- wide joints to install sealant.

- G. Attachment to Steel Framing: Attach panels so leading edge or end of each panel is attached to open (unsupported) edges of stud flanges first.
- H. Wood Framing: Install gypsum panels over wood framing, with floating internal corner construction. Do not attach gypsum panels across the flat grain of wide-dimension lumber, including floor joists and headers. Float gypsum panels over these members or provide control joints to counteract wood shrinkage.
- I. Install sound attenuation blankets before installing gypsum panels unless blankets are readily installed after panels have been installed on one side.

#### 3.3 APPLYING INTERIOR GYPSUM PANELS FOR CEILINGS AND SOFFITS

- A. Apply panels perpendicular to supports, with end joints staggered and located over supports.
  - 1. Install with 1/4-inch open space where panels abut other construction or structural penetrations.
  - 2. Fasten with corrosion-resistant screws.

#### 3.4 INSTALLING TRIM ACCESSORIES

- A. General: For trim with back flanges intended for fasteners, attach to framing with same fasteners used for panels. Otherwise, attach trim according to manufacturer's written instructions.
- B. Control Joints: Install control joints according to ASTM C 840 and in specific locations approved by Architect for visual effect.
- C. Aluminum Trim: Install in locations indicated on Drawings.

#### 3.5 FINISHING GYPSUM BOARD

- A. General: Treat gypsum board joints, interior angles, edge trim, control joints, penetrations, fastener heads, surface defects, and elsewhere as required to prepare gypsum board surfaces for decoration. Promptly remove residual joint compound from adjacent surfaces.
- B. Prefill open joints and damaged surface areas.
- C. Apply joint tape over gypsum board joints, except for trim products specifically indicated as not intended to receive tape.
- D. Gypsum Board Finish Levels: Finish panels to levels indicated below and according to ASTM C 840:
  - 1. Level 1: Ceiling plenum areas, concealed areas, and where indicated.
  - 2. Level 5: Smooth where exposed to view.
    - a. Primer and its application to surfaces are specified in Section 099123 "Interior Painting."

#### 3.6 PROTECTION

- A. Protect adjacent surfaces from drywall compound and promptly remove from floors and other non-drywall surfaces. Repair surfaces stained, marred, or otherwise damaged during drywall application.
- B. Protect installed products from damage from weather, condensation, direct sunlight, construction, and other causes during remainder of the construction period.
- C. Remove and replace panels that are wet, moisture damaged, and mold damaged.
  - 1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
  - 2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

END OF SECTION 092900



MPANY, INC. 431 W. McGregor Dr., Boise, ID 83705
P: 208.384.0800 | F: 208.345.5323 | www.cmcompany.com

## **Pre-Bid Request for Information**

To: CM Company Inc.

431 W McGregor Dr.

**Boise Idaho** 

seans@cmcompany.com

**RFI No.: 06** 

Date: 06/1/2021

Job: Chubbuck Police H.Q. & Animal

**Shelter** 

Job Phone: 208-384-0800

Cc:

**Subject: Finishes** 

Drawing: See Below Spec Section:

Request: Date Required:

- 1. 095423 Linear Metal Ceilings 1.5 A. 1. Notes batt insulation to be installed in concealed and exposed locations. Please provide details. What R-Value is required?
- 2. 095113 Acoustical Panel Ceilings 2.2B is calling for fire rated 9/16 grid. Both of these requirements will add significant costs to the project. Since the specified tile is square edge is 15/16 acceptable? Is non fire rated grid acceptable?
- 3. A402 details 8,9,10, and 11 show rigid sheet wall covering. Section 102600 Wall and Door Protection 2.2 4. Shows this to be textured. Is Marlite standard embossed/pebbled FRP .09" acceptable?

Submitted by: Sean Setterberg, CM Company, Inc. for Sub-Contractor

#### Response:

- 1. Batt insulation can be friction fit between roof joists. Purpose of batts is to absorb and dampen sound, so there is no R-value requirement.
- 2. Non fire-rated 15/16" grid is acceptable.
- 3. Marlite standard .09" FRP is acceptable. Finish should be smooth.

Answered by: Ben Ledford Answered date: 06.02.21



Rev 12-17-18

## **CONSTRUCTION MANAGERS · GENERAL CONTRACTORS**

COMPANY, INC. 431 W. McGregor Dr., Boise, ID 83705
P: 208.384.0800 | F: 208.345.5323 | www.cmcompany.com

## **Pre-Bid Request for Information**

To:	CM Company Inc.	RFI No.: 07
	431 W McGregor Dr. Boise Idaho	Date: 06/1/2021
	seans@cmcompany.com	Job: Chubbuck Police H.Q. & Animal
	<u> </u>	Shelter
		Job Phone: 208-384-0800
Cc:		
Subj	ect: Door Frames	
Draw	ring:	Spec Section:
Requ	lest:	Date Required:
	Submitted by: Sean Setterberg, CM Company,	Inc. for Sub-Contractor
R	esponse:	
1.		terior wall construction appears to be mainly 3 ½" metal ction. Wall thicknesses will need to be field verified after thickness.
A	nswered by:	Answered date:

Page 1 of 1



MPANY, INC. 431 W. McGregor Dr., Boise, ID 83705
P: 208.384.0800 | F: 208.345.5323 | www.cmcompany.com

## **Pre-Bid Request for Information**

To: CM Company Inc.

431 W McGregor Dr.

**Boise Idaho** 

seans@cmcompany.com

**RFI No.: 08** 

Date: 06/2/2021

Job: Chubbuck Police H.Q. & Animal

**Shelter** 

Job Phone: 208-384-0800

Cc:

**Subject: Animal Shelter Storefront/HM Frames** 

Drawing: See below Spec Section: See below

#### Request: Date Required:

- 1. Is there a Basis of design for storefront metal? Spec book calls for 1 ¾" x4 ½" thermally broken......Typical tb frames are 2" x 4 ½", please clarify. Do they have a u-value that they are needing to meet? (This will help determine glass type and frame type). Do they need TB doors as well? (Thermal Doors can have a significant increase in cost of doors)
- 2. Door mk#102 type A frame is listed on door schedule as insulated glass and painted metal, the adjacent frame D door mk#103 is clear anodized with ¼" glazing. Is this correct?
- 3. Is door frame type B used or is it mislabeled on d/s? Please clarify.
- 4. What frame is section 084113-3 1.6 b&c referring too? It appears to be some form of fire rating or special type of insulated foam filled frame? Please clarify.
- 5. Is ab applied film acceptable for accent glass type G-5 in window frame 100A located on the front of building? Will they want that glass type used in adjacent door frame?
- 6. All the interior door frames with flush wood doors are listed as aluminum (type f) instead of hollow metal was this the intent? Please clarify.

Submitted by: Sean Setterberg, CM Company, Inc. for Sub-Contractor

#### Response:

- 1. Use Kawneer 451UT as basis of design, which is indeed 2"x4½". Doors do not need to be Thermally Broken.
- 2. Door 102 should be clear anodized and *not* thermally broken.
- 3. Doors 100 and 101 should be shown as Type B.
- 4. No fire rated doors are included, so 1.6 B&C can be disregarded.
- 5. We will want to stay with the etched glass for greater durability. Yes, it should extend into Door 100 as well.
- 6. Yes, interior doors are intended to be aluminum to eliminate rust from daily cleanings.

Answered by: Ben Ledford Answered date: 6.2.21

### REQUEST FOR INTERPRETATION

R.F.I. No:09	To: Sear Setterberg
Date: 5/24/2021	Project Name: Chulluck As
Regarding: Kennels- Steding Gates	Contract For: Shor- Line
From: Fred Petzold	Project No:
Specification Section Paragraph 117510 Paragraph 2 17 D 3 a	Drawing No Detail A 100 P 22/23
Drawn detals Bliding Kennel	Gatise when They are not
regular or advantageons -	
Sliding Guts represent a n	namterace headache and elective
quality issues.	
That - Line does not ma	unfactor any stiding kneel gats
Firther The room has plan	to of work space to hardle
	as detailed in all other kines
Signed by: John Jodge In w	Date: 5/24/2021
Response:	
Kennels D22 and D23 may be changed to have a sw gate similar to other kennels.	vinging

Signed by: Benjamin Ledford

Date: 6/02/21

Date Rec'd: Date Ret'd: Attachments

Copies: Date Rec'd: Consultant Downer Dothers


## REQUEST FOR INTERPRETATION

R.F.I. No: 10	To: Sea Settebus
Date: $\frac{5/24/2021}{}$	Project Name: Chushnel A5
Regarding: Kennel - Resty Buchs	Contract For: Shor-Line
From: Fred Petzell	Project No:
Specification Section Paragraph 2:3  Request: Charafication - Accessories.	Drawing No Detail
Request: Chrispatin - Azzessories.	
Accessories descriped an	[competitor] Mason & Testy shelve
Stor-line Does Not use	Ahanim / FRP in any of our
comparts du to quality and	sure life 185us.
Shoreline is Bonis of des	sign for there hevel component.
Bus Fold-up buchs are made	h of Stamless Steel and Dipped
Puc Steel Beds - See descrip Shor-line at mason comp	stors attached somet do not comingle.
Signed by: John 7 Partie (18)	Date: 5/24/2021
Dognongo	

No resting benches are required. Paragraph 2.3 can be disregarded.

Signed by: Benjamin Ledford Date: 6/02/21 Date Rec'd: Date Ret'd: **Attachments** Copies: □Architect  $\Box$ Contractor □ Consultant **□Owner** 

□ Others



310.0887.00 NYLON BUSHING WASHER 310.0887.01-NYLON FLAT WASHER BRACKET BRACKET 320.0269.99.41 FLIP UP BENCH MTG. ANG. lammon 062.2505.01 1/4-20 X 1/2 TRUSS HD. PHL. SS SCREW

THE FOLLOWING DOCUMENT CONTAINS INFORMATION PROPRIETARY TO SCHROER MANUFACTURING COMPANY. ANY REPRODUCTION, DISCLOSURE, OR USE OF THE DOCUMENT IS EXPRESSLY PROHIBITED WITHOUT WRITTEN CONSENT OF SCHROER MANUFACTURING SCHROER MANUFACTURING MAKES NO WARRANTIES, EITHER EXPRESSED OR IMPLIED WITH REGARD TO CUSTOMER REQUESTED MODIFICATIONS AND TO THE EXTENT SUCH MODIFICATIONS AND TO THE EXTENT SCHOOLS SCHOOLS SCHOOLS WITH RESELY AFFECT THE PRODUCTS, SUCH MODIFICATIONS VOID ANY WARRANTIES OF THE PRODUCTS, CUSTOMER FURTHER RELEASES AND AGREES TO INDEMNIFY DEFEND AND HOLD HARMERSS SCHROER MANUFACTURING FOR, FROM AND AGAINST ANY AND ALL CLAIMS DAMAGES LOSSES, LIABILITIES, COSTS OR EXPENSES FOR EXPENSES (INCLUDING ATTORNEYS' AND EXPERTS FEES) ARISING OUT OF OR RELATED TO SUCH MODIFICATIONS TO THE PRODUCTS.

## REQUEST FOR INTERPRETATION

R.F.I. No: 11	To: Sea Setter Serg
Date: 5/24/2021	Project Name: Chuldnok AS
Regarding: Kennels	Contract For: _ Show Line
From: Fred Petrold	Project No:
Specification Section Paragrap	oh Z Z Drawing No Detail
Request: Cloubeater!	
Setion A - Kennel Fr	ents defin Shor-Line (Brand) componer
1e: 14 tusing /78" H	tenset
Where Section B of	efuer T. Kennel (Brad) compount.
12: 1" Tusing /72	
Both components made	by Shor-Ima BUT do No
Comingle	
Secrettethed desery	tor pages - Choose proper compant
Signed by: group July 7/	Tolles 5/24/2021
Response:	
The Shor-Line component group is interreference to 1 1/4" tubing and 78" heigh	ded as the basis of design, as indicated by in Section 2.2.A
The reference to 1" tubing in Section 2.2 with the other paragraphs.	.D should be corrected to 1 1/4" to be consistent
Signed by:Benjamin Ledford	<b>Date:</b> 6/02/21
Date Rec'd: Date Ret'd:	Attachments
Copies:   Architect   Contra	ctor Consultant Owner Others

□Consultant

□Owner

□ Others

## **ANATOMY OF A SHOR-LINE RUN SYSTEM**

Shor-Line Stainless Steel Kennels are the crown jewel of our Shor-Line family. Years of craftsmanship have gone into creating our industry leading kennels that will last decades in your facility.

These runs are entirely constructed of Stainless Steel components, including a 1¼" Stainless Steel tube frame and Stainless Steel door. Two heavygauge Stainless Steel panels are sandwiched between a Sound Dampening Technology core to help reduce sound and add strength.

The shine of Stainless will reflect the quality of your organization, so we are committed to making it available in many sizes and designs to meet the unique needs of your facility.

#### **Optional Glass Colors**








#### **PERFORMANCE FEATURES:**

- · 6'6" run height.
- · 14" Staimless Steel tubing with mitered corners.
- · 14" Staimless Steel wire panel spaced every 6" for security.
- · Wire pamel rods welded at every intersection.
- · Choose from Tempered Glass or Wire Doors.
- · Tempered Glass awailable on doors, side panels and/or back panels.
- · Rods pass into gate frame tube for added security.
- · 16-gange Staimless Steel hardware.
- Dual Pin Latch for security (can be locked).
- Hands-free latch operation.
- Side panels available in 48" isolation or full isolation.
- · Nylom, brass or flag hinges are available.
- Wedge Kennel Run System follows the slope of the floor to prevent cross contamination.
- Imside run width is specified gate size.
- · Gates mount between side panels or walls.
- Optional feeding systems for food and water available, but must be ordered when doors are made because it can't be retrofitted.



## SHOR-LINE SINGLE KENNEL

#### **Benefits:**


The quality of this kennel is evident in the extra premium features, such as welds at every intersection and the smooth feel of crafted Stainless Steel. A pet in a Shor-Line kennel is protected by our well-crafted kennel that will withstand decades of use.

You choose the width and length to fit your needs, and mix and match side and back panels to make a statement. If you can dream it, we will make your vision sparkle!

#### Features:

- Our most durable kennel system features full Stainless Steel throughout this kennel.
- · Frame is made up of 11/4"-square tubing.
- · Stainless Steel is the best and easiest surface to clean and disinfect.
- · Installed freestanding or against a wall using modular components.
- Stainless Steel side panels are sloped ¼" per foot. Other slopes available by request.
- Optional PVC Isolation side panels are available in multiple colors to complement your decor.
- Two heavy-gauge Stainless Steel panels are sandwiched between a Sound Dampening Technology core to help reduce sound and add strength.
- Optional accessories: Top wire panel, side transfer door, Stainless Steel glass door, elevated PVC floor and swivel feeding system.
- Specs: standard widths: 30", 36" and 48"; standard depths: 5' and 6'; height 6'6" (approx.) 7' 2" (approx.) on elevated PVC Floor.

See "How to Buy Shor-Line Run Systems" on page 8 for outline of options.







▲ WARNING: This product can expose you to chemicals including chromium, which is known to the State of California to cause cancer. For more information go to www.P65Warnings.ca.gov

## **ANATOMY OF A T-KENNEL RUN SYSTEM**

**NEW!** T-Kennel Run Systems just got better with our new **T-Core** with Perfect Panel Design™. The new side and back panels use state-of-the-art lamination process that bonds two sheets of Acrylic PVC to an extra-dense foam core. The result is an extremely strong, lightweight and sound-dampening panel that lowers pet stress.

The new two-piece construction lets you easily choose the upper flag piece—Stainless or galvanized wire, glass or full isolation panel. This new design works both indoors and outdoors!




- · 6' run height.
- 1"-tubing with mitered corners (Stainless Steel or galvanized available).
- 3/16" Stainless Steel wire panel spaced every 6" for security. (Galvanized is 0.177 diameter wire).
- · Wire panel rods welded at every intersection.
- · Choose between Stainless Steel, Galvanized Steel or Tempered Glass gate.
- · Gate can open in or out and is completely removable.
- · Tempered Glass available on doors, side panels and/or back panels.
- · Rods pass into gate frame tube for added security.
- 16-gauge Stainless Steel hardware.
- · Single Pin Latch for security (can be locked) and Hands-Free latch operation.
- Side and back panels use our NEW! T-Core with Perfect Panel Design™ with Stainless Steel trim that provides strength, sound deadening and extra protection against chewing.
- Side and back panels can have top sections of Stainless or galvanized steel, tempered glass or PVC isolation panels.
- Provides triple protection from cross contamination with the Perfect Panel's channel design.
   We construct the channel from durable, corrosion-proof PVC that adds longevity.
- · Optional feeding systems for food and water available.

#### Standard PVC Colors



#### **Premium PVC Colors**





## **T-KENNEL SINGLE KENNEL**

#### **Benefits:**

This functional T-Kennel Run System allows you to design a room (or a row of rooms) that makes good use of space. Our T-Core with Perfect Panel Design™ adds strength and extra sound-dampening. Our options for colored PVC, tempered glass, Stainless and galvanized steel let you mix and match your look to fit budget and aesthetic choices.

#### Features:

- · Durable frame is made up of 1" square tubing.
- · You can install freestanding or against a wall.
- Includes one 2' wide gate that opens inward and outward, and it is completely removeable.
- Has two slots for optional slide-in feed and water trays. (Any Kennel less than 4' wide will receive only one feed tray slot.)
- Raised floor systems can run 32' in either direction before a stub out is needed and feature leveling legs to rectify floor imperfections.
- Our T-Core with Perfect Panel Design<sup>TM</sup> bonds two PVC panels to an extra-dense foam core. The heat and pressure from the sandwiched foam and PVC help reduce sound and add strength. New Stainless Steel trim adds styling and strength.
- NEW! Triple sealing channel follows the slope of the floor (up to to ½" per foot) to prevent cross contamination.
   Special design provides extra sealing power. Other slopes available by request.
- · Raised Floor Systems include a back panel.
- Easy to clean PVC Panels are available in multiple colors to complement your decor.
- Optional accessories: top wire panel, side transfer door, Half T-Cover, Stainless Steel wire door and Stainless Steel glass door. Choice of Stainless or galvanized steel components.
- Specs: standard Widths: 3', 3'6", & 4'; standard lengths:
   3', 4', 5', 6' & 8'; standard height: 6' on concrete (approx.),
   6' 10" on raised floor (approx.).



See "How to Buy T-Kennel Run Systems" on page 14 for outline of options.



Trench drain with half T-Cover.

## REQUEST FOR INTERPRETATION

	To:	Sea Setter for	ing .
1	Project Name: _	Chulbuch	As
Installe to.	Contract For: _	Shor-Lin	e
rold	Project No:		
Paragraph	Drawing N	o Detail	
Part 3 P	3.2 In	still Regard	in pricing
Part 3 PP	3.2 In	otali Required	in pricis
		u h	h h
			et include
Total And Sh	Welter Bose	Brd	
" Furnish and	d Install"		
14			
Photo w		Date: 5/24	12021
	Part 3 PP Part 3 PP Part 3 PP Part A:8	Project Name:	Distalle to: Shor-Line  201d Project No:  Paragraph Drawing No Detail  Part 3 P 3.2 Install Regard  Part 4:8 "Bid Package does no  Fatal Anul Shelter Base Bid  Furnish and Install"

Installation is **not** included in Bid Package #27.

Signed by: Sean Setterberg

Date: 5/28/2021

Date Rec'd: Attachments

Copies: 

| Architect | Contractor | Consultant | Owner | Others



MPANY, INC. 431 W. McGregor Dr., Boise, ID 83705
P: 208.384.0800 | F: 208.345.5323 | www.cmcompany.com

6/3/2021

Re: Chubbuck Police HQ & Animal Shelter:

To All Bidders,

The attached project schedule is broken into two phases, as outlined on the attached site material handling plan. Phase 1 is the North side of the Police HQ, Animal Shelter and associated sitework. Phase 2 is the South side of the Police HQ and associated sitework.


CM Company has made every effort to phase the work to most effectively use manpower and equipment, however there may be periods during construction when multiple crews will be required to be present to maintain the scheduled progress. Please review the scheduled start dates for each activity and take note of the times when multiple crews will be required on site. It is expected that this condition be planned for and the costs associated with this requirement be included in the bid amount.

The schedule establishes major activity start and finish dates only and is not to be considered exhaustive. It is expected that all bidders review the schedule and by acknowledging this addendum agree to commence work on or before the dates specified in the schedule and finish each task within the set forth duration.

Each contractor will be required to maintain close contact with CM Company's project manager and superintendent throughout the duration of the project to determine precise start dates. All subcontractors / suppliers should reasonably expect that the scheduled dates shown will vary to some degree as the construction progresses.

Thank you for your consideration,

Garrett Goldade Project Manager



Page 1A

Original

2021



		0							2021			2022	2		
ID	Description	Original Duration	Start	Finish	May	Jun	Jul	Aug	Sep	Oct No	v Dec	Jan Feb Mar Apr	May	Jun J	Jul
P1-250	Overhead Fire Sprinkler	15	08/30/21	09/20/21		11:		:		Overhead I	ire Sprink	ler			1 1
	MEP Rough In Walls	15	09/07/21	09/27/21					Y	MEP Rou					
	Measure and Fabricate Exterior Storefronts	15	09/08/21	09/28/21					₹III	544 E E	~	cate Exterior Storefronts			
P1-280	Install Exterior Flashings	3	09/08/21	09/10/21					<b>▼</b>	Install Exterio					
	Install Pony Wall Supports	1	09/14/21	09/14/21					7	Install Pony	1				
	Install Blocking & Backing	3	09/14/21	09/16/21					Υ.	Install Block					9
	Install Hollow Metal Door Frames	2	09/14/21	09/15/21					▼.	Install Hollov	1				
	Install Front Entry Steel	2	09/17/21	09/20/21					Y	Install Fron	1.1				
	Install Sunshade Knife Plates	2	09/21/21	09/22/21					1	Install Sun					
P1-320	Insulate Interior / Exterior Walls	4	09/22/21	09/27/21					1	<b>V</b>		terior Walls			
	Frame & Sheath Front Entry Walls	4	09/23/21	09/28/21								ont Entry Walls			
	Hang / Tape / Texture Sheetrock	18	09/24/21	10/19/21						7		Texture Sheetrock			
	Install Bullet Resistant Fiberglass Panels	2	09/28/21	09/29/21						V -		ant Fiberglass Panels			
	Install Exterior Storefronts & Glazing	5	09/29/21	10/05/21						<b>▼</b> :	1 1	prefronts & Glazing			
	Install Entry Beams & Roof Joists	3	09/29/21	10/01/21						▼ 1	1.5	s & Roof Joists			9
	Exterior MEP Rough In	7	09/29/21	10/07/21							r MEP Ro				
<del>                                   </del>	Install Entry Roof Sheathing	2	10/04/21	10/05/21						∀	1.1	Sheathing			
	Install Liquid Applied Membrane	3	10/06/21	10/08/21							3	lied Membrane			
	Patch & Repair EIFS	10	10/11/21	10/22/21						<del>   </del>	ch & Repa				
	Install Entry Masonry	10	10/11/21	10/22/21						<del>   </del>	tall Entry N				
	Interior Paint	12	10/13/21	10/28/21						- <del> </del>	terior Pair				
P1-470	Paint Exterior EIFS	12	10/25/21	11/09/21						<b>∀</b>	1 1	erior EIFS			9
	Install Acoustic Ceiling Grid	8	10/26/21	11/04/21						- +	1.3	ustic Ceiling Grid			
	Install Overhead Coiling Door	1	10/29/21	10/29/21							1.25	head Coiling Door			
	Install Interior Storefronts & Glazing	4	10/29/21	11/03/21							1.5	rior Storefronts & Glazing			
	MEP Trim Walls	1	10/29/21	10/29/21							13 :	Valls			
P1-510	Install Exterior Hand railings	2	11/01/21	11/02/21						∀	18 11	erior Hand railings			
P1-520	Install Millwork & Solid Surface	8	11/05/21	11/16/21							13 ::	Millwork & Solid Surface			
P1-530	Overhead MEP Trim	15	11/05/21	11/29/21						<u> </u>	13 3:	rhead MEP Trim			-
P1-540	Install Wood Veneer Ceilings	5	11/05/21	11/11/21						<b>1</b>	1 B 2 1	ood Veneer Ceilings			
P1-550	Install Entry Cladding / Soffits	10	11/10/21	11/23/21						Y	Instal	LEntry Cladding / Soffits			
	Install Ceramic Tile (Floors & Walls)	7		11/29/21	a a					47		all Ceramic Tile (Floors & Walls	)		
P1-570	Install Transaction Window	1	11/17/21	11/17/21	B .						7     3 :	Transaction Window	,		
P1-580	Install Ceiling Tile	7	11/24/21	12/06/21							77	stall Ceiling Tile			4
P1-590	Overhead Inspections	2	11/24/21	11/29/21	T ata						<del></del>	erhead Inspections			jai
P1-600	Install Sunshades	3	11/24/21	11/30/21	2						<b>▼</b>	all Sunshades			to
	Install Lap Seam Wall Panels	4		12/01/21	<u>-</u>						<b>V</b>	tall Lap Seam Wall Panels			Droi
Bid Sche	Start Date: 05/17 Finish Date: 08/10 Data Date: 05/17 Run Date: 06/03	0/22 7/21 3/21			(	Chub				& Anima edule 021			CO	OMPANY,	NC.

		Oniminal						2	021						2022	!			
ID	Description	Original Duration	Start	Finish	May	Jun	ı Jul	Aug	Sep	Oct	Nov	Dec	Jan Feb	Mar	Apr	May	Jun	Jul	
P1-620	Exterior MEP Trim	1	11/24/21	11/24/21								Exter	ior MEP Trim						
P1-630	Install Specialties / Safety Pads / Gym Mirrors	3	11/30/21	12/02/21								Ins	tall Specialtie	s / Safety	Pads / G	ym Mirro	ors		
P1-640	Install Storefront Doors	2	11/30/21	12/01/21								Inst	all Storefront	Doors					
P1-650	Install RSF / Carpet	18	12/01/21	12/28/21									Install RS	F / Carpe	t				
P1-660	Misc Exterior Painting As Req'd	4	12/02/21	12/07/21								<u> </u>	isc Exterior F	ainting As	Req'd				
P1-670	Install Access Control / Security Devices	10	12/07/21	12/20/21								<u> </u>	Install Acce	ss Contro	l / Securit	ty Device	es		
P1-680	Install Window Treatments	4	12/07/21	12/10/21								<u>.</u>	nstall Window	Treatme	nts				
P1-690	Plumbing Fixture Trim	9	12/14/21	12/28/21								<u> </u>	Plumbing	Fixture T	rim				
P1-700	Install Lockers / Special Cabinetry	6	12/15/21	12/22/21								<u> </u>	Install Lock	ers / Spec	cial Cabin	netry			
P1-710	Install / Relocate Special Systems Gear	15	12/21/21	01/13/22								Y_	Instal	l / Relocat	te Specia	l System	ıs Gear		
P1-720	Install Locker Benches	2	12/29/21	12/30/21									Install Lo	cker Benc	hes				
P1-730	Install Wood Doors & Hardware	4	12/29/21	01/04/22									📋 🛮 Install V	lood Dool	rs & Hard	ware			
P1-740	Install Appliances	1	12/29/21	12/29/21									Install Ap	pliances					
P1-750	Final Inspections	5	12/29/21	01/05/22									Final In	spections					
P1-760	Misc Sheetrock Patching as Req'd	4	01/05/22	01/10/22									Misc S	Sheetrock	Patching	as Req'o	d		
P1-770	Paint Touch Up	1	01/10/22	01/10/22									Paint	Touch Up					
P1-780	Final Cleaning	8	01/11/22	01/20/22									Fina	al Cleanin	9				
P1-790	OAC Punchlist	1	01/21/22	01/21/22									OA	C Punchli	st				
P1-800	Complete Punchlist Items	10	01/24/22	02/04/22										Complete	Punchlis	t Items			
P1-810	Owner Furniture Install	5	02/07/22	02/11/22									1	Owner I	urniture	Install			
P1-820	Dispatch Switch Over	2	02/14/22	02/15/22									1	··· Dispat	ch Switch	Over			
Site	work Phase 1																		
S1-10	Install Traffic Control	2	07/30/21	08/02/21			Ĭ.	Inst	tall Traff	ic Con	rol								
S1-20	Disconnect & Remove Site Lighting	3	07/30/21	08/03/21			Ĭ.	Dis	connect	t & Rer	nove Si	te Lightin	ģ						
S1-30	Install Erosion Control	1	07/30/21	07/30/21			Ĭ	Insta	all Erosi	on Con	trol								
S1-40	Provide Temporary Irrigation as Req'd	2	07/30/21	08/02/21			Ĭ	Pro	vide Te	mporar	y Irriga	tion as R	eq'd						
S1-50	Relocate Memorial Tree	1	07/30/21	07/30/21			Y	Relo	cate Me	emorial	Tree								
S1-60	Install Temporary Fencing	2	08/02/21	08/03/21			<u> 1</u>	Inst	tall Tem	porary	Fencin	g							
S1-70	Saw cut & Demo Asphalt	3	08/04/21	08/06/21			Y	Sa	w cut &	Demo	Asphal	t							
S1-80	Install Construction Entrance	1	08/09/21	08/09/21	<u>.</u>			<u> </u>	stall Co	nstruct	on Enti	rance							
S1-90	Intercept & Extend Natural Gas to Animal Shelter	4	08/09/21	08/12/21	5			<u>þ</u>	ntercept	t & Exte	nd Nat	ural Gas	to Animal Sh	elter					
S1-100	Sitework Demo As Req'd	4	08/10/21	08/13/21				<b>1</b> . §	Sitework	Demo	As Red	q'd							
S1-110	Remove & Protect Monument, Plaque, Flagpole etc.	2	08/16/21	08/17/21	ļ.			1	Remov	e & Pro	tect Mo	nument,	Plaque, Flag	pole etc.					4
S1-120	Demo Existing Awning	2	08/18/21	08/19/21	B D			<u>\                                   </u>	Demo	Existin	) Awnir	ng							Eini
S1-130	Demo Existing Entry Stair & Ramp	2	08/19/21	08/20/21	5			<u> </u>	Demo	Existin	g Entry	Stair & F	Ramp						too!
S1-140	Install 6" Water Tap & 6" Water Line	5	08/20/21	08/26/21	F		- P		Insta	ll 6" Wa	iter Tap	& 6" Wa	ter Line						Dr.C
	Start Date: 05/17 Finish Date: 08/10 Data Date: 05/17 Run Date: 06/03	0/22   7/21			(	Chu	bbuck P	Bid	HQ Sche /2/202	dule	imal :	Shelte	r						



ID	Description	Original Duration	Start	Finish	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	у ,	Jun	Jul	
S1-150	Install Water Meter and 1 1/2" Water Line	5	08/27/21	09/02/21		1		<u> </u>	Ins	tall Wat	er Meter a	and 1 1	/2" Wate	er Line	-						
S1-160	Excavate Parking Structure Footings	3	09/03/21	09/08/21				₹	1:18:	: 1: 11	Parking		1 1								0 0
	Excavate Front Entry Footings	2	09/09/21	09/10/21				7	<b>▽</b> -	9 15 11	Front Er			igo							
S1-180	Form & Pour Parking Structure Footings	7	09/09/21	09/17/21				7		: : ::	Pour Pa		-	Footing	ıs						
S1-190	Install New Idaho Power Utility & Transformer	10	09/09/21	09/22/21				١ .	믬.	: 1: 11	l New Ida	-	1 1	l i	li .						
S1-200	Install Underground Power Feeds to All Building	10	09/09/21	09/22/21				1	<b>T</b>	. 1- 11	I Undergro		1 1 1		- 1	-					
S1-210	Form & Pour Front Entry Footings	4	09/13/21	09/16/21					<b>Y</b>	: 1: 11	Pour Fro	- 1									
S1-220	Intercept and Extend SS to Animal Shelter	4	09/13/21	09/16/21					₹.	Interce	pt and Ex	tend S	S to Anir	mal She	lter						
S1-230	Form & Pour Entry Bench Walls & Cap	6	09/17/21	09/24/21						Form	& Pour E	Entry Be	ench Wa	ills & Ca	ар						
S1-240	Install Fiber Optic to Animal Shelter	2	09/17/21	09/20/21					Y	Install	Fiber Op	tic to A	nimal Sh	nelter							
S1-250	Install Storm New Storm Drain Systems	5	09/21/21	09/27/21						Insta	all Storm I	New St	orm Dra	in Syste	ems						
S1-260	Install Electric Gate Infrastructure	2	09/23/21	09/24/21					<b>Y</b> .	Insta	II Electric	Gate Ir	nfrastruc	ture							
S1-270	Site Lighting Underground & Pole Bases	8	09/23/21	10/04/21						Sit	e Lighting	g Under	rground	& Pole E	Bases	3					
S1-280	Excavate / Form / Pour Site Wall Footings & Walls	8	09/28/21	10/07/21						¥ F	xcavate /	Form /	Pour Si	te Wall F	Footin	igs & W	/alls				
S1-290	Prep Curb & Gutter	7	10/08/21	10/18/21							Prep Cu	rb & Gi	utter								
S1-300	Install Site Wall Masonry	10	10/08/21	10/21/21							Install S	Site Wa	ll Mason	ıry							
S1-310	Form & Pour Curb & Gutter	10	10/19/21	11/01/21							Form	n & Pou	ır Curb 8	& Gutter							
S1-320	Install Electric Gate & Access Control	2	10/22/21	10/25/21						Ĭ.	Install	Electric	Gate &	Access	Cont	rol					
S1-330	Install Site Wall Metal Panels	8	10/22/21	11/02/21							Insta	all Site \	Wall Me	tal Pane	els						
S1-340	Form & Pour Entry Steps & Ramp	5	10/25/21	10/29/21						Y	Form	& Pour	Entry S	teps & F	Ramp						
S1-350	Prep Sidewalks / Concrete Flatwork	6	11/03/21	11/10/21							Pr	ep Side	walks /	Concret	te Flat	twork					
S1-360	Install Irrigation Sleeving	3	11/11/21	11/15/21							<u> </u>	nstall In	rigation	Sleeving	g						
S1-370	Prep Site for Asphalt	2	11/11/21	11/12/21							] Pr	rep Site	for Asp	halt							
S1-380	Install Signage	1	11/11/21	11/11/21							in:	stall Sig	nage								
S1-390	Install Asphalt Paving	2	11/15/21	11/16/21							<u>I</u> i,	nstall A	sphalt P	aving							
S1-400	Pour Colored Concrete Sidewalks	2	11/16/21	11/17/21							<u>I</u> I i	Pour Co	olored C	oncrete	Sidev	valks					
S1-410	Install Chain Link Fencing	3	11/17/21	11/19/21							<u>J</u> [	Install (	Chain Li	nk Fenci	ing						
S1-420	Pour Stamped Concrete Sections	2	11/18/21	11/19/21							I I	Pour St	tamped	Concret	e Sec	tions					
S1-430	Pour Sidewalks & Flatwork	7	11/22/21	12/02/21							j	Pou	r Sidewa	alks & F	latwo	rk					
S1-440	Site Cleaning	5	12/03/21	12/09/21							ľ	Si	te Clear	ing							
Polic	ce Station Roof																				0 0
R-10	Remove Existing Skylights	2	08/05/21	08/06/21			I	Rem	ove I	Existing	Skylights										
R-20	Remove Existing Rooftop HVAC Equipment	8	08/05/21	08/16/21	,		Ĭ	Re	emov	e Existir	ng Roofto	p HVA	C Equipr	nent							4
R-30	Cut Openings in Roof for New Skylights	3	08/09/21	08/11/21	B			Cut	t Ope	nings in	Roof for	New S	kylights								Fini
R-40	Remove Coping Cap & Flashings	2	08/09/21	08/10/21	Ĕ			Rer	move	Coping	Cap & Fla	ashings	•								ţ
R-50	Infill Skylight Openings	4	08/09/21	08/12/21	Ĕ			Infi	II Sky	light Op	enings										Q
	Start Date: 05/17 Finish Date: 08/10 Data Date: 05/17	0/22 7/21			(	Chub	buck Po	Bid S		dule	mal Sh	nelter	r						=6	$\widehat{\mathbf{M}}$	

Run Date: 06/03/21

Page 4A

6/2/2021

2021



		Original							2	021							20					
ID	Description	Original Duration	Start	Finish	May	Jun	Jul	I A	Aug	Sep C	ct	Nov	Dec	Jan	Feb	Mar	Apr	May	y Ji	un	Jul	
R-60	Remove Existing Roof Drains as Req'd	3	08/11/21	08/13/21					) - j F	Remove Exi	sting I	Roof D	rains a	s Req'd	Т	T						0
R-70	Cut / Frame New Roof Access Hatch	2	08/13/21	08/16/21	1			7		Cut / Frame	New	Roof A	Access	Hatch								
R-80	Inspect Roof Drains as Req'd	2	08/16/21	08/17/21	1				<b>Y</b>	Inspect Ro	of Dra	ins as	Req'd									0 0
R-90	Remove Existing Roofing Membrane	5	08/17/21	08/23/21					<b>\dagger</b> .	Remove I	Existin	ıg Roo	fing Me	mbrane								
R-100	Fill Lower Portion of Roof w/ Insulation	2	08/24/21	08/25/21					Ţ.	Fill Lowe	Porti	on of F	Roof w	nsulati	on							
R-110	Obtain / Install New Rooftop Curbs	5	08/24/21	08/30/21					V	Obtain /	Instal	ll New	Roofto	։ p Curbs								0 0
R-120	Install New Roofing Membrane	10	08/31/21	09/14/21					4	Inst	all Nev	w Roo	ing Me	mbrane								
R-130	Obtain / Install New Skylights	6	09/15/21	09/22/21						<b>1</b> 0	otain /	/ Instal	New S	: Skylights								
R-140	Install New Coping Caps / Flashings	5	09/15/21	09/21/21						In	stall N	lew Co	ping C	aps / Fla	  shings							0 0
R-150	Install HVAC Rooftop Units	5	09/21/21	09/27/21										p Units								
Anin	nal Shelter																					0
A-10	Establish Gridlines	1	08/09/21	08/09/21				<b>∀</b>	E	stablish Gri	dlines											
A-20	Excavate Footings	2	08/10/21	08/11/21	1			V	E	xcavate Fo	otings	;										
A-30	Form & Pour Footings	3	08/12/21	08/16/21				4		Form & Po	ır Foo	tings										
A-40	Form & Pour Foundation & Thermomass Walls	6	08/17/21	08/24/21						Form & F			ion & <sup>-</sup>	hermon	nass W	alls						
A-50	MEP Foundation Block Outs	3	08/17/21	08/19/21					71	MEP Foun	dation	n Block	Outs									
A-60	Install Foundation Insulation	1	08/25/21	08/25/21					Ÿ	Install Fo	undat	ion Ins	ulation									
A-70	Backfill Foundation	2	08/26/21	08/27/21					Ÿ	Backfill F	ound	ation										0
A-80	Underslab Plumbing	3	08/30/21	09/01/21					7	Unders	lab Pl	umbin	9									
A-90	Underslab Electrical	3	08/30/21	09/01/21					7	Unders	lab El	ectrica	I									
A-100	Form & Pour Interior Footings	2	09/02/21	09/03/21						Form 8	Pour	Interio	or Foot	ings								
A-110	Install Underslab Insulation	2	09/07/21	09/08/21						Instal	l Unde	erslab	Insulat	ion								
A-120	Install Compacted Base Over Slab Insulation	2	09/09/21	09/10/21						Insta	I Com	npacte	d Base	Over SI	ab Insu	lation						0 0
A-130	Install In floor Heating Systems	10	09/13/21	09/24/21						lr	ıstall I	n floor	Heatir	ig Syste	ms							
A-140	Install Sanitary Sewer System	5	09/17/21	09/23/21						In	stall S	Sanitar	y Sewe	er Syster	n							
A-150	Install Storm Systems	3	09/24/21	09/28/21						<b>\frac{1}{4}</b>	nstall	Storm	Syste	ns								
A-160	Install Trench Drains	2	09/27/21	09/28/21						Ţ	nstall	Trenc	h Drair	ıs								0 0
A-170	Install Slab Vapor Barrier & Slab Reinforcing	2	09/27/21	09/28/21						1	nstall	Slab \	/apor E	3 arrier &	Slab R	einforci	ing					
A-180	Pour Building Slab	2	09/29/21	09/30/21						Y	Pour l	Buildin	g Slab									
A-190	Excavate / Form & Pour Kennel Foundations	6	09/29/21	10/06/21						<u></u>	Exc	avate /	Form	& Pour k	ennel I	Founda	tions					
A-200	Install CMU Walls	12	10/01/21	10/18/21	3						ļ:- lr	nstall 🤇	MU W	alls								
A-210	Install Electrical / Special Systems with Masonry	12	10/01/21	10/18/21						<u> </u>	lr (r	nstall E	lectric	al / Spec	ial Sys	tems wi	ith Maso	onry				
A-220	Plumbing Rough In at Masonry Walls	12	10/01/21	10/18/21						<u> </u>	I P	lumbir	ng Rou	gh In at	Masoni	y Walls	3					q
A-230	Install Gluelam Beams as Req'd	1	10/19/21	10/19/21	5						Y ij	nstall (	Gluelar	n Beams	as Re	q'd						igi
A-240	Measure & Fabricate Exterior Storefronts	10	10/19/21	11/01/21	2							Mea	sure 8	Fabrica	ite Exte	rior Sto	refronts	3				tooi
A-250	Install Exterior Flashings	2	10/19/21	10/20/21	F						<u>I</u> i	nstall l	Exterio	r Flashir	ıgs							Dro
Bid Sched	Start Date: 05/1' Finish Date: 08/1' Data Date: 05/1' Run Date: 06/0	7/21 3/21				Chul	obucł		3id	e HQ & / Schedu /2/2021		nal S	helte	er					COM	PANY	) (, IN(	<b>S</b> .


		Original						2	2021			2022	)		
ID		Original Duration	Start	Finish	May	Jun	Jul	Aug	Sep	Oct	Nov Dec	Jan Feb Mar Apr	May Jun	Jul	
A-260	Install Ledgers & Roof Joists	4	10/20/21	10/25/21							Install Ledge	rs & Roof Joists			
A-270	Install Roof Sheathing	3	10/26/21	10/28/21	1					¥	Install Roof				
A-280	Install Kennel Steel Columns & Beams	2	10/29/21	11/01/21	1					Ÿ	#I -0	nel Steel Columns & Beams			
A-290	Frame Interior Wood / Steel / Furring Walls	3	10/29/21	11/02/21	1					Ý	41 B B	rior Wood / Steel / Furring Wall	2		
A-300	Install Install Skylight Curbs	2	10/29/21	11/01/21	1					¥		all Skylight Curbs	•		
A-310	Install Roof Penetrations / Rooftop Curbs	3	10/29/21	11/02/21	1					¥		f Penetrations / Rooftop Curbs			
A-320	Install Fluid Applied Air Barrier	4	10/29/21	11/03/21	1					4		d Applied Air Barrier			
A-330	Frame & Sheath Kennel Roof	4	11/02/21	11/05/21	1					,	♥	Sheath Kennel Roof			
A-340	Install Skylights	2	11/02/21	11/03/21	1					,	Install Skyl				
A-350	Install Roofing Insulation & Membrane	4	11/02/21		1							ofing Insulation & Membrane			
A-360	Install Insulation	1	11/03/21	11/03/21	-						Install Insu				
A-370	Install CMU Veneer & Precast Sills	5	11/03/21		-						<b>∀</b>	MU Veneer & Precast Sills			
A-380	Install Exterior Storefronts	4	11/04/21	11/10/21	-						<b>∀</b>        : : !	terior Storefronts			
A-390	Install Sunshade Brackets	2	11/04/21		1						<b>∀</b>	nshade Brackets			
A-400	Install Standing Seam Roofing at Kennel	3	11/04/21	11/10/21	-						$\forall$				
A-410	MEP Overhead Rough In	7	11/08/21		-							anding Seam Roofing at Kenne	l		
A-410 A-420	Install Prefinished Metal Fascia / Coping Caps / Gut	1	11/11/21		-						<b>▼</b>  :  :	overhead Rough In	Coma / Cust	4	
A-420 A-430	Install EIFS	7	11/11/21		-						Install	Prefinished Metal Fascia / Copin	g Caps / Gui	iers	
A-430 A-440	Set Rooftop Equipment	3	11/11/21		-						<b>∀</b>				
A-440 A-450		2	11/18/21		-						<b>∀       </b>   :	ooftop Equipment			
	Install Suspended Gyp Ceilings	7	11/10/21	12/02/21	-						▼	Suspended Gyp Ceilings			
A-460	Hang / Tape / Texture Sheetrock Install Wood Soffits	7	11/22/21		-						<b>▼ III :</b>	ng / Tape / Texture Sheetrock			
A-470		3			-						<b>₩</b>	Wood Soffits			
A-480	Exterior Paint as Req'd	6	11/29/21	12/06/21	-						<b>♥</b>      -	terior Paint as Req'd			
A-490	Prep & Pour Exterior Concrete Flatwork	8	11/29/21	12/08/21	-						₩ :	rep & Pour Exterior Concrete Fl	atwork		
A-500	Install Sunshades	2	11/29/21	11/30/21	-						<b>∀</b>    :	all Sunshades			
A-510	Interior Paint	9	12/03/21	12/15/21	-						4	Interior Paint			
A-520	Install Building Signage	2	12/07/21	12/08/21	-						<b>▼</b> 1 = 5	stall Building Signage			
A-530	Install Chain Link Fencing & Gates	3	12/09/21	12/13/21	-							Install Chain Link Fencing & Ga	tes		
A-540	Patch Asphalt	1	12/09/21	12/09/21	-						<b>₩</b> *-	atch Asphalt			
A-550	Install Interior Aluminum Frames & Doors	2	12/16/21	12/17/21	-						<b>⊅</b> E	Install Interior Aluminum Frame	es & Doors		
A-560	Install Overhead Door	2		12/17/21							<b>*</b>	Install Overhead Door			
A-570	MEP Trim Walls	5	12/16/21	12/22/21	2						<b>₽</b>	MEP Trim Walls			
A-580	Install Grid Ceilings	3	12/16/21	12/20/21	5						₽	Install Grid Ceilings			
A-590	Install Linear Metal Ceilings	4	12/16/21		Ł						<b>↓</b> · ·	Install Linear Metal Ceilings			doi
A-600	Install Rigid Wall Coverings & Specialties	2	12/16/21	12/17/21	Ĕ							Install Rigid Wall Coverings &	Specialties		10.4
A-610	Seal Concrete Floors	2	12/20/21	12/21/21	9						1	Seal Concrete Floors			ogio
A-620	MEP Overhead Trim	6	12/22/21	01/03/22	F		İ					MEP Overhead Trim			هٔ
Bid Sche	Start Date: 05/17 Finish Date: 08/10 Data Date: 05/17 Run Date: 06/03	0/22 7/21 3/21			(	Chuk	buck F		e HQ Sche /2/202		mal Shelte	r	COMP	ANY, IN	L IC.

ID	Description	Original Duration	Start	Finish	May	Jun	Jul	Aug Sep	Oct	Nov Dec	Jan	Feb	Mar Apı	r Ma	ay Jur	n Jul	
A-630	Install Millwork	3	12/23/21	12/29/21		1 :	<u> </u>				Insta	all Millwor	k i				
A-640	Install Ceiling Tile	2	01/04/22								NZ.	stall Ceilir					
A-650	Paint Paw Prints on Wall	1	01/06/22		1						$\forall$		Prints on W	/all			
A-660	Install Walk Off Mat	1	01/06/22								. ∀	stall Walk	E 3	uir			
A-670	Install Kennels / Cages	5	01/06/22								▼		nels / Cag	<b>6</b> 9			
A-680	Install Wood Doors & Hardware	2	01/07/22		1						♦		od Doors &		are		
A-690	Touch Up Paint	3	01/13/22		1						<b>∀</b>	Touch U		i idi divi	uio		-
A-700	Final Clean	4	01/18/22								₹.	Final Cl					
A-710	OAC Punchlist	1	01/24/22								4		unchlist				
A-720	Complete Punchlist Items	5		01/31/22	1						¥		olete Punch	alist Iter	ms		
Polic	ce Station Phase 2																
P2-10	Asbestos Testing	10	06/09/21	06/22/21			Asbes	tos Testing····									
P2-20	Asbestos Remediation as Req'd	10	03/09/22	03/22/22								,	Ast	estos l	Remedia	tion as R	eq'd
P2-30	Demo Existing Ceilings, Drywall, Walls, Etc.	6	03/23/22	03/30/22									. ♦			eilings, D	11 1 1
P2-40	Demo Existing Plumbing as Req'd	2	03/23/22	03/24/22									- 😝 ii			mbing as	1 1 1
P2-50	Demo Existing HVAC as Req'd	6	03/23/22	03/30/22									F 🗘 🗆 :			VAC as F	1 5 11
P2-60	Demo Existing Electrical as Req'd	4	03/23/22	03/28/22									▼		_	ectrical as	11 7 11
P2-70	Saw cut and Prep Basement Footings	3	03/31/22	04/04/22									<u> </u>	Saw cu	ut and Pr	ep Basen	nent F
P2-80	Remove Existing Windows	3	03/31/22	04/04/22									7	Remov	e Existin	g Windov	vs
P2-90	Shoring as Req'd	2	03/31/22	04/01/22									<b>7</b> S	3horing	as Req'o	t	
P2-100	Saw cut Slabs for Electrical / Plumbing Routings	3	03/31/22	04/04/22										Saw cu	ıt Slabs f	or Electric	cal / P
P2-110	MEP Rough In Overhead	12	03/31/22	04/15/22										MEF	<sup>2</sup> Rough	In Overhe	ead
P2-120	Overhead Fire Sprinkler	10	03/31/22	04/13/22									<b>*</b>	Over	head Fir	e Sprinkle	ər
P2-130	Underslab Electrical / Plumbing	2	04/05/22	04/06/22									<b>Y</b>	Unders	slab Elec	trical / Pl	umbin
P2-140	Form & Pour Basement Footings	3	04/05/22	04/07/22									1	Form {	& Pour B	asement	Footir
P2-150	Install Structural Columns & Beams	3	04/08/22	04/12/22									Y	Insta	II Structu	ral Colum	ıns & I
P2-160	Install New Floor Joists and Sheathing	3	04/13/22	04/15/22										Insta	all New F	loor Joist	s and
P2-170	Cut New Window / Door Openings and Re-Frame	6	04/13/22	04/20/22										L Cu	t New W	indow / D	oor O
P2-180	Install New Interior Wall Sheathing	4	04/21/22	04/26/22										<u>l</u> Ir	าstall Neง	w Interior	Wall S
P2-190	Measure & Fabricate Exterior Storefronts	10	04/21/22	05/04/22	2										Measure	e & Fabrio	cate E
P2-200	Interior Non-Load Bearing Framing	5	04/21/22	04/27/22										lr Ir	nterior No	on-Load E	3earin
P2-210	Install Exterior Flashings	3	04/21/22	04/25/22	B									ln In	stall Exte	erior Flasl	nings
P2-220	MEP Rough In Walls	5	04/26/22	05/02/22	ļ.										MEP Ro	ugh In W	alls 🦸
P2-230	Install Blocking & Backing	3	04/28/22	05/02/22	B D									Ä	Install Bl	ocking &	Backii
P2-240	Install Hollow Metal Door Frames	2	04/28/22	04/29/22	م م									1	nstall Ho	llow Meta	al Dooi
P2-250	Insulate Interior / Exterior Walls	3	05/03/22	05/05/22	É									111	Insulate	Interior /	Exter
Bid Sche	Start Date: 05/17 Finish Date: 08/10 Data Date: 05/17 Run Date: 06/03 dule.ppx	0/22 7/21 3/21			(	Chub	buck	Police HQ Bid Sche 6/2/202	dule	nal Shelt	er				COMF	ANY, IN	IC.

2021

		Original						2	021							2	022			
ID	Description	Original Duration	Start	Finish	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Арі	Ma	ay Jun	Jul	
P2-260	Install Exterior Storefronts	4	05/05/22	05/10/22											E	1 1		Install E	xterior	Storefr
P2-270	Hang / Tape / Texture Sheetrock	14	05/06/22	05/25/22													7			e / Tex
P2-280	Patch & Repair EIFS	8	05/11/22	05/20/22													Y	- <b>6</b> 1 5 5		air EIF
P2-290	Paint Exterior EIFS	10	05/23/22	06/06/22														▼		cterior I
P2-300	Interior Paint	10	05/24/22	06/07/22														i i	nterior	Paint
P2-310	Install Acoustic Ceiling Grid	6	06/03/22	06/10/22														<b>7</b>	Install A	Acousti
P2-320	MEP Trim Walls	5	06/06/22	06/10/22														<b>1</b>	MEP T	rim Wa
P2-330	Misc Exterior Painting As Req'd	1	06/07/22	06/07/22														<b>7</b> N	∕lisc Ex	terior F
P2-340	Install Interior Storefronts	4	06/08/22	06/13/22														7	Install	Interio
P2-350	Overhead MEP Trim	7	06/09/22	06/17/22														<b>1</b>	Overl	head M
P2-360	Install Millwork & Solid Surface	3	06/13/22	06/15/22															İnstall	l Millwc
P2-370	Install Access Control / Security Devices	5	06/13/22	06/17/22														T <sub>1</sub>	Instal	I Acces
P2-380	Plumbing Fixture Trim	4	06/16/22	06/21/22														1	Plun	nbing F
P2-390	Overhead Inspections	1	06/17/22	06/17/22														1	Overl	head Ir
P2-400	Install Ceiling Tile	4	06/20/22	06/23/22														<u> </u>	Inst	all Ceil
P2-410	Install Storefront Doors	2	06/20/22	06/21/22														I	Insta	all Store
P2-420	Final Inspections	5	06/20/22	06/24/22														I	Fin	al Inspe
P2-430	Install Special Systems Gear	1	06/20/22	06/20/22														1	Insta	all Spec
P2-440	Install RSF / Carpet	8	06/21/22	06/30/22														ĭ	In	stall R
P2-450	Install Window Treatments	2	06/24/22	06/27/22														1	lns	stall Wi
P2-460	Install Lockers / Special Cabinetry	3	07/01/22	07/07/22																Install I
P2-470	Install Wood Doors & Hardware	3	07/01/22	07/07/22											ŀ				H	Install \
P2-480	Install Appliances	1	07/01/22	07/01/22															H In	ıstall A
P2-490	Misc Sheetrock Patching as Req'd	3	07/06/22	07/08/22															1	Misc S
P2-500	Install Specialties	2	07/06/22	07/07/22															1	Install
P2-510	Paint Touchup	1	07/08/22	07/08/22															1	Paint 1
P2-520	OAC Punchlist	1	07/11/22	07/11/22															I-	OAC
P2-530	Final Cleaning	5	07/11/22	07/15/22															<b>₽</b> i	Final
P2-540	Complete Punchlist Items	7	07/12/22	07/20/22																Cor
P2-550	Owner Furniture Install	5	07/21/22	07/27/22															ľ	0
Sitev	vork Phase 2																			
S2-10	Install Erosion Control	1	03/09/22	03/09/22											Y:: 1	nstall l	Erosio	n Control		
S2-20	Install Traffic Control	1	03/10/22	03/10/22											Y	Install	Traffic	Control		ę
S2-30	Install Temporary Fencing	2	03/10/22	03/11/22	B										7	Install	Tempo	orary Fenc	ing	i i
S2-40	Saw cut & Demo Asphalt	2	03/14/22	03/15/22	2										1	Saw	cut & C	emo Asph	alt	ţ
S2-50	Sitework Demo As Req'd	3	03/16/22	03/18/22	<u> </u>										Y <sub>1</sub>	Sitev	vork D	emo As Re	eq'd	Q
	Start Date: 05/1 Finish Date: 08/1 Data Date: 05/1 Run Date: 06/0	0/22 7/21			(	Chub	buck I	Bid :	HQ Sche 2/202	dule	mal S	helte	r							
Bid Sched	dule.ppx Page	8A																COMPA	NN Y, II	NC.

Original				2021						2022								
ID	Description	Original Duration	Start	Finish	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr May	Jun Jul	
S2-60	Remove Existing Entry Canopy	3	03/21/22	03/23/22											<u>, i</u>	Remove Exist	ing Entry Canor	у
S2-70	Install Electric Gate Infrastructure	2	03/21/22	03/22/22											<b>Y</b> .	Install Electric	Gate Infrastruc	ιure
S2-80	Remove Existing Window Wells	2	03/24/22	03/25/22											7	Remove Exis	ting Window We	ells
S2-90	Excavate For New Basement Windows	2	03/28/22	03/29/22											7	Excavate Fo	r New Basemer	nt Wi
S2-100	Saw cut New Basement Windows	2	03/30/22	03/31/22											7	Saw cut Nev	w Basement Wi	ndov
S2-110	Excavate Remainder of Parking Structure Footings	2	03/30/22	03/31/22											4	Excavate Re	emainder of Par	king
S2-120	Infill Existing Windows as Req'd	4	04/08/22	04/13/22												▼ :::	ting Windows a	-
S2-130	Form & Pour Window Wells	5	04/14/22	04/20/22												<b>*</b>	Pour Window	
S2-140	Excavate / Form / Pour Site Wall Footings & Walls	6	04/21/22	04/28/22												Exca	vate / Form / Po	our S
S2-150	Form & Pour Remainder of Parking Structure Footin	4	04/21/22	04/26/22												Form	& Pour Remair	ıder
S2-160	Install Parking Canopy Steel	7	04/27/22	05/05/22												Ins	tall Parking Car	юру
S2-170	Install Site Wall Masonry	6	04/29/22	05/06/22												♥  : :	tall Site Wall M	
S2-180	Paint Parking Canopy Steel	8	05/06/22	05/17/22												4	Paint Parking C	: : !!
S2-190	Prep Curb & Gutter	2	05/09/22	05/10/22												₩ .	rep Curb & Gutt	: 11
S2-200	Install Site Wall Metal Panels	4	05/09/22	05/12/22												₩ !	stall Site Wall I	
S2-210	Install Irrigation Sleeving	1	05/11/22	05/11/22												▼ !	stall Irrigation S	1 1
S2-220	Form & Pour Curb & Gutter	3	05/12/22													₩	Form & Pour Cu	: : !!
S2-230	Prep Sidewalks / Concrete Flatwork	2	05/17/22		-											₩	Prep Sidewalks	
S2-240	Install Signage	1	05/19/22		-											4	Install Signage	- 1
S2-250	Pour Sidewalks & Flatwork	3	05/20/22		-											<b>†</b>	Pour Sidewall	: : !!
S2-260	Import Topsoil as Req'd	5	05/25/22													1	Import Tops	
S2-270	Landscape Curbing	3	06/02/22		-												Landscape	
S2-280	Install Irrigation Systems	10	06/02/22													,	Install Ir	: 11
S2-290	Prep Site for Asphalt	2	06/02/22		-											,	Prep Site fo	: 11
S2-300	Install Asphalt Paving	1	06/06/22														Install Asp	
S2-310	Install Electric Gate & Access Control	2	06/07/22														Install Ele	
S2-320	Install Turf Sod & Plantings	10	06/16/22														Insta	
	Site Cleaning	3		07/06/22	-												Sit	"   u
02-000	one dearning	3	00/30/22	01/00/22	-												<u> </u>	
					k l													nich
					Ĕ													ii y
					5													ojo
					<u> </u>													
Start Date: 05/17/21 Finish Date: 08/10/22 Data Date: 05/17/21						Chubbuck Police HQ & Animal Shelter									-			
Data Date: 05/10/22 Data Date: 05/17/21 Run Date: 06/03/21 Bid Schedule 6/2/2021																		
									ا ال									
Bid Sche	dule.ppx Page	9A														C(	ompany, inc	<b>,.</b>
L 356	,,	- '																



LOMBARD CONRAD ARCHITECTS 1221 Shoreline Lane | Boise, ID 83702 P 208.345.6677 | F 208.344.9002





# SUBSTITUTION REQUEST FORM

TO:	CM Company I	nc., Attention: Se	ean Setterberg ( <u>se</u>	ans@cmcompan	y.com)	
PROJECT	: CHUBBUCA	e Payce D	EPALTMENT RE	NOVATION		
We hereby	y submit for your o	onsideration the	following product	instead of the sp	ecified item for the	e above
Section		<u>Paragraph</u>		Specified Item		
Attach co	ons, drawings, pheh th description of cl	l data, includir otographs, perfo	ng product descormance and test	cription, propose data adequate f	ed manufacturers or evaluation of r	request.
WILLTCH	Manufacturer and		NER SYSTEM LA	1177 MOVABLE	- DRAW LOCAT	704
	ct does proposed s	substitution have	on the product be	ing purchased?		
specified is shown on warranty r	rsigned certifies the tem. Undersigned the the trawings, will requirements, and ed agrees to pay for	d further certifies not have advers that maintenanc	s that the propose se impact on other se and service is a	ed substitution do trades, construct vailable locally o	es not affect dimition schedule or some readily obtainable	ensions pecified le. The
Submitted	By:					
Signature		KOBERT	Name (Printed)			
	OBURY LM DR. City, State	MONED BEACH	,	704 90:	irm 7 9838 hone	
X Acce	epted	By:	nBen	<b>J</b>		
	accepted	Date:	6-3-2021			
Acce	epted as noted	Remarks:				
Rec	eived too late					