DIVISION 23: HEATING, VENTILATING, AND AIR-CONDITIONING

- 23 0000 HEATING, VENTILATING, AND AIR-CONDITIONING
- 23 0501 COMMON HVAC REQUIREMENTS
- 23 0553 IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT
- 23 0593 TESTING, ADJUSTING, AND BALANCING
- 23 0712 DUCTWORK INSULATION
- 23 0717 ROUND SUPPLY DUCT INSULATION
- 23 0718 DUCT LINING
- 23 0800 FIRE STOPPING
- 23 0933 TEMPERATURE CONTROLS

23 2000 PIPING SYSTEMS

- 23 2300 REFRIGERANT PIPING SYSTEMS
- 23 3000 HVAC AIR DISTRIBUTION
- 23 3114 LOW-PRESSURE STEEL DUCTWORK
- 23 3346 FLEX DUCT
- 23 3400 EXHAUST FANS
- 23 3450 HVAC FANS
- 23 3713 AIR OUTLETS & INLETS
- 23 4100 DISPOSABLE FILTERS
- 23 5134 FLUES
- 23 5416 SEPARATED COMBUSTION UNIT HEATERS
- 23 5418 RADIANT HEATING SYSTEM

23 6000 CENTRAL COOLING EQUIPMENT

- 23 6210 EVAPORATIVE AIR COOLING EQUIPMENT
- 23 6220 ROOFTOP HEATING-COOLING UNIT
- 23 8127 SPLIT SYSTEM AIR CONDITIONING UNITS

END TABLE OF CONTENTS

SECTION 23 0501 – COMMON HVAC REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and General Provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Furnish labor, materials, and equipment necessary for completion of work as described in Contract Documents.
- B. It is the intent of these specifications that the systems specified herein are to be complete and operational before being turned over to the owner. During the bidding process, the contractor is to ask questions or call to the engineer's attention any items that are not shown or may be required to make the system complete and operational. Once the project is bid and the contractor has accepted the contract, it is his responsibility to furnish and install all equipment and parts necessary to provide a complete and operational system without additional cost to the owner.
- C. Furnish and install fire stopping materials to seal penetrations through fire rated structures and draft stops.
- D. Includes But Not Limited To:
 - 1. General procedures and requirements for HVAC.
- E. Related Sections:
 - 1. Section 23 0593: Testing, Adjusting, and Balancing for HVAC.

1.3 SUBMITTALS

- A. Substitutions: By specific designation and description, standards are established for specialties and equipment. Other makes of specialties and equipment of equal quality will be considered provided such proposed substitutions are submitted to the Architect for his approval, complete with specification data showing how it meets the specifications, at least 5 working days prior to bid opening. A list of approved substitutions will be published as an addendum.
 - 1. Submit a single copy of Manufacturer's catalog data including Manufacturer's complete specification for each proposed substitution.
 - 2. The Architect or Engineer is to be the sole judge as to the quality of any material offered as an equal.
- B. Product Data, Shop Drawings: Within 30 days after award of contract, submit 10 sets of Manufacturer's catalog data for each manufactured item.
 - 1. Literature shall include enough information to show complete compliance with Contract Document requirements.
 - 2. Mark literature to indicate specific item with applicable data underlined.
 - 3. Information shall include but not be limited to capacities, ratings, type of material used, guarantee, and such dimensions as are necessary to check space requirements.
 - 4. When accepted, submittal shall be an addition to Contract Documents and shall be in equal force. No variation shall be permitted.
 - 5. Even though the submittals have been accepted by the Engineer, it does not relieve the contractor from meeting all of the requirements of the plans and specifications and providing a complete and operational system.
- C. Drawings of Record: One complete sets of blue line mechanical drawings shall be provided for the purpose of showing a complete picture of the work as actually installed.
 - 1. These drawings shall serve as work progress report sheets. Contractor shall make notations neat and legible therein daily as the work proceeds.
 - 2. The drawings shall be kept at the job at a location designated by the Mechanical Engineer.
 - 3. At completion of the project these "as-built" drawings shall be signed by the Contractor, dated, and returned to the Architect.

- D. Operating Instructions and Service Manual: The Mechanical Contractor shall prepare 2 copies of an Operation and Maintenance Manual for all mechanical systems and equipment used in this project. Manuals shall be bound in hard-backed binders and the front cover and spine of each binder shall indicate the name and location of the project. Use plastic tab indexes for all sections. Provide a section for each different type of equipment item. The following items shall be included in the manual, together with any other pertinent data. This list is not complete and is to be used as a guide.
 - 1. Provide a master index at the beginning of the manual showing all items included.
 - 2. The first section of the manual shall contain:
 - a. Names, addresses, and telephone numbers of Architect, Mechanical Engineer, Electrical Engineer, General Contractor, Plumbing Contractor, Sheet Metal Contractor, and Temperature Control Contractor.
 - b. List of Suppliers which shall include a complete list of each piece of equipment used with the name, address, and telephone number of vendor.
 - c. General Description of Systems including -
 - 1) Location of all major equipment
 - 2) Description of the various mechanical systems
 - 3) Description of operation and control of the mechanical systems
 - 4) Suggested maintenance schedule
 - Copy of contractor's written warranty
 - 3. Provide a copy of approved submittal literature for each piece of equipment.
 - 4. Provide maintenance and operation literature published by the manufacturer for each piece of equipment which includes: oiling, lubrication and greasing data; belt sizes, types and lengths; wiring diagrams; step-by-step procedure to follow in putting each piece of mechanical equipment in operation.
 - 5. Include parts numbers of all replaceable items.
 - 6. Provide control diagram and operation sequence, along with labeling of control piping and instruments to match diagram.
 - 7. Include a valve chart indicating valve locations.
- E. Include air balance and/or water balance reports.

1.4 SUBMITTALS FOR COMMON HVAC REQUIREMENTS

- A. Samples: Sealer and gauze proposed for sealing ductwork.
- B. Quality Assurance / Control:

d.

- 1. Manufacturer's installation manuals providing detailed instructions on assembly, joint sealing, and system pressure testing for leaks.
- 2. Specification data on sealer and gauze proposed for sealing ductwork.
- C. Quality Assurance
 - 1. Requirements: Construction details not specifically called out in Contract Documents shall conform to applicable requirements of SMACNA HVAC Duct Construction Standards.
 - 2. Pre-Installation Conference: Schedule conference immediately before installation of ductwork.

1.5 QUALITY ASSURANCE

- A. Requirements of Regulatory Agencies:
 - 1. Perform work in accordance with applicable provisions of local and state Plumbing Code, Gas Ordinances, and adoptions thereof. Provide materials and labor necessary to comply with rules, regulations, and ordinances.
 - 2. In case of differences between building codes, state laws, local ordinances, utility company regulations, and Contract Documents, the most stringent shall govern. Promptly notify Architect in writing of such differences.
- B. Applicable Specifications: Referenced specifications, standards, and publications shall be of the issues in effect on date of Advertisement for Bid.
 - 1. "Heating, Ventilating and Air Conditioning Guide" published by the American Society of Heating and Air Conditioning Engineers.
 - 2. "Engineering Standards" published by the Heating, Piping, and Air Conditioning Contractors National Association.

- 3. "2018 International Building Code", "2018 International Mechanical Code", and "2018 International Fire Code" as published by the International Conference of Building Officials.
- 4. 2018 International Plumbing Code.
- 5. "National Electrical Code" as published by the National Fire Protection Association.
- 6. "2018 International Energy Conservation Code ".
- C. Identification: Motor and equipment name plates as well as applicable UL and AGA labels shall be in place when Project is turned over to Owner.

1.6 INSPECTIONS AND PERMITS

A. Pay for permits, fees, or charges for inspection or other services. Local and state codes and ordinances must be properly executed without expense to Owner and are considered as minimum requirements. Local and state codes and ordinances do not relieve the Contractor from work shown that exceeds minimum requirements.

1.7 ADDITIONAL WORK:

A. Design is based on equipment as described in the drawing equipment schedule. Any change in foundation bases, electrical wiring, conduit connections, piping, controls and openings required by alternate equipment submitted and approved shall be paid for by this division. All work shall be in accordance with the requirements of the applicable sections.

PART 2 - PRODUCTS FOR COMMON HVAC REQUIREMENTS

- A. Finishes, Where Applicable: Colors as selected by Architect.
- B. Duct Hangers:
 - 1. One inch 25 mm by 18 ga 1.27 mm galvanized steel straps or steel rods as shown on Drawings, and spaced not more than 96 inches 2 400 mm apart. Do not use wire hangers.
 - 2. Attaching screws at trusses shall be 2 inch 50 mm No. 10 round head wood screws. Nails not allowed.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Site Inspection:
 - 1. Examine premises and understand the conditions which may affect performance of work of this Division before submitting proposals for this work.
 - 2. No subsequent allowance for time or money will be considered for any consequence related to failure to examine site conditions.

B. Drawings:

- 1. Mechanical drawings show general arrangement of piping, ductwork, equipment, etc, and do not attempt to show complete details of building construction which affect installation. This Contractor shall refer to architectural, structural, and electrical drawings for additional building detail which affect installation of his work.
 - a. Follow mechanical drawings as closely as actual building construction and work of other trades will permit.
 - b. No extra payments will be allowed where piping and/or ductwork must be offset to avoid other work or where minor changes are necessary to facilitate installation.
 - c. Everything shown on the mechanical drawings shall be the responsibility of Mechanical Contractor unless specifically noted otherwise.
- 2. Consider architectural and structural drawings part of this work insofar as these drawings furnish information relating to design and construction of building. These drawings take precedence over mechanical drawings.
- 3. Because of small scale of mechanical drawings, it is not possible to indicate all offsets, fittings, and accessories which may be required. Investigate structural and finish conditions affecting this work and arrange work accordingly, providing such fittings, valves, and accessories required to meet conditions. Do not scale drawings for locations of equipment or piping. Refer to large scale dimensioned drawings for exact locations.

- C. Insure that items to be furnished fit space available. Make necessary field measurements to ascertain space requirements including those for connections and furnish and install equipment of size and shape so final installation shall suit true intent and meaning of Contract Documents.
 - 1. If approval is received to use other than specified items, responsibility for specified capacities and insuring that items to be furnished will fit space available lies with this Division.
 - 2. If non-specified equipment is used and it will not fit job site conditions, this Contractor assumes responsibility for replacement with items named in Contract Documents.

3.2 PREPARATION

- A. Cut carefully to minimize necessity for repairs to existing work. Do not cut beams, columns, or trusses.
 1. Patch and repair walls, floors, ceilings, and roofs with materials of same quality and appearance as adjacent
 - Surfaces unless otherwise shown. Surface finishes shall exactly match existing finishes of same materials.
 Each Section of this Division shall bear expense of cutting, patching, repairing, and replacing of work of
 - Each section of this Division share bear expense of cutting, patching, repairing, and replacing of v other Sections required because of its fault, error, tardiness, or because of damage done by it.
 Cutting, patching, repairing, and replacing pavements, sidewalks, roads, and curbs to permit insta
 - 3. Cutting, patching, repairing, and replacing pavements, sidewalks, roads, and curbs to permit installation of work of this Division is responsibility of Section installing work.

3.3 INSTALLATION

A. Arrange pipes, ducts, and equipment to permit ready access to valves, unions, traps, starters, motors, control components, and to clear openings of doors and access panels.

3.4 STORAGE AND PROTECTION OF MATERIALS:

- A. Provide storage space for storage of materials and assume complete responsibility for losses due to any cause whatsoever. Storage shall not interfere with traffic conditions in any public thoroughfare.
- B. Protect completed work, work underway, and materials against loss or damage.
- C. Close pipe openings with caps or plugs during installation. Cover fixtures and equipment and protect against dirt, or injury caused by water, chemical, or mechanical accident.

3.5 EXCAVATION AND BACKFILL

- A. Perform necessary excavation of whatever substance encountered for proper laying of all pipes and underground ducts.
 - 1. Excavated materials not required for fill shall be removed from site as directed by Engineer.
 - 2. Excavation shall be carried low enough to allow a minimum coverage over underground piping of 5'-0" or to be below local frost level.
 - 3. Excess excavation below required level shall be backfilled at Contractor's expense with earth, sand, or gravel as directed by Engineer. Tamp ground thoroughly.
 - 4. Ground adjacent to all excavations shall be graded to prevent water running into excavated areas.
- B. Backfill pipe trenches and allow for settlement.
 - 1. Backfill shall be mechanically compacted to same density as surrounding undisturbed earth.
 - 2. Cinders shall not be used in backfilling where steel or iron pipe is used.
 - 3. No backfilling shall be done until installation has been approved by the Engineer.

3.6 COOPERATION

A. Cooperate with other crafts in coordination of work. Promptly respond when notified that construction is ready for installation of work under Division 23000. Contractor will be held responsible for any delays which might be caused by his negligence or failure to cooperate with the other Contractors or crafts.

3.7 SUPERVISION

A. Provide a competent superintendent in charge of the work at all times. Anyone found incompetent shall be removed at once and replaced by someone satisfactory, when requested by the Architect.

3.8 INSTALLATION CHECK:

- A. An experienced, competent, and authorized representative of the manufacturer or supplier of each item of equipment indicated in the equipment schedule shall visit the project to inspect, check, adjust if necessary, and approve the equipment installation. In each case, the equipment supplier's representative shall be present when the equipment is placed in operation. The equipment supplier's representative shall revisit the project as often as necessary until all trouble is corrected and the equipment installation and operation is satisfactory to the Engineer.
- B. Each equipment supplier's representative shall furnish to the Owner, through the Engineer, a written report certifying the following:
 - 1. Equipment has been properly installed and lubricated.
 - 2. Equipment is in accurate alignment.
 - 3. Equipment is free from any undue stress imposed by connecting piping or anchor bolts.
 - 4. Equipment has been operated under full load conditions.
 - 5. Equipment operated satisfactorily.
- C. All costs for this installation check shall be included in the prices quoted by equipment suppliers.

3.9 CLEANING EQUIPMENT AND PREMISES

- A. Properly lubricate equipment before Owner's acceptance.
- B. Clean exposed piping, ductwork, equipment, and fixtures. Repair damaged finishes and leave everything in working order.
- C. Remove stickers from fixtures and adjust flush valves.
- D. At date of Substantial Completion, air filters shall be new, clean, and approved by Owner's representative.
- E. Trap elements shall be removed during cleaning and flushing period. Replace trap elements and adjust after cleaning and flushing period.

3.10 TESTS

- A. No piping work, fixtures, or equipment shall be concealed or covered until they have been inspected and approved by the inspector. Notify inspector when the work is ready for inspection.
- B. All work shall be completely installed, tested as required by Contract Documents and the city and county ordinances and shall be leak-tight before the inspection is requested.
- C. Tests shall be repeated to the satisfaction of those making the inspections.
- D. Water piping shall be flushed out, tested at 100 psi and left under pressure of supply main or a minimum of 40 psi for the balance of the construction period.

3.11 WARRANTEE

- A. Contractor shall guarantee work under Division 23 to be free from inherent defects for a period of one year from acceptance.
 - 1. Contractor shall repair, revise or replace any and all such leaks, failure or inoperativeness due to defective work, materials, or parts free of charge for a period of one year from final acceptance, provided such defect is not due to carelessness in operation or maintenance.
 - 2. In addition, the Contractor shall furnish all refrigeration emergency repairs, emergency service and all refrigerant required due to defective workmanship, materials, or parts for a period of one year from final acceptance at no cost to the Owner, provided such repairs, service and refrigerant are not caused by lack of proper operation and maintenance.
- B. In addition to warrantee specified in General Conditions, heating, cooling, and plumbing systems are to be free from noise in operation that may develop from failure to construct system in accordance with Contract Documents.

3.12 SYSTEM START-UP, OWNER'S INSTRUCTIONS

A. Off-Season Start-up

- 1. If Substantial Completion inspection occurs during heating season, schedule spring start-up of cooling systems. If inspection occurs during cooling season, schedule autumn start-up for heating systems.
- 2. Notify Owner 7 days minimum before scheduled start-up.
- 3. Time will be allowed to completely service, test, check, and off-season start systems. During allowed time, train Owner's representatives in operation and maintenance of system.
- 4. At end of off-season start-up, furnish Owner with letter confirming that above work has been satisfactorily completed.
- B. Owner's Instructions
 - 1. Instruct building maintenance personnel and Owner Representative in operation and maintenance of mechanical systems utilizing Operation & Maintenance Manual when so doing.
 - 2. Minimum instruction periods shall be as follows
 - a. Mechanical Four hours.
 - b. Temperature Control Four hours.
 - c. Refrigeration Two hours.
 - 3. Instruction periods shall occur after Substantial Completion inspection when systems are properly working and before final payment is made.
 - 4. None of these instructional periods shall overlap another.

3.13 **PROTECTION**

- A. Do not run heat pump, air handling units, fan coil units, or other pieces of equipment used for moving supply air without proper air filters installed properly in system.
- B. The mechanical systems are not designed to be used for temporary construction heat. If any equipment is to be started prior to testing and substantial completion, such equipment will be returned to new condition with full one year warranties, from date of substantial completion after any construction use. This includes, but is not necessarily limited to: Equipment, filters, ductwork, fixtures, etc.

3.14 COMMON HVAC REQUIREMENTS:

A. INSTALLATION

- 1. During installation, protect open ends of ducts by covering with plastic sheet tied in place to prevent entrance of debris and dirt.
- 2. Make necessary allowances and provisions in installation of sheet metal ducts for structural conditions of building. Revisions in layout and configuration may be allowed, with prior written approval of Architect. Maintain required airflows in suggesting revisions.
- 3. Hangers And Supports:
 - a. Install pair of hangers close to each transverse joint and elsewhere as required by spacing indicated in table on Drawings.
 - b. Install upper ends of hanger securely to floor or roof construction above by method shown on Drawings.
 - c. Attach strap hangers to ducts with cadmium-plated screws. Use of pop rivets or other means will not be accepted.
 - d. Where hangers are secured to forms before concrete slabs are poured, cut off flush all nails, strap ends, and other projections after forms are removed.
 - e. Secure vertical ducts passing through floors by extending bracing angles to rest firmly on floors without loose blocking or shimming. Support vertical ducts, which do not pass through floors, by using bands bolted to walls, columns, etc. Size, spacing, and method of attachment to vertical ducts shall be same as specified for hanger bands on horizontal ducts.

B. CLEANING

1. Clean interior of duct systems before final completion.

SECTION 23 0553 - IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 **RELATED DOCUMENTS**

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

1.2 **SUMMARY**

- Furnish and install identification of equipment and piping as described in Contract Documents. A.
- Β. Mechanical Contractor shall touch-up equipment where factory paint has been damaged. Repaint entire item where more than 20 percent of the surface is involved.
- C. Primary painting of walls, ceilings, ductwork, piping and plenums is covered in the general painting section of these Contract Documents.

PART 2 - PRODUCTS

2.1 PAINT

- A. Benjamin Moore Impervo or equivalent by Paint Manufacturer approved in Section 09 900.
- Β. Use appropriate primer.

2.2 LABELS

Black Formica with white reveal on engraving. A.

2.3 **CODED BANDS**

- Using colored bands and arrows to indicate supply and return, with colored reflective tape, color code all piping A. installed in this contract at not more than 20-foot intervals, at equipment, at walls, etc., in accordance with ANSI Standards.
- Β. Approved Manufacturers:
 - 1. Seton
 - 2. Craftmark

PIPE IDENTIFICATION 2.4

In addition to the colored bands, stencil with black paint in 1/2 inch high letters a symbol and directional arrow for all A. fluids handled or use Seaton coded and colored pipe markers and arrows to meet ANSI Standards.

2.5 EOUIPMENT IDENTIFICATION

- Provide an engraved plastic plate for each piece of equipment stating the name of the item, symbol number, area A. served, and capacity. Label all control components with plastic embossed mechanically attached labels. Sample:
 - Supply Fan SF-1 North Classrooms 1.
 - 2. 10,000 CFM @ 2.5"

VALVE IDENTIFICATION 2.6

- Make a list of and tag all valves installed in this work. A.
 - Valve tags shall be of brass, not less than 1"x2" size, hung with brass chains. 1.

2. Tag shall indicate plumbing or heating service.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Engraved Plates:
 - 1. Identify thermostats and control panels in mechanical rooms, furnaces, boilers and hot water heating specialties, duct furnaces, air handling units, electric duct heaters, and condensing units with following data engraved and fastened to equipment with screws
 - a. Equipment mark noted on Drawings (i.e., SF-1)
 - b. Area served (i.e., North Classrooms)
 - c. Capacity (10,000 CFM @ 2.5)
- B. Stenciling: 1. Loc
 - Locate identifying legends and directional arrows at following points on each piping system
 - a. Adjacent to each item of equipment and special fitting.
 - b. At point of entry and exit where piping goes through wall.
 - c. On each riser and junction.
 - d. Every 50 feet on long continuous lines.
 - 2. Gas, & Valve Identification
 - a. Identify specific pipe contents by stenciling pipe with written legend and placing of arrows to indicate direction of flow.
- C. Painting:
 - 1. Background Color Provide by continuous painting of piping.

Symbol	Name	Color
NG	Natural Gas	Yellow
FS	Fire Sprinkler	Red
AIR	Air	Blue

2. Identification stenciling and flow arrows shall be following colors for proper contrast:

Arrows & ID Stenciling	Color Shade of Pipe
White	Red, Grays, & black
Black	Yellows, Oranges, Greens, & White

SECTION 23 0593 - TESTING, ADJUSTING, AND BALANCING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Division 23 0501 - Common HVAC Requirements and Basic Mechanical Materials and Methods Sections apply to work of this section.

1.2 SUMMARY SCOPE

- A. This Section includes TAB to produce design objectives for the following:
 - 1. Air Systems.
 - a. Rooftop Units.
 - b. Evaporative Coolers.
 - c. Exhaust fans.

1.3 SUBMITTALS

- A. Agency Data:
 - 1. Submit proof that the proposed testing, adjusting, and balancing agency meets the qualifications specified below. The firm or individuals performing the work herein specified may not be the installing firm.
- B. Engineer and Technicians Data:
 - 1. Submit proof that the Test and Balance Engineer assigned to supervise the procedures, and the technicians proposed to perform the procedures meet the qualifications specified below.
- C. Procedures and Agenda: Submit a synopsis of the testing, adjusting, and balancing procedures and agenda proposed to be used for this project.
- D. Sample Forms: Submit sample forms, if other than those standard forms prepared by the AABC or NEBB are proposed.
- E. Certified Reports: Submit testing, adjusting, and balancing reports bearing the seal and signature of the Test and Balance Engineer. The reports shall be certified proof that the systems have been tested, adjusted, and balanced in accordance with the referenced standards; are an accurate representation of how the systems have been installed; are a true representation of how the systems are operating at the completion of the testing, adjusting, and balancing procedures; and are an accurate record of all final quantities measured, to establish normal operating values of the systems. Follow the procedures and format specified below.
 - 1. Draft Reports: Upon completion of testing, adjusting, and balancing procedures, prepare draft reports on the approved forms. Draft reports may be hand written, but must be complete, factual, accurate, and legible. Organize and format draft reports in the same manner specified for the final reports. Submit 2 complete sets of draft reports. Only 1 complete set of draft reports will be returned.
 - 2. Final Report: Upon verification and approval of draft reports, prepare final reports, type written, and organized and formatted as specified below. Submit 4 complete sets of final reports.
 - 3. Report Format: Report forms shall be those standard forms prepared by the referenced standard for each respective item and system to be tested, adjusted, and balanced. Bind report forms complete with schematic systems diagrams and other data. Divide the contents of the binder into the below listed divisions, separated by divider tabs:
 - a. General Information and Summary
 - b. Air Systems
 - c. Temperature Control System Verification.
- F. Report Contents: Provide the following minimum information, forms, and data:
 - 1. General information and Summary: Inside cover sheet to identify testing, adjusting, balancing agency, Contractor, Owner, Engineer, and Project. Include addresses and contact names and telephone numbers. Also include a certification sheet containing the seal and name, address, telephone number, and signature of the Certified Test and Balance Engineer. Include in this division a listing of the instrumentation used for the procedures along with the instrument calibration sheet.

- 2. The remainder of the report shall contain the appropriate forms containing as a minimum, the information indicated on the standard report forms prepared by the AABC or NEBB, for each respective item and system. Prepare a schematic diagram for each item of equipment and system to accompany each respective report form. The report shall contain the following information, and all other data resulting from the testing, adjusting, and balancing work:
 - a. All nameplate and specification data for all air handling equipment and motors.
 - b. Actual metered running amperage for each phase of each motor on all pumps and air handling equipment.
 - c. Actual metered voltage at air handling equipment (phase-to-phase for all phases).
 - d. Fan RPM for each piece of air handling equipment.
 - e. Total actual CFM being handled by each piece of air handling equipment.
 - f. Actual CFM of systems by rooms.
- 3. Certify that all smoke and fire dampers operate properly and can be reset under actual system operating conditions.
- G. Calibration Reports:
 - 1. Submit proof that all required instrumentation has been calibrated to tolerances specified in the referenced standards, within a period of six months prior to starting the project.

1.4 CERTIFICATION

- A. Agency Qualifications:
 - 1. Employ the services of a certified testing, adjusting, and balancing agency meeting the qualifications specified below, to be the single source of responsibility to test, adjust, and balance the building mechanical systems identified above, to produce the design objectives. Services shall include checking installations for conformity to design, measurement, and establishment of the fluid quantities of the mechanical systems as required to meet design specifications, recording and reporting the results, and operation of all systems to demonstrate satisfactory performance to the owner.
 - 2. The testing, adjusting, and balancing agency certified by National Environmental Balancing Bureau (NEBB) or Associated Air Balance Council (AABC) in those testing and balancing disciplines required for this project, and having at least one person certified by NEBB or AABC as a Test and Balance supervisor, and a registered professional mechanical engineer, licensed in the state where the work will be performed.
- B. Codes and Standard:
 - 1. NEBB: "Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems."
 - 2. AABC: "National Standards for Total System Balance."
 - 3. ASHRAE: ASHRAE Handbook, 1984 Systems Volume, Chapter 37, Testing, Adjusting, and Balancing.

1.5 **PROJECT CONDITIONS**

A. Systems Operation: Systems shall be fully operation and clean prior to beginning procedures.

1.6 SEQUENCING AND SCHEDULING

- A. Test, adjust, and balance the air systems before hydronic, steam, and refrigerant systems within +10% to -5% of contract requirements.
- B. The report shall be approved by the Engineer. Test and balance shall be performed prior to substantial completion.

PART 2 - NOT USED

PART 3 - EXECUTION

3.1 PRELIMINARY PROCEDURES FOR AIR SYSTEM BALANCING

- A. Before operating the system, perform these steps.
 - 1. Obtain design drawings and specifications and become thoroughly acquainted with the design intent.
 - 2. Obtain copies of approved shop drawings of all air handling equipment, outlets (supply, return, and exhaust) and temperature control diagrams.
 - 3. Compare design to installed equipment and field installations.

- 4. Walk the system from the system air handling equipment to terminal units to determine variations of installation from design.
- 5. Check filters for cleanliness and to determine if they are the type specified.
- Check dampers (both volume and fire) for correct and locked position. Check automatic operating and safety controls and devices to determine that they are properly connected, functioning, and at proper operating setpoint.
- 7. Prepare report test sheets for both fans and outlets. Obtain manufacturer's outlet factors and recommended procedures for testing. Prepare a summation of required outlet volumes to permit a cross-check with required fan volumes.
- 8. Determine best locations in main and branch ductwork for most accurate duct traverses.
- 9. Place outlet dampers in the full open position.
- 10. Prepare schematic diagrams of system "As-Built" ductwork and piping layouts to facilitate reporting.
- 11. Lubricate all motors and bearings.
- 12. Check fan belt tension.
- 13. Check fan rotation.

3.2 MEASUREMENTS

- A. Provide all required instrumentation to obtain proper measurements, calibrated to the tolerances specified in the referenced standards. Instruments shall be properly maintained and protected against damage.
- B. Provide instruments meeting the specifications of the referenced standards.
- C. Use only those instruments which have the maximum field measuring accuracy and are best suited to the function being measured.
- D. Apply instrument as recommended by the manufacturer.
- E. Use instruments with minimum scale and maximum subdivisions and with scale ranges proper for the value being measured.
- F. When averaging values, take a sufficient quantity of readings which will result in a repeatability error of less than 5%. When measuring a single point, repeat readings until 2 consecutive identical values are obtained.
- G. Take all readings with the eye at the level of the indicated value to prevent parallax.
- H. Use pulsation dampeners where necessary to eliminate error involved in estimating average of rapidly fluctuation readings.
- I. Take measurements in the system where best suited to the task.

3.3 PERFORMING TESTING, ADJUSTING, AND BALANCING

- A. Perform testing and balancing procedures on each system identified, in accordance with the detailed procedures outlined in the referenced standards. Balancing of the air systems and hydronic systems shall be achieved by adjusting the automatic controls, balancing valves, dampers, air terminal devices, and the fan/motor drives within each system.
- B. Cut insulation, ductwork, and piping for installation of test probes to the minimum extent necessary to allow adequate performance of procedures.
- C. Patch insulation, ductwork, and housings, using materials identical to those removed.
- D. Seal ducts and piping, and test for and repair leaks.
- E. Seal insulation to re-establish integrity of the vapor barrier.
- F. Adjust timing relays of environmental equipment motor reduced voltage starters to the optimum time period for the motor to come up to the maximum reduced voltage speed and then transition to the full voltage speed to prevent

damage to motor, and to limit starting current spike to the lowest possible and practical.

- G. Mark equipment settings, including damper control positions, valve indicators, fan speed control levers, and similar controls and devices, to show final settings. Mark with paint or other suitable, permanent identification materials.
- H. Retest, adjust, and balance systems subsequent to significant system modifications, and resubmit test results.

3.4 RECORD AND REPORT DATA

- A. Record all data obtained during testing, adjusting, and balancing in accordance with, and on the forms recommended by the referenced standards, and as approved on the sample report forms.
- B. Prepare report of recommendations for correcting unsatisfactory mechanical performances when system cannot be successfully balanced.
- C. Report shall be certified and stamped by a registered professional mechanical engineer employed by the agency and licensed in the state where the work will be performed.
- D. Engineer is to provide a floor plan and test and balance contractor to include the plan in test and balance report and identify actual cfm on drawing or number the diffusers to match report.

3.5 DEMONSTRATION

- A. If requested, testing, adjusting, and balancing agency shall conduct any or all of the field tests in the presence of the engineer.
- B. Agency shall include a maximum of one (1) call back to the project within the one year warranty period to make additional adjustments if requested by the engineer.

SECTION 23 0712 - DUCTWORK INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, and Section 23 0501 apply to this Section.

1.2 SUMMARY

- A. Furnish and install insulation on air ducts outside building insulation envelope as described in Contract Documents.
- B. Furnish and install insulation on fresh air ducts and combustion air ducts within building insulation envelope as described in Contract Documents.
- C. Furnish and install insulation on other air ducts where indicated on Drawings.

PART 2 - PRODUCTS

2.1 INSULATION

- A. 1-1/2 inch thick fiberglass with aluminum foil scrim kraft facing and have a density of one lb/cu ft.
- B. Approved Manufacturers:
 - 1. Manville Microlite FSK
 - 2. CSG Type IV standard duct insulation
 - 3. Owens-Corning FRK
 - 4. Knauf (Duct Wrap FSK)

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install duct wrap in accordance with Manufacturer's recommendations.
- B. Do not compress insulation except in areas of structural interference.
- C. Completely seal joints.

SECTION 23 0717 - ROUND SUPPLY DUCT INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

1.2 SUMMARY

A. Furnish and install round supply duct insulation as described in Contract Documents.

1.3 QUALITY ASSURANCE

A. Insulation shall be UL rated with FSK (foil-skrim-kraft) facing.

PART 2 - PRODUCTS

2.1 MANUFACTURED UNITS

- A. Fiberglass blanket insulation
- B. Approved Manufacturers:
 - 1. Johns-Manville R-4 Microlite (R-4 does not include the vapor barrier material).
 - 2. Owens-Corning faced duct wrap insulation FRK-25 ED-150
 - 3. Certainteed Standard Duct Wrap.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Insulate round air supply ducts.
- B. Facing shall overlap 2" at joints and shall be secured with outward clinch staples on 4" centers.
- C. Ducts over 30" in width shall have spot application of adhesive, weld pins or metal screws and caps on not more than 18" centers applied to underside.
- D. 3" wide vapor barrier paper shall be applied over seams and sealed with vapor barrier adhesive.
- E. Insulate attenuators.
- F. Insulate high and low pressure flex ducts.

SECTION 23 0718 - DUCT LINING

PART 1 - GENERAL

RELATED DOCUMENTS 1.1

Drawings, General Provisions of Contract, including General and Supplementary Conditions and other Division 1 A. Specification Sections, and Section 23 0501 apply to this Section.

1.2 SUMMARY

- Furnish and install acoustic lining in following above ground metal ductwork as described in Contract Documents A. unless detailed otherwise:
 - Supply air 1.
 - Return air 2.
 - Mixed air 3.
 - Transfer air 4.
 - 5. Relief air
 - 6. Elbows, fittings, and diffuser drops greater than 12 inches in length.

SYSTEM DESCRIPTION 1.3

Duct dimensions shown on Drawings are for free area inside insulation. Allowance must be made for insulation, A. where applicable.

1.4 **RATINGS:**

Material shall have maximum air friction correction factor of 1.10 at 1000 FPM velocity and have a minimum sound A. absorption coefficient NRC of .60.

PART 2 - PRODUCTS

2.1 DUCT LINER

- One inch thick, 1-1/2 lb density fiberglass, factory edge coated. Α.
- B. Duct lining materials are to meet the requirements of UL 181 for mold, humidity, and erosion resistance.
- C. Approved Manufacturers:
 - Certainteed Ultralite 150 Certa Edge Coat 1.
 - 2. Knauf - Type M
 - Manville Lina-Coustic 3.
 - 4. Owen Corning Fiberglas - Aeroflex

2.2 ADHESIVE

- A. Water Base Type:
 - Cain Hydrotak 1.
 - Duro Dyne WSA 2.
 - 3.
 - Kingco 10-568 Miracle PF-101 4.
 - Mon-Eco 22-67 5.
 - Techno Adhesive 133 6.
- Solvent Base (non-flammable) Type: B.
 - Cain Safetak 1.
 - 2. Duro Dyne - FPG
 - 3. Kingco - 15-137

- 4. Miracle PF-91
- 5. Mon-Eco 22-24
- 6. Techno Adhesive 'Non-Flam' 106
- C. Solvent Base (flammable) Type:
 - 1. Cain HV200
 - 2. Duro Dyne MPG
 - 3. Kingco 15-146
 - 4. Miracle PF-96
 - 5. Mon-Eco 22-22
 - 6. Techno Adhesive 'Flammable' 106

2.3 FASTENERS

- A. Adhesively secured fasteners not allowed.
- B. Approved Manufacturers:
 - 1. AGM Industries Inc "DynaPoint" Series DD-9 pin
 - 2. Cain
 - 3. Duro Dyne
 - 4. Omark dished head "Insul-Pins"
 - 5. Grip nails may be used if each nail is installed by "Grip Nail Air Hammer" or by "Automatic Fastener Equipment" in accordance with Manufacturer's recommendations.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install mat finish surface on air stream side. Secure insulation to cleaned sheet metal duct with continuous 100% coat of adhesive and with 3/4 inch long mechanical fasteners 12 inches on center maximum unless detailed otherwise on Drawings. Pin all duct liner.
- B. Accurately cut liner and thoroughly coat ends with adhesive. Butt joints tightly. Top and bottom sections of insulation shall overlap sides. If liner is all one piece, folded corners shall be tight against metal. Ends shall butt tightly together.
- C. In casings and plenums further contain insulation with wire mesh.

3.2 FIELD QUALITY CONTROL

- A. If insulation is installed without longitudinal and end joints butted together, installation will be rejected and work removed and replaced with work that conforms to this Specification.
- B. Insulation shall be installed in accordance with Duct Liner Application Standard SMACNA Manual 15.

3.3 ADJUSTING, CLEANING

A. Keep duct liner clean and free from dust. At completion of project, vacuum duct liner if it is dirty or dusty.

SECTION 23 0800 - FIRE STOPPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

1.2 SUMMARY

A. Furnish and install fire stopping as described in Contract Documents.

1.3 QUALITY ASSURANCE

A. Fire stopping material shall meet ASTM E814, E84 and be UL listed.

PART 2 - PRODUCTS

2.1 MANUFACTURED UNITS

- A. Material shall be flexible, long lasting, intumescent acrylic seal to accommodate vibration and building movement.
- B. Caulk simple penetrations with gaps of 1/4" or less with:
 - 1. Dow Corning Fire Stop Sealant
 - 2. Pensil 300
- C. Caulk multiple penetrations and/or penetrations with gaps in excess of 1/4" with:
 - 1. Dow Corning Fire Stop Foam
 - 2. Pensil 200
 - 3. IPC flame safe FS-1900
 - 4. Tremco "Tremstop 1A"

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Follow manufacturer's installation instructions explicitly.
- B. Seal penetrations of ductwork, piping, and other mechanical equipment through one-hour and two-hour rated partitions as shown on Architectural and Mechanical Drawings.
- C. Install fire stopping material on clean surfaces to assure adherence.

SECTION 23 0933 – TEMPERATURE CONTROLS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, and Section 23 0501 apply to this Section.

1.2 SUMMARY

- A. Furnish and install a complete electric-electronic system of automatic temperature control as described in Contract Documents.
- B. Control Contractor shall coordinate his work with balancing and start-up Engineer to insure operation of mechanical equipment.
- C. Control Contractor shall be responsible to run control wires and make final connections to control equipment whether furnished by Control Contractor or furnished by Mechanical Contractor with equipment.

1.3 SERVICE AND GUARANTEE

- A. After completion of installation, Automatic Control Contractor shall adjust thermostats, motors and other equipment provided under his contract. He shall place them in complete operating condition subject to approval of Engineer.
- B. Control system specified herein shall be free from defects in workmanship and material under normal use and service. If within twelve months from date of acceptance by Architect and/or Engineer any of equipment herein described is proved to be defective in workmanship or material, it shall be adjusted, repaired, or replaced free of charge by Automatic Control Contractor.

1.4 QUALITY ASSURANCE

A. Wiring shall comply with NEC.

1.5 ELECTRIC WIRING

A. Wiring in connection with automatic control systems, including electrical interlock, shall be furnished and installed by Control Contractor, except as noted on electrical drawings. All wiring shall be run in EMT conduit.

1.6 SUBMITTALS AND INSTRUCTIONS

- A. Temperature Control Contractor shall submit the required number of shop drawings of entire control system to Engineer for approval before starting work.
- B. On completion of work, Temperature Control Contractor shall instruct Owner's operating personnel in proper operation of this system.

PART 2 - PRODUCTS

2.1 CONTROL COMPONENTS

- A. Room Thermostats:
 - 1.
 - 2.
 - Electric-electronic low voltage type. Fully proportional with adjustable throttling range. Automatically change from day to night operation on a change in the time clock. 7 Day Programmable Capability. 3.
 - 4.
 - Approved Manufacturers: 5.
 - Honeywell Prestige Series or Approved Equal. a.
- See Individual Equipment Sections for Further Information. B.

SECTION 23 2300 - REFRIGERANT PIPING SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

1.2 SUMMARY

A. Furnish and install piping for refrigeration systems as described in Contract Documents.

1.3 QUALITY ASSURANCE

- A. Qualifications:
 - 1. Refrigerant piping shall be installed by a refrigeration contractor licensed by State.

PART 2 - PRODUCTS

2.1 REFRIGERANT PIPING

- A. Meet requirements of ASTM B 280-88, "Specification for Seamless Copper Tube for Air Conditioning & Refrigeration Field Service", hard drawn straight lengths.
- B. Do not use pre-charged refrigerant lines.

2.2 REFRIGERANT FITTINGS

- A. Wrought copper with long radius elbows.
- B. Approved Manufacturers:
 - 1. Mueller Streamline
 - 2. Nibco Inc
 - 3. Grinnell
 - 4. Elkhart Products Corp

2.3 SUCTION LINE TRAPS

A. Manufactured standard one-piece traps.

2.4 CONNECTION MATERIAL

- A. Brazing Rods:
 - 1. Copper to Copper Connections:
 - 2. AWS Classification BCuP-4 Copper Phosphorus (6% silver).
 - 3. AWS Classification BCuP-5 Copper Phosphorus (15% silver).
 - 4. Copper to Brass or Copper to Steel Connections:
 - 5. AWS Classification BAg-5 Silver (45% silver).
 - 6. Do not use rods containing Cadmium.

2.5 FLUX

- A. Approved Manufacturers:
 - 1. "Stay-Silv white brazing flux" by J W Harris Co
 - 2. High quality silver solder flux by Handy & Harmon

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Do not install refrigerant piping underground or in tunnels.
- B. Slope suction lines down toward compressor one inch/10 feet. Locate traps at vertical rises against flow in suction lines.
- C. Refrigeration system connections shall be copper-to-copper, copper-to-brass, or copper-to-steel type properly cleaned and brazed with specified rods. Use flux only where necessary.
 - 1. No soft solder (tin, lead, antimony) connections will be allowed in system.
- D. Braze valve, sight glass, and flexible connections.
- E. Circulate dry nitrogen through tubes being brazed to eliminate formation of copper oxide during brazing operation.

3.2 FIELD QUALITY CONTROL

- A. Make evacuation and leak tests in presence of Architect's Engineer after completing refrigeration piping systems. Positive pressure test will not suffice for procedure outlined below.
 - 1. Draw vacuum on each entire system with vacuum pump to 200 microns using vacuum gauge calibrated in microns. Do not use cooling compressor to evacuate system nor operate it while system is under high vacuum. Isolate compressor from system piping using shut-off valves prior to pulling vacuum.
 - 2. Break vacuum with freon to be used and re-establish vacuum test. Vacuum shall hold for 24 hours at 200 microns without compressor running.
 - 3. Conduct tests at 70 deg F ambient temperature minimum.
 - 4. Do not run systems until above tests have been made and systems started up as specified. Inform Owner's Representative of status of systems at time of final inspection and schedule start-up and testing if prevented by outdoor conditions before this time.
 - 5. After testing, fully charge system with refrigerant and conduct test with Halide Leak Detector.

SECTION 23 3114 - LOW-PRESSURE STEEL DUCTWORK

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

1.2 SUMMARY

A. Furnish and install above-grade ductwork and related items as described in Contract Documents.

PART 2 - PRODUCTS

2.1 DUCTS

- A. Fabricate of zinc-coated lockforming quality steel sheets meeting requirements of ASTM 653A/653M, "Specification for Sheet Steel Zinc-Coated (Galvanized) by the Hot-Dip Process, Lock Forming Quality", with G 60 coating.
- B. Use of aluminum, non-metallic, or round ducts is not permitted. [Specification writer: Use of aluminum ducts in areas with high chlorine content (eg.: ventilation for pools, spas, etc.) should be considered on a per job basis.]

2.2 DUCT JOINTS

- A. Ducts with sides up to and including 36 inches shall be as detailed in the SMACNA manual.
- B. Duct sizes over 36 inches shall be fabricated using SMACNA T-24 flange joints or pre-fabricated systems as follows:
 1. Ducts with sides over 36 inches to 48 inches:
 - a. transverse duct joint system by Ductmate/25, Nexus, Ward, or WDCI (Lite) (SMACNA "E" or "G" Type connection).
 - 2. Ducts 48 inches & larger:
 - a. Ductmate/35, Nexus, or WDCI (Heavy) (SMACNA "J" Type connection).
 - 3. Approved Manufacturers:
 - a. Ductmate Industries Inc, 10760 Bay Meadows Drive, Sandy, UT 84092 (801) 571-5308
 - b. Nexus, Exanno Corp, P O Box 729, Buffalo, NY 14206 (716) 849-0545
 - c. Ward Industries Inc, 1661 Lebanon Church Road, Pittsburg, PA 15236 (800) 466-9374
 - d. WDCI, P O Box 10868, Pittsburg, PA 15236 (800) 245-3188

2.3 ACCESS DOORS IN DUCTS

- A. At each manual outside air damper and at each motorized damper, install factory built insulated access door with hinges and sash locks. Locate doors within 6 inches of installed dampers. Construction shall be galvanized sheet metal, 24 ga minimum.
- B. Fire and smoke damper access doors shall have a minimum clear opening of 12" x 12" or as specified on Drawings to easily service fire or smoke damper. Doors shall be within 6 inches of fire and smoke dampers and in Mechanical Room if possible.
- C. Identify each door with 1/2" high letters reading "smoke damper" or "fire damper".
- D. Approved Manufacturers:
 - 1. AirBalance Fire/Seal #FSA 100
 - 2. Air Control Products HAD-10
 - 3. Cesco-Advanced Air HAD-10
 - 4. Elgen Model 85 A
 - 5. Kees Inc ADH-D.
 - 6. Louvers & Dampers #SMD-G-F

- 7. Nailor-Hart Industries Inc Series 0831
- 8. National Controlled Air Inc Model AD-FL-1

2.4 FLEXIBLE EQUIPMENT CONNECTIONS

- A. 30 oz closely woven UL approved glass fabric, double coated with neoprene.
- B. Fire retardant, waterproof, air-tight, resistant to acids and grease, and withstand constant temperatures of 250 deg F.
- C. Approved Manufacturers:
 - 1. Cain N-100
 - 2. Duro Dyne MFN
 - 3. Elgen ZLN
 - 4. Ventfabrics Ventglas

2.5 CONCEALED CEILING DAMPER REGULATORS

- A. Approved Manufacturers:
 - 1. Cain
 - 2. Duro Dyne
 - 3. Metco Inc
 - 4. Vent-Lock #666
 - 5. Young #303

2.6 VOLUME DAMPERS

- A. In Main Ducts:
 - 1. 16 gauge galvanized steel, opposed blade type with 3/8 inch pins and end bearings. Blades shall have 1/8 inch clearance all around.
 - 2. Damper shall operate within acoustical duct liner.
 - 3. Provide channel spacer equal to thickness of duct liner.
 - 4. Approved Manufacturers:
 - a. Air Balance Model AC-2
 - b. Air Control Products CD-OB
 - c. American Warming VC-2-AA
 - d. Greenheck VCD-1100
 - e. NCA, Safe Air
 - f. Vent Products 5100
- B. In Sheet Metal Branch Ducts:
 - 1. Extruded aluminum, opposed blade type. When in open position, shall not extend beyond damper frame.
 - 2. Maximum blade length 12 inches.
 - 3. Damper Regulator shall be concealed type with operation from bottom or with 90 deg miter gear assembly from side.
 - 4. Approved Manufacturers:
 - a. Air Control Products TCD-OB
 - b. Air Guide OB
 - c. Arrow OBDAF-207
 - d. CESCO CDA
 - e. Reliable Metals OBD-RO
 - f. Tuttle & Bailey A7RDDM
 - g. Safe Air
 - h. Young 820-AC
- C. Dampers above removable ceiling and in Mechanical Rooms shall have locking quadrant on bottom or side of duct. Otherwise, provide concealed ceiling damper regulator and cover plate.

2.7 BACKDRAFT DAMPER

A. Backdraft blades shall be nonmetallic and shall be neoprene coated fiberglass.

- B. Stop shall be galvanized steel screen or expanded metal, 1/2 inch mesh.
- C. Frame shall be galvanized steel or extruded aluminum alloy.
- D. Approved Models & Manufacturers:
 - 1. Air Control Products FBD
 - 2. American Warming BD-15
 - 3. CESCO FBD 101
 - 4. Ruskin NMS2
 - 5. Safe Air

2.8 DUCT HANGERS

- A. 1" x 18 gauge galvanized steel straps or steel rods as shown on Drawings, and spaced not more than 8 feet apart. Do not use wire hangers.
- B. Attaching screws at trusses shall be 1-1/2 inch No. 10 round head wood screws. Nails not allowed.

2.9 DUCT SEALER

- A. Cain Duct Butter or Butter Tak
- B. Design Polymerics DP 1010
- C. DSC Stretch Coat
- D. Duro Dyne S2
- E. Hardcast #601 Iron-Grip or Peel-N-Seal Tape
 - 1. Kingco 15-325
 - 2. Mon-Eco 44-41
 - 3. Trans-Continental Equipment Co Multipurpose Duct Sealant
 - 4. United Sheet Metal duct-sealer

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Ducts:
 - 1. Straight and smooth on inside with joints neatly finished unless otherwise directed.
 - 2. Duct panels through 48 inch dimension having acoustic duct liner need not be crossbroken or beaded.
 - 3. Crossbreak unlined ducts and duct panels larger than 48 inch or bead 12 inches on center.
 - 4. Securely anchor ducts to building structure with specified duct hangers attached with screws. Do not hang more than one duct from a duct hanger.
 - 5. Brace and install ducts so they shall be free of vibration under all conditions of operation.
 - 6. Ducts shall not bear on top of structural members.
 - 7. Make duct take-offs to branches, registers, grilles, and diffusers as detailed on Drawings.
 - 8. Ducts shall be large enough to accommodate inside acoustic duct liner. Dimensions shown on Drawings are net clear inside dimensions after duct liner has been installed.
 - 9. Properly flash where ducts protrude above roof.
 - 10. Install internal ends of slip joints in direction of flow. Make joints air tight using specified duct sealer.
 - 11. Cover horizontal and longitudinal joints on exterior ducts with two layers of Hardcast tape installed with Hardcast HC-20 adhesive according to Manufacturer's recommendations.
 - 12. Paint ductwork visible through registers, grilles, and diffusers flat black.
- B. Install flexible inlet and outlet duct connections to each furnace, fan, fan coil unit, and air handling unit.
- C. Install concealed ceiling damper regulators.
 - 1. Paint cover plates to match ceiling tile.

- 2. Damper regulators will not be required for dampers located directly above removable ceilings or in Mechanical Rooms.
- D. Provide each take-off with an adjustable volume damper to balance that branch.
 - 1. Anchor dampers securely to duct.
 - 2. Install dampers in main ducts within insulation.
 - 3. Dampers in branch ducts shall fit against sheet metal walls, bottom and top of duct, and be securely fastened. Cut duct liner to allow damper to fit against sheet metal.
 - 4. Where concealed ceiling damper regulators are installed, provide a cover plate.
- E. Install grilles, registers, and diffusers. Level floor registers and anchor securely into floor.
- F. Air Turns:
 - 1. Permanently installed, consisting of single thickness curved metal blades with one inch straight trailing edge to permit air to make abrupt turn without appreciable turbulence, in 90 degree elbows of above ground supply and return ductwork.
 - 2. 4-1/2 inch wide minimum vane rail. Do not use junior vane rails.
 - 3. Double thickness vanes not acceptable.
 - 4. Quiet and free from vibration when system is in operation. See SMACNA Manual

SECTION 23 3346 - FLEX DUCT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

1.2 SUMMARY

A. Furnish and install supply air branch duct runouts to diffusers as described in Contract Documents.

PART 2 - PRODUCTS

2.1 DUCTS

- A. Formable, flexible, circular duct which shall retain its cross-section, shape, rigidity, and shall not restrict air flow after bending.
- B. Nominal 1-1/2 inches thick, 3/4 lb/cu ft density fiberglass insulation with air-tight, polyehtylene or polyester core, sheathed in seamless vapor barrier jacket factory installed over flexible assembly.
- C. Assembly, including insulation and vapor barrier, shall meet Class I requirement of NFPA 90A and be UL 181 rated, with flame spread of 25 or less and smoke developed rating of 50 or under.
- D. Length of flexible ductwork shall not exceed 8'-0".

2.2 APPROVED MANUFACTURERS

- A. ANCO-FLEX 4625
- B. Flex-Aire PF/UPC #090
- C. Hart & Cooley F114
- D. Thermaflex G-KM

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install duct in fully extended condition free of sags and kinks.
- B. Make duct connections by coating exterior of duct collar for 3 inches with duct sealer and securing duct in place over sheet metal collar with 1/2 inch wide metal cinch bands and sheet metal screws.

SECTION 23 3400 - EXHAUST FANS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

1.2 SUMMARY

A. Furnish and install exhaust fans as described in Contract Documents.

1.3 QUALITY ASSURANCES

A. Requirements of Regulatory Agencies:1. Bear AMCA seal and UL label.

PART 2 - PRODUCTS

2.1 CEILING MOUNTED EXHAUST FANS

- A. Acoustically insulated housings.
- B. Sound level rating of 4.6 sones maximum for fan RPM and CFM listed on Drawings.
- C. Include chatterproof integral back-draft damper with no metal to metal contact.
- D. True centrifugal wheels.
- E. Entire fan, motor, and wheel assembly shall be easily removable without disturbing housing.
- F. Suitably ground motors and mount on rubber-in shear vibration isolators.
- G. Provide wall or roof cap, as required.

H. Approved Manufacturers:

- 1. Cook-Gemini
- 2. Greenheck Sp
- 3. Pace
- 4. Penn Zephyr

2.2 ROOF MOUNTED EXHAUST FANS

- A. Direct drive or have adjustable pitch V-belt as noted on Drawings.
- B. Wheels shall be backward curved and housing shall be removable or hinged aluminum.
- C. Isolate motor with vibration dampeners.
- D. Provide quiet type back-draft dampers.
- E. Insulated, pre-fabricated metal roof curb shall be for flat or sloped roof as shown on Drawings.
- F. Approved Manufacturers:
 - 1. Fans:
 - a. Penn

- b. Centri-Master
- c. Cook
- d. Greenheck G, GB 2.
 - Standard curbs:
 - Penn a.
 - Cook b.
 - Greenheck c.
- Sound attenuating curbs: 3.
 - Penn a.
 - Greenheck b.

PART 3 - EXECUTION

3.1 INSTALLATION

А. Anchor fan units securely to structure or curb.

SECTION 23 3450 - HVAC FANS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

1.2 WORK INCLUDED

A. The ceiling mounted, circulation fan shall be Patterson Fan Co. or approved equal. The fan shall be the model scheduled with the capacities indicated. The fan shall be furnished with standard mounting hardware and variable speed controls.

1.3 RELATED WORK

A. Factory installation services shall be available through the manufacture; consult the appropriate installation scope of work for more information. Installation of the fan, miscellaneous or structural metal work (if required), field electrical wiring, cable, conduit, fuses and disconnect switches other than those not addressed in the installation scope of work consulted, will be provided by others.

PART 2 - PRODUCT

2.1 MANUFACTURER

- A. Patterson Fan Company, 1120 North Point Blvd., Blythewood, SC 29016. Phone (800) 768-3985, Fax (803) 691-4751, Website <u>www.pattersonfan.com</u>.
- B. Delta T Corporation, dba Big Ass Fans, PO Box 11307, Lexington, Kentucky 40575. Phone (877) 244-3267. Fax (859) 233-0139. Website: www.bigassfans.com.

2.2 HIGH VOLUME, LOW SPEED FANS

A. Complete Unit:

- 1. The fan shall be ETL certified and built pursuant to construction guidelines set forth by UL standard 507 and CSA standard 22.2. The fan shall be designed to move an effective amount of air for cooling and destratification in large industrial applications over an extended life. The fan and components shall be designed specifically for high volume, low speed fans to ensure lower noise operation. The sound levels from the fan operating at maximum speed shall not exceed 55 dBA (measured 20' or 6.1 m below the blades and 20' or 6.1 m horizontally from the center of the fan).
- B. Airfoils:
 - 1. The fan shall be equipped with ten (10) high volume, low speed airfoils of precision extruded aluminum alloy. Each airfoil shall be of the high performance Powerfoil design. The airfoils shall be connected by means of two (2) locking bolts per airfoil. The airfoils shall be connected to the hub and interlocked with zinc plated steel retainers.
- C. Winglets:
 - 1. The fan shall be equipped with ten (10) Powerfoil winglets designed to redirect outward airflow into downward airflow, thereby enhancing the efficiency and effectiveness of the fan. The winglets shall be molded of high density polypropylene and nominally measure 8-1/2" x 3" (21.6 cm x 7.6 cm). A winglet shall be attached at the tip of each airfoil by means of a barrel screw. The standard color of the winglets shall be "Safety Yellow."
- D. Motor:
 - 1. The fan motor shall be an AC induction type inverter rated at 1725 RPM, 230/460 VAC, and 60 Hz for 3 φ and 1725 RPM, 208 VAC, and 60 Hz for 1 φ . The motor shall be totally enclosed, fan cooled (TEFC) with an

IP55 NEMA classification. NEMA standard frames 56C/143TC/145TC shall be provided for ease of service. The motor shall be manufactured with a double baked Class F insulation and be capable of continuous operation in -30oF to 122oF (-34oC to 50oC) ambient conditions.

- E. Gearbox:
 - 1. The fan gearbox shall be a NitroSeal[™] Drive designed specifically for the Powerfoil X. The gearbox shall include a high efficiency, hermetically sealed, nitrogen filled, offset helical gear reducer with two stage
 - 2. gearing, a 2-1/2" (6.4 cm) hollow output shaft, cast iron housing, double lip seals, high quality SKF Explorer Series bearings with crowned cages for optimal lubrication flow, and precision machined gearing to maintain backlash less than 11 arc-minutes over the life of the unit. Lubrication shall be a high grade, low foaming synthetic oil with extreme pressure additives and a wide temperature range.
 - 3. The fan gearbox shall be equipped with a passageway in which wiring, piping, etc. can be routed below the fan. A non-rotating, standard junction box shall be provided at the base of the fan for installing optional features such as lights, cameras, and VESDA. An aluminum cover plate shall be provided for attachment to the junction box when these features are not installed.

F. Mounting Post:

1. The fan shall be equipped with a mounting post that provides a structural connection between the fan assembly and upper mounting system. The mounting post shall be 3" x 3" (7.6 cm x 7.6 cm) square tubing and powder coated for corrosion resistance and appearance. As an option, mounting post may be colored as specified by the architect or owner.

G. Hub:

1. The fan hub shall be precision cast aluminum alloy for high strength and light weight. The hub shall be secured to the output shaft of the gearbox by means of a steel flange interface. Both hub and flange shall be precision machined to achieve a well balanced and solid rotating assembly. The hub shall incorporate five (5) safety retaining clips made of 1/4" (0.6 cm) thick steel that shall restrain the hub/airfoil assembly in case of gearbox output shaft failure.

H. Mounting System:

1. The fan mounting system shall be designed for quick and secure installation from a structural support beam. All components in the mounting system shall be of welded construction using low carbon steel no less than 3/16" (0.5 cm) thick and be powder coated for appearance and resistance to corrosion. All mounting bolts shall be SAE Grade 8 or equivalent. As an option, mounting components may be colored as specified by the architect or owner.

I. Safety Cable:

- 1. The fan shall be equipped with a safety cable that provides an additional means of securing the fan assembly to the building structure. The safety cable shall be 3/8" (1 cm) diameter and fabricated out of 7 x 19 stranded galvanized steel. The loops shall be secured with swaged Nicopress fittings, pre-loaded and tested to 3,000 lb f (13,345 N).
- 2. Field construction of safety cables is not permitted.

J. Controller:

- The fan controller shall be constructed using a Variable Speed Drive (VSD) that is pre-wired to the motor and factory programmed to minimize the starting and braking torques, for smooth and efficient operation. The controller shall be prewired to the motor using a short run of flexible conduit THHM with a dedicated ground conductor to minimize electromagnetic interference (EMI) and radio frequency interference (RFI). An incoming power cord shall also be pre-wired to the controller for ease of installation. The controller shall be contained within a completely sealed aluminum enclosure with an IP45 NEMA classification for 3 φ and a NEMA 4/12 rating for 1 φ. The controller will be secured to the mounting post 'onboard' the fan assembly.
- K. Wall Control:
 - 1. The fan shall be equipped with a remote wall control. The wall control shall be a digital keypad device mounted inside an aluminum bezel. The bezel shall be capable of mounting to a standard wall box. The wall control shall be equipped with touchpad controls and an LED display for controlling the fan's direction, operation and speed. Communication with the fan drive and controller shall be by a standard
 - commercially available CAT-5 (or higher) Ethernet cable that is field installed and provided by the installer. A 5' (1.5 m) 'patch cable' shall be provided to test and verify communication signals locally prior to connecting the remote connection cable.

- 3. The wall control shall be equipped with a simple diagnostic program to identify faults in the system. Provisions must be made for retrieving fan operation and diagnostic data (fault messages) through the remote wall device.
- L. Warranty:
 - 1. The manufacturer shall replace any products or components defective in material or workmanship, free of charge to the customer, pursuant to the complete terms and conditions of the Non-Prorated Warranty in accordance to the following schedule:
 - a. Airfoils Lifetime (Parts)
 - b. Hub Lifetime (Parts)
 - c. Motor 10 years (Parts)†
 - d. Gearbox 10 years (Parts)†
 - e. Controller 10 years (Parts)†
 - f. Labor 1 year††
 - g. † 10 year parts warranty only valid with factory installation, 5 year parts without factory installation.
 - h. ^{††} All reasonable costs of repair or replacement will be paid or reimbursed provided customer obtains pre-approval; see full warranty for details.
 - 2. Further information on the terms and conditions of the warranties can be found in the Installation Guide.

PART 3 - ANCILLARY

3.1 INSTALLATION

- A. The fan shall be mounted to an angle iron or I-beam structure. Consult the Installation Guide for acceptable I-beam width, and proper sizing and placement of angle iron for a span mount. A structural engineer must be consulted for installation methods outside the manufacturer's recommendation and a certification submitted prior to installation.
- B. To reduce the risk of injury to persons, the fan shall be installed so that the airfoils are at least 10' (3 m) above the floor. The fan installation area must be free of obstructions such as lights, cables, sprinklers or other building structures; with the airfoils at least 2' (61 cm) clear of all obstructions. The fan should not be installed where it will be continuously subjected to wind gusts or in close proximity to the outputs of HVAC systems.
- C. If the fan is hung from an extension tube that measures 4' (1.2 m) or longer, it may be necessary to provide guy cables or struts to limit potential lateral movement of the fan. A stiffening strut braced against an additional beam may be required if there is a close clearance situation.
- D. The design criteria for the fan mounting system shall be capable of handling 300 ft⁻lbs (407 N⁻m) of torque.

3.2 WORKMANSHIP

A. Good workmanship shall be evident in all aspects of construction. Field balancing of the airfoils shall not be acceptable.

3.3 DOCUMENTATION

- A. The manufacturer shall furnish a copy of all operating and maintenance instructions for the fan.
- B. All data is subject to change without notice. Data indicated in this document are for your convenience and were correct at the time of printing with the exception of clerical and/or printing errors. This document supersedes all previously published documents.

SECTION 23 3713 - AIR OUTLETS & INLETS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

1.2 SUMMARY

A. Furnish and install wall supply registers, transfer grilles, return air grilles, soffit grilles, ceiling diffusers, louvers connected to ductwork, and registers as described in Contract Documents.

PART 2 - PRODUCTS

2.1 GRILLES & REGISTERS

- A. Approved Manufacturers:
 - 1. Price
 - 2. Anemostat
 - 3. Krueger
 - 4. Titus
 - 5. Tuttle & Bailey

B. Wall or Roof Caps:

- 1. Aluminum Architectural style with backdraft damper.
- 2. Category Four Approved Products. See Section 01 6200 for definitions of Categories:
 - a. PennBarry: WC10.

2.2 SPIN-IN FITTINGS

- A. Low pressure round take-offs to diffusers shall be made with spin-in fittings. They shall incorporate a manual balancing damper. The damper shall be spring loaded and a positive locking wing nut shall secure the damper position.
- B. Approved Manufacturers:1. Sheet metal fittings: Genflex DB-1DEL, Hercules

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Anchor securely into openings.
- B. Install with screws to match color and finish of grilles and registers.
- C. Touch-up any scratched finish surfaces.
- D. Install in accordance with manufacturer's instructions.
- E. Check location of outlets and inlets and make necessary adjustments in position to conform with architectural features, symmetry, and lighting arrangement.
- F. Install diffusers to ductwork with air tight connection.

- G. Provide balancing dampers on duct take-off to diffusers, and grilles and registers, despite whether dampers are specified as part of the diffuser, or grille and register assembly.
- H. Paint ductwork visible behind air outlets and inlets matte black. Refer to Section 09 9000.

SECTION 23 4100 – DISPOSABLE FILTERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

1.2 SUMMARY

A. Furnish and install filters used in mechanical equipment.

PART 2 - PRODUCTS

2.1 AIR HANDLING UNIT FILTERS

- A. 2 inch thick, medium efficiency, disposable type pre-formed pleated design, having at least 4.5 sq ft of filtering media per sq ft of face area.
- B. Media shall be reinforced non-woven cotton fabric, treated with adhesive similar to "Vyclad B" and continuously laminated to supporting steel wire grid conforming to configuration of pleats.
- C. Media pack shall be sealed in a chipboard frame or beverage board.
- D. Filters shall have rated average efficiency of 25 to 30% on ASHRAE Test Standard 52-76 and be capable of operating with variable face velocities up to 500 FPM without impairing efficiency.
- E. Initial resistance shall not exceed 0.30 inches w.g. at 500 FPM or 0.14 inch w.g. at 300 FPM. Filter shall be listed Class 2 by UL.
- F. Approved Manufacturers:
 - 1. Type 30/30 by Farr Co
 - 2. Mark 80 by Serv-Aire
 - 3. HC Type 40 by Envopleat
 - 4. DP2-40 by Air Guard

SECTION 23 5134 – FLUES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

1.2 SUMMARY

A. Furnish and install flues as described in Contract Documents.

PART 2 - PRODUCTS

2.1 FLUES

- A. Sections shall be UL listed.
- B. Sections shall have:
 - 1. Outer jacket of aluminum-coated or galvanized steel.
 - 2. One inch minimum insulating air space.
 - 3. Inner gas carrying pipe of stainless steel.
 - 4. Capability of handling flue gas temperatures up to 1400 deg F on continuous basis.
- C. Furnish items which form part of assembly including but not limited to:
 - 1. Bracing and supports as recommended by Flue Manufacturer.
 - 2. Cleanout sections
 - 3. T-sections
 - 4. Necessary straight sections
 - 5. Ventilated roof thimble
 - 6. Flashing and counterflashing
 - 7. 'Backdraft preventer' installed at top of water heater and boiler flues.

D. Approved Manufacturers:

- 1. Metalbestos Model PS
- 2. Metivent Model GTD
- 3. Metal-Fab Inc All Fuel Chimney

2.2 VENT CAPS

- A. Non-backdraft type.
- B. Approved Manufacturers:
 - 1. Ameri-cap
 - 2. Breidert Type L
 - 3. Triangle AFL
 - 4. Acme Mastervent Type MVR.
 - 5. Dura-Vent

SECTION 23 5416 - SEPERATED COMBUSTION UNIT HEATERS

PART 1 - GENERAL

RELATED DOCUMENTS 1.1

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

SUMMARY 1.2

Furnish and install separated combustion unit heaters as described in Contract Documents. A.

PART 2 - PRODUCTS

2.1 MANUFACTURED UNITS

- Α. Provide high-efficiency, separated combustion, gas fired unit heaters as manufactured by Reznor. They are to be designed for a fuel use improvement of 25% and engineered for use in building areas with negative pressure and/or extremely dirty or mildly corrosive atmospheres. The use of a factory-installed power venter to draw combustion air from outside is to prevent dirt, lint, dust, or other contaminants present in the heated space from entering the unit. The combustion air supply pipe and flue exhaust pipe shall be run parallel to a factory-supplied (horizontal), (vertical) vent terminal assembly. The vent terminal assembly shall be arranged to provide preheating of the combustion supply air and to allow a single wall or roof penetration.
- B. The SC series shall be provided with a 24-volt control transformer, a(n) (single-stage), (two-stage), (electronic modulation) gas control system with a regulated combination redundant gas valve and an intermittent spark pilot with electronic flame supervision (and timed lockout). The SC is to include all limit and safety controls, including a combustion air pressure differential switch to verify proper vent flow before allowing operation of the gas valve.
- Each unit shall be equipped for use with (natural), (propane) gas and (120/1), (208/3), (203/3), (460/3) volt power C. supply. The heat exchanger shall be the Reznor Themrocore design of (aluminized), E-3 [408] stainless) steel and include flared ports (burner air shutters) and a stainless steel insert. The units shall be designed for 80% thermal efficiency.
- These units are to be propeller fan(s), open drip-proof fan motor(s) with internal overloads, and safety fan guard(s). D. Horizontal (and vertical) louvers shall be provided for directing air flow. The unit must be arranged for ceiling suspension with threaded hanger connections (and provided with hanger kits). The cabinet shall be constructed of zinc grip steel and finished with baked-on enamel.
- E. All separated-combustion unit heaters must be design-certified by the American Gas Association and bear the A.G.A. label.

1

F. Provide with 7 day programmable thermostat equal to Honeywell Prestige- See Section 23 0933.

SECTION 23 5418 - RADIANT HEATING SYSTEM

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

1.2 SUMMARY

A. Furnish and install radiant heating system as described in Contract Documents.

1.3 QUALITY ASSURANCE

A. Total heating system supplied shall be design certified by the American Gas Association and this per American National Standard Z83.6 - 1987 "Vented Infrared Radiant Heater".

PART 2 - PRODUCTS

2.1 MANUFACTURED UNITS

- A. Burners shall be designed for firing in tandem without adverse effects from combustion gases from upstream burners.
- B. Burners shall be supplied to fire at the design of burners supplied and the design of burners supplied shall provide for maintaining a constant proportion of fuel gas to filtered combustion air. These conditions are met for burners in which the pressure of both fuel gas and combustion air are both introduced at zero (atmospheric) pressure and flow of each is established by a vacuum of downstream side of flow metering orifices.
- C. To assure a high degree of fail-safe operation, the design shall preclude flow of gas if any or all of the following abnormal conditions occur in the non-firing mode:
 - 1. Main valve fails in open position.
 - 2. Vacuum pump motor fails to operate.
 - 3. Power fails.
- D. To further assure a high degree of safety, the system will be under negative pressure at all times during operation to preclude the possibility of the escape of combustion gases inside the building.
- E. All combustion chambers and heat exchanger pipes connected to a vacuum pump shall be pre-purged with air for a period of at least 20 seconds (10 air changes minimum) prior to initiation of firing sequence.
- F. All combustion chambers and heat exchanger pipes connected to a vacuum pump shall be post-purged with air for a period of at least 20 seconds (10 air changes minimum) after shutdown of the last burner firing into the vacuum pump.
- G. All vacuum pump motors shall be provided with vacuum switches to prevent energization of gas valves until vacuum is proven.
- H. Burner: Each burner shall consist of heavy-duty cast iron burner head, pre-wired gas controls with electric ignition and combustion air filter. Each burner and control assembly will be factory equipped with means to attach a safety chain to facilitate safe remove. Each burner will be supplied with a device which will prevent the removal of the burner control doors until the entire burner and control assembly is removed to a work area.
- I. Reflectors: To maximize downward directive release of infrared energy and minimize upward convection losses, all reflectors shall be designed and equipped as follows:
 - 1. Reflectors shall be of "deep dish" design with both lower edges protruding past the bottom of the heat exchanger tube.
 - 2. The end of each reflector run is to be provided with an end cap.

- 3. All heat exchanger elbows and tees shall be covered with a reflector joint piece that connects the reflectors with no spaces allowed for loss of radiant energy.
- J. Vacuum Pump: The housing shall be heavy-duty cast iron. The impeller shall be cast aluminum alloy dynamically balanced and mounted for direct drive on the motor shaft. The vacuum pump shall be acoustically isolated from the system with a flexible connector with temperature rating of 350 deg. F. minimum. The motor in the vacuum pump shall be secured with rubber mounts for acoustical isolation. Vacuum pump motor shall be 230/115V, 60 Hz, 3450 RPM, reversible rotation, with at least 3/4 HP, TEFC capacitor start, ball bearing and thermally protected.
- K. Heat Exchanger: Radiant pipe (between burners and 20 feet downstream of last burner) shall be of 4" O.D. steel pipe (i.e. tubing). The balance of pipe shall be 4" O.D. steel tubing with an internal coating of acid-resistant porcelain. All heat exchanger (pipe) connections shall be made with stainless steel coupling assemblies. These will be of two types as follows: Unlined coupling for use with uncoated tubing or joints to connect uncoated tubing to coated tubing. The maximum input firing rate shall not exceed 2,400 BTU per hour per square foot of exterior radiating surface of heat exchanger for the heating system in total. The total heat exchanger surface is that associated with one vacuum pump.
- L. Burner Control Modules: All burners shall be pre-wired with a three conductor electrical cord and plug with the third wire for ground circuit.
- M. Panel box for System Controls: Pre-wired system control circuits shall be supplied in a panel box with each vacuum pump. The panel box for the standard burners shall provide relays and terminals to accommodate up to four temperature zones with a thermostat and associated control circuits for the burners for each temperature zone. Provide complete with one thermostat.
- N. Provide with 7 day programmable thermostat equal to Honeywell Prestige. See Section 23 0933
- O. Approved Manufacturers:
 - 1. Superior Radiant
 - 2. or approved equal

SECTION 23 6210 - EVAPORATIVE AIR COOLING EQUIPMENT

PART 1 - GENERAL

1.1 SUMMARY

- A. Includes But Not Limited To: Furnish and install rooftop evaporative air handlers as described in Contract Documents. 1.
- Β. **Related Sections:** Section 23 0501: Common HVAC Requirements. 1.

1.2 **DELIVERY, STORAGE, AND HANDLING**

Α. Ship units with lifting sky hooks.

PART 2 - PRODUCTS

2.1 MANUFACTURED UNITS

- A. Units shall be completely factory assembled and tested. UL507 listed.
- B. Units shall include following components and features
 - 1. Casing:
 - a. Hot-dipped galvanized steel with epoxy powder coat finish. Double thick corners.
 - Unit braced by factory supplied support legs. b.
 - Curb and curb counter-flashing. c.
 - d. Auto-damper with grille diffuser.
 - Provide easy access to external distributor clean outs. e.
 - Height from top of curb to top of unit 3 feet maximum. f.
 - Provide make-up water, over-flow drain, and power utilities through bottom of unit and within curb. g.
 - 2. Fan:
 - Axial, propeller type fan, dynamically balanced and with corrosion resistant finish. Down discharge. a. Self-aligning, heavy duty, greaseable, pillow block, ball bearing.
 - Belt driven, keyed steel shaft with self-tensioning belt. b.
 - Adjustable motor sheave. c.
 - d. Provide slide frame accessibility to fan, motor and drive.
 - Motor: Totally enclosed for wet environment. 3.
 - Pads: 8 inch thick cross-fluted 80 percent efficient media with side access removal. 4.
 - Water Distribution: 5.
 - a. Provide distribution system for uniform flow thru media.
 - Centrifugal pump. b.
 - Cold water make-up valve with float. C.
 - Performance Standard: United Metal Products, 'FAN-AIR' UMP-724 with UFD33-2 diffuser and full size 6. barometric damper.
 - 7. Type One Acceptable Manufacturers:
 - United Metal Products, Tempe, AZ www.unitedmetal.com. a.
 - Equal as approved by Architect before bidding. See Section 01 6200. b.
 - 8. Units to be controlled from Manual Evaporative Cooler Thermostat with high/low fan operation, pump on/off, vent only options as recommended by equipment manufacturer. See section 23 0933.

1

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install units on factory supplied curb. Completely enclose wiring and piping within curb. Penetrations through curbs and roofing membrane are not allowed.
- B. Install barometric damper in discharge duct.
- C. Coordinate attachment of cooler support legs with Architect. Anchor leg supports to roof structure. However, attachment shall not distract from roofing system's integrity nor impact life expectancy of roofing system.
- D. Coat non-finished or unprotected surfaces with two coats of approved corrosion-resistant paint after installation. Color as selected by Architect.

SECTION 23 6220 - ROOFTOP HEATING-COOLING UNIT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

1.2 QUALITY ASSURANCE

A. Unit shall be AGA certified.

1.3 WARRANTY

A. Provide five-year warranty on compressors.

PART 2 - PRODUCTS

2.1 MANUFACTURED UNITS

- A. Unit shall be one piece combination air-to-air DX mechanical cooling system and gas fired heating system complete with automatic controls.
- B. Equipment shall be shipped completely assembled, pre-charged, piped and wired internally ready for field connections.
- C. Roof mounting frame shall be furnished and installed. Frame shall be steel and mate to bottom perimeter of equipment. When flashed into roof, it shall make a unit mounting curb and provide weather-proof duct connection and entry into conditioning area.
- D. Power Saver: (Fresh Air Dampers)
 - 1. Provide complete with all controls and air mixing damper assembly, including fresh air, recirculated air, and exhaust air dampers.
 - 2. Fresh air section shall be equipped with air filters.
 - 3. Mixing box sections shall contain low leakage dampers with edge seals and inflatable blade seals.

E. Cooling System:

- 1. Coils shall be non-ferrous construction with aluminum fins mechanically bonded to seamless copper tubes.
- 2. Condenser coil shall have sub-cooling rows.
- 3. Compressor shall be resiliently mounted, have built-in 3-mode crankshaft lubrication, crankcase heater, discharge temperature limiter, current and temperature sensing motor overloads.
- 4. Cooling system shall be protected by high and low pressure switches and compressor timed off control.
- 5. Provide with hail guard over condenser coil.
- F. Heating System:
 - 1. Automatic controls furnished to give 50/50 2-stage operation.
 - 2. Cylindrical tube and drum exchanger constructed of Duraglass coated steel or stainless steel.
 - 3. Stainless steel burner listed for operation at low outdoor air temperatures.
 - 4. Visual inspection of burner flame possible through observation port at rear of heat exchanger.
 - 5. Power vented.
- G. Air Movers:
 - 1. Twin centrifugal conditioned air blowers with permanently lubricated ball bearings, adjustable belt drive or direct drive as shown on drawings.
 - 2. Condenser fans shall be direct driven.
 - 3. Motors shall have inherent protection devices.

- H. Frame and Casing:
 - 1. Frame shall be welded construction.
 - 2. Casing shall be galvanized panels with baked-on outdoor enamel finish.
 - 3. Entire cabinet shall be insulated with 1" thick fiberglass.
 - 4. Provide coil guards on exposed condenser coils.
- I. Furnish two sets of 2" throw away filters.
- J. Provide with 7 day programmable thermostat equal to Honeywell Prestige. See Section 23 0933.
- K. Approved Manufacturers:
 - 1. Lennox
 - 2. Trane
 - 3. Carrier
 - 4. York

PART 3 - EXECUTION

- 3.1 FIELD QUALITY CONTROL
 - A. Provide manufacturer's startup and warranty.

SECTION 23 8127 - SPLIT-SYSTEM HEATING AND COOLING

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Indoor ductless fan & coil units.

1.2 **RELATED REQUIREMENTS**

- A. Section 22 1005 - Plumbing Piping: Indoor coil condensate drain.
- Section 26 0519 Line-Voltage Electrical Power Conductors and Cables: Electrical characteristics and wiring B.

connections and installation and wiring of thermostats and other controls components.

1.3 **REFERENCE STANDARDS**

- AHRI 210/240 Standard for Performance Rating of Unitary Air Conditioning and Air-Source Heat Pump Α. Equipment; Air-Conditioning, Heating, and Refrigeration Institute; 2008.
- B. AHRI 270 - Sound Rating of Outdoor Unitary Equipment; Air-Conditioning, Heating, and Refrigeration Institute; 2008
- C. ASHRAE Std 15 - Safety Standard for Refrigeration Systems; American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc.; 2010 (ANSI/ASHRAE Std 15).
- NEMA MG 1 Motors and Generators; National Electrical Manufacturers Association; 2015, Revision 1 2010. D.
- E. NFPA 90A - Standard for the Installation of Air-Conditioning and Ventilating Systems; National Fire Protection Association; 2015.
- F. UL 207 - Refrigerant-Containing Components and Accessories, Nonelectrical; Underwriters Laboratories Inc.;

Current Edition, Including All Revisions.

1.4 SUBMITTALS

- A. See Section 01 3300 - for submittal procedures.
- B. Product Data: Provide rated capacities, weights, accessories, electrical nameplate data, and wiring diagrams.
- C. Shop Drawings: Indicate assembly, required clearances, and location and size of field connections.
- D. Design Data: Indicate refrigerant pipe sizing.
- E. Manufacturer's Instructions: Indicate rigging, assembly, and installation instructions.
- F. Operation and Maintenance Data: Include manufacturer's descriptive literature, operating instructions, installation instructions, maintenance and repair data, and parts listing.
- Warranty: Submit manufacturer's warranty and ensure forms have been filled out in Owner s name and registered G. with manufacturer.
- H. Maintenance Materials: Furnish the following for Owner's use in maintenance of project. 1. Substitutions: See Section 01 2500.

1.5 QUALITY ASSURANCE

- Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, A. with minimum three years of documented experience.
- B. Installer Qualifications: Company specializing in performing the work of this section with minimum 3 years of experience and approved by manufacturer.

WARRANTY 1.6

- See Section 01 7700 Closeout Procedures, for additional warranty requirements. A.
- B. Provide five year manufacturer's warranty for compressors.

23 8127

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Mitsubishi: www.mitsubish.com.
- B. Sanyo: www.sanyo.com.
- C. Daikin: www.dainkin.com.
- D. LG: www.lg.com.

2.2 SYSTEM DESIGN

- A. Split-System Heating and Cooling Units: Self-contained, packaged, matched factory-engineered and assembled, prewired indoor and outdoor units; UL listed.
 - 1. Heating and Cooling: Air-source electric heat pump located in outdoor unit with evaporator.
 - 2. Provide refrigerant lines internal to units and between indoor and outdoor units, factory cleaned, dried, pressurized and sealed, with insulated suction line.
- B. Performance Requirements: See Drawings for additional requirements.
 - 1. Efficiency:
 - a. Seasonal Energy Efficiency Ratio: 10.0, minimum.
 - b. Energy Efficiency Ratio: 12.
 - c. Heating Seasonal Performance Factor: 6.8, minimum.

2.3 INDOOR UNITS FOR DUCTLESS SYSTEMS

- A. Indoor Units: Self-contained, packaged, factory assembled, pre-wired unit consisting of cabinet, supply fan, evaporator coil, and wall mounted controls; wired for single power connection with control transformer.
 - 1. Location: Ceiling or wall.
 - 2. Power: Run from outdoor unit.
 - 3. Cabinet: Galvanized steel.
 - a. Finish: White.
 - 4. Fan: Line-flow fan direct driven by a single motor.
 - 5. Filter return air with washable, antioxidant pre-filter and a pleated anti-allergy enzyme filter.
- B. Evaporator Coils: Copper tube aluminum fin assembly, galvanized or polymer drain pan sloped in all directions to drain, drain connection, refrigerant piping connections, restricted distributor or thermostatic expansion valve.
 - 1. Construction and Ratings: In accordance with AHRI 210/240 and UL listed.
 - 2. Manufacturer: System manufacturer.
- C. Remote: Wall mounted controller/thermostat.

2.4 OUTDOOR UNITS

- A. Outdoor Units: Self-contained, packaged, pre-wired unit consisting of cabinet, with compressor and condenser.
 - 1. Comply with AHRI 210.
 - 2. Refrigerant: R-410A.
 - 3. Cabinet: Galvanized steel with baked enamel finish, easily removed and secured access doors with safety interlock switches, glass fiber insulation with reflective liner.
 - 4. Construction and Ratings: In accordance with AHRI 210/240 with testing in accordance with ASHRAE Std 23 and UL listed.
 - 5. Sound Rating: 69 dBA, when measured in accordance with AHRI 270.
- B. Compressor: AHRI 520; hermetic, two speed 1800 and 3600 rpm, resiliently mounted integral with condenser, with positive lubrication, crankcase heater, high pressure control, motor overload protection, service valves and drier. Provide time delay control to prevent short cycling and rapid speed changes.
- C. Air Cooled Condenser: ARI 520; Aluminum fin and copper tube coil, with direct drive axial propeller fan resiliently mounted, galvanized fan guard.
 - 1. Condenser Fans: Direct-drive propeller type.
 - 2. Condenser Fan Motor: Enclosed, 1-phase type, permanently lubricated.
- D. Coil: Air-cooled, aluminum fins bonded to copper tubes.
- E. Accessories: Filter drier, high pressure switch (manual reset), low pressure switch (automatic reset), service valves and gage ports, thermometer well (in liquid line).
 - 1. Provide thermostatic expansion valves.
 - 2. Provide heat pump reversing valves.

- F. Operating Controls:
 - 1. Control by room thermostat to maintain room temperature setting.
 - 2. Low Ambient Kit: Provide refrigerant pressure switch to cycle condenser fan on when condenser refrigerant pressure is above 285 psig (1965 kPa) and off when pressure drops below 140 psig (965 kPa) for operation to 0 degrees F (-18 degrees C).
- G. Mounting Pad: Roof mounted curb to maintain units 12 inches above roofing. Cover curb with roofing material and maintain roof integrity.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify that substrates are ready for installation of units and openings are as indicated on shop drawings.
- B. Verify that proper power supply is available and in correct location.

3.2 INSTALLATION

- A. Install in accordance with manufacturer's instructions and requirements of local authorities having jurisdiction.
- B. Install in accordance with NFPA 90A and NFPA 90B.
- C. Install refrigeration systems in accordance with ASHRAE Std 15.

END OF SECTION 23 8127

END OF DIVISION 23