

**DIVISION 23: HEATING, VENTILATING, AND AIR-CONDITIONING**

**23 0000 HEATING, VENTILATING, AND AIR-CONDITIONING**

23 0501 COMMON HVAC REQUIREMENTS  
23 0502 DEMOLITION AND REPAIR  
23 0553 IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT  
23 0593 TESTING, ADJUSTING, AND BALANCING  
23 0712 MECHANICAL INSULATION AND FIRE STOPPING  
23 0716 DUCTWORK INSULATION  
23 0717 ROUND SUPPLY DUCT INSULATION  
23 0718 DUCT LINING  
23 0800 FIRE STOPPING

**23 2000 HVAC PIPING AND PUMPS**

23 2113 HYDRONIC PIPING  
23 2200 WATER SOURCE HEAT PUMP SYSTEM  
23 2600 CONDENSATE DRAIN PIPING

**23 3000 HVAC AIR DISTRIBUTION**

23 3114 LOW-PRESSURE STEEL DUCTWORK  
23 3346 FLEX DUCT  
23 3713 AIR OUTLETS & INLETS

**END TABLE OF CONTENTS**

## SECTION 23 0501 – COMMON HVAC REQUIREMENTS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and General Provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Furnish labor, materials, and equipment necessary for completion of work as described in Contract Documents.
- B. It is the intent of these specifications that the systems specified herein are to be complete and operational before being turned over to the owner. During the bidding process, the contractor is to ask questions or call to the engineer's attention any items that are not shown or may be required to make the system complete and operational. Once the project is bid and the contractor has accepted the contract, it is his responsibility to furnish and install all equipment and parts necessary to provide a complete and operational system without additional cost to the owner.
- C. Furnish and install fire stopping materials to seal penetrations through fire rated structures and draft stops.
- D. Includes But Not Limited To:
  - 1. General procedures and requirements for HVAC.
- E. Related Sections:
  - 1. Section 23 0593: Testing, Adjusting, and Balancing for HVAC.

#### 1.3 SUBMITTALS

- A. Substitutions: By specific designation and description, standards are established for specialties and equipment. Other makes of specialties and equipment of equal quality will be considered provided such proposed substitutions are submitted to the Architect for his approval, complete with specification data showing how it meets the specifications, at least 5 working days prior to bid opening. A list of approved substitutions will be published as an addendum.
  - 1. Submit a single copy of Manufacturer's catalog data including Manufacturer's complete specification for each proposed substitution.
  - 2. The Architect or Engineer is to be the sole judge as to the quality of any material offered as an equal.
- B. Product Data, Shop Drawings: Within 30 days after award of contract, submit 10 sets of Manufacturer's catalog data for each manufactured item.
  - 1. Literature shall include enough information to show complete compliance with Contract Document requirements.
  - 2. Mark literature to indicate specific item with applicable data underlined.

3. Information shall include but not be limited to capacities, ratings, type of material used, guarantee, and such dimensions as are necessary to check space requirements.
  4. When accepted, submittal shall be an addition to Contract Documents and shall be in equal force. No variation shall be permitted.
  5. Even though the submittals have been accepted by the Engineer, it does not relieve the contractor from meeting all of the requirements of the plans and specifications and providing a complete and operational system.
- C. Drawings of Record: One complete sets of blue line mechanical drawings shall be provided for the purpose of showing a complete picture of the work as actually installed.
1. These drawings shall serve as work progress report sheets. Contractor shall make notations neat and legible therein daily as the work proceeds.
  2. The drawings shall be kept at the job at a location designated by the Mechanical Engineer.
  3. At completion of the project these "as-built" drawings shall be signed by the Contractor, dated, and returned to the Architect.
- D. Operating Instructions and Service Manual: The Mechanical Contractor shall prepare 2 copies of an Operation and Maintenance Manual for all mechanical systems and equipment used in this project. Manuals shall be bound in hard-backed binders and the front cover and spine of each binder shall indicate the name and location of the project. Use plastic tab indexes for all sections. Provide a section for each different type of equipment item. The following items shall be included in the manual, together with any other pertinent data. This list is not complete and is to be used as a guide.
1. Provide a master index at the beginning of the manual showing all items included.
  2. The first section of the manual shall contain:
    - a. Names, addresses, and telephone numbers of Architect, Mechanical Engineer, Electrical Engineer, General Contractor, Plumbing Contractor, Sheet Metal Contractor, and Temperature Control Contractor.
    - b. List of Suppliers which shall include a complete list of each piece of equipment used with the name, address, and telephone number of vendor.
    - c. General Description of Systems including –
      - 1) Location of all major equipment
      - 2) Description of the various mechanical systems
      - 3) Description of operation and control of the mechanical systems
      - 4) Suggested maintenance schedule
    - d. Copy of contractor's written warranty
  3. Provide a copy of approved submittal literature for each piece of equipment.
  4. Provide maintenance and operation literature published by the manufacturer for each piece of equipment which includes: oiling, lubrication and greasing data; belt sizes, types and lengths; wiring diagrams; step-by-step procedure to follow in putting each piece of mechanical equipment in operation.
  5. Include parts numbers of all replaceable items.
  6. Provide control diagram and operation sequence, along with labeling of control piping and instruments to match diagram.
  7. Include a valve chart indicating valve locations.
- E. Include air balance and/or water balance reports.

#### 1.4 SUBMITTALS FOR COMMON HVAC REQUIREMENTS

- A. Samples: Sealer and gauze proposed for sealing ductwork.
- B. Quality Assurance / Control:
  - 1. Manufacturer's installation manuals providing detailed instructions on assembly, joint sealing, and system pressure testing for leaks.
  - 2. Specification data on sealer and gauze proposed for sealing ductwork.
- C. Quality Assurance
  - 1. Requirements: Construction details not specifically called out in Contract Documents shall conform to applicable requirements of SMACNA HVAC Duct Construction Standards.
  - 2. Pre-Installation Conference: Schedule conference immediately before installation of ductwork.

#### 1.5 QUALITY ASSURANCE

- A. Requirements of Regulatory Agencies:
  - 1. Perform work in accordance with applicable provisions of local and state Plumbing Code, Gas Ordinances, and adoptions thereof. Provide materials and labor necessary to comply with rules, regulations, and ordinances.
  - 2. In case of differences between building codes, state laws, local ordinances, utility company regulations, and Contract Documents, the most stringent shall govern. Promptly notify Architect in writing of such differences.
- B. Applicable Specifications: Referenced specifications, standards, and publications shall be of the issues in effect on date of Advertisement for Bid.
  - 1. "Heating, Ventilating and Air Conditioning Guide" published by the American Society of Heating and Air Conditioning Engineers.
  - 2. "Engineering Standards" published by the Heating, Piping, and Air Conditioning Contractors National Association.
  - 3. "2015 International Building Code", "2015 International Mechanical Code", "2015 International Plumbing Code" and "2015 International Fire Code" as published by the International Conference of Building Officials.
  - 4. "National Electrical Code" as published by the National Fire Protection Association.
  - 5. "2015 International Energy Conservation Code".
- C. Identification: Motor and equipment name plates as well as applicable UL and AGA labels shall be in place when Project is turned over to Owner.

#### 1.6 INSPECTIONS AND PERMITS

- A. Pay for permits, fees, or charges for inspection or other services. Local and state codes and ordinances must be properly executed without expense to Owner and are considered as minimum requirements. Local and state codes and ordinances do not relieve the Contractor from work shown that exceeds minimum requirements.

#### 1.7 ADDITIONAL WORK:

- A. Design is based on equipment as described in the drawing equipment schedule. Any

change in foundation bases, electrical wiring, conduit connections, piping, controls and openings required by alternate equipment submitted and approved shall be paid for by this division. All work shall be in accordance with the requirements of the applicable sections.

## PART 2 - PRODUCTS FOR COMMON HVAC REQUIREMENTS

- A. Finishes, Where Applicable: Colors as selected by Architect.
- B. Duct Hangers:
  - 1. One inch 25 mm by 18 ga 1.27 mm galvanized steel straps or steel rods as shown on Drawings, and spaced not more than 96 inches 2 400 mm apart. Do not use wire hangers.
  - 2. Attaching screws at trusses shall be 2 inch 50 mm No. 10 round head wood screws. Nails not allowed.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Site Inspection:
  - 1. Examine premises and understand the conditions which may affect performance of work of this Division before submitting proposals for this work.
  - 2. No subsequent allowance for time or money will be considered for any consequence related to failure to examine site conditions.
- B. Drawings:
  - 1. Mechanical drawings show general arrangement of piping, ductwork, equipment, etc, and do not attempt to show complete details of building construction which affect installation. This Contractor shall refer to architectural, structural, and electrical drawings for additional building detail which affect installation of his work.
    - a. Follow mechanical drawings as closely as actual building construction and work of other trades will permit.
    - b. No extra payments will be allowed where piping and/or ductwork must be offset to avoid other work or where minor changes are necessary to facilitate installation.
    - c. Everything shown on the mechanical drawings shall be the responsibility of Mechanical Contractor unless specifically noted otherwise.
  - 2. Consider architectural and structural drawings part of this work insofar as these drawings furnish information relating to design and construction of building. These drawings take precedence over mechanical drawings.
  - 3. Because of small scale of mechanical drawings, it is not possible to indicate all offsets, fittings, and accessories which may be required. Investigate structural and finish conditions affecting this work and arrange work accordingly, providing such fittings, valves, and accessories required to meet conditions. Do not scale drawings for locations of equipment or piping. Refer to large scale dimensioned drawings for exact locations.
- C. Insure that items to be furnished fit space available. Make necessary field measurements to ascertain space requirements including those for connections and furnish and install equipment of size and shape so final installation shall suit true intent

and meaning of Contract Documents.

1. If approval is received to use other than specified items, responsibility for specified capacities and insuring that items to be furnished will fit space available lies with this Division.
2. If non-specified equipment is used and it will not fit job site conditions, this Contractor assumes responsibility for replacement with items named in Contract Documents.

### 3.2 PREPARATION

- A. Cut carefully to minimize necessity for repairs to existing work. Do not cut beams, columns, or trusses.
  1. Patch and repair walls, floors, ceilings, and roofs with materials of same quality and appearance as adjacent surfaces unless otherwise shown. Surface finishes shall exactly match existing finishes of same materials.
  2. Each Section of this Division shall bear expense of cutting, patching, repairing, and replacing of work of other Sections required because of its fault, error, tardiness, or because of damage done by it.
  3. Cutting, patching, repairing, and replacing pavements, sidewalks, roads, and curbs to permit installation of work of this Division is responsibility of Section installing work.

### 3.3 INSTALLATION

- A. Arrange pipes, ducts, and equipment to permit ready access to valves, unions, traps, starters, motors, control components, and to clear openings of doors and access panels.

### 3.4 STORAGE AND PROTECTION OF MATERIALS:

- A. Provide storage space for storage of materials and assume complete responsibility for losses due to any cause whatsoever. Storage shall not interfere with traffic conditions in any public thoroughfare.
- B. Protect completed work, work underway, and materials against loss or damage.
- C. Close pipe openings with caps or plugs during installation. Cover fixtures and equipment and protect against dirt, or injury caused by water, chemical, or mechanical accident.

### 3.5 EXCAVATION AND BACKFILL

- A. Perform necessary excavation of whatever substance encountered for proper laying of all pipes and underground ducts.
  1. Excavated materials not required for fill shall be removed from site as directed by Engineer.
  2. Excavation shall be carried low enough to allow a minimum coverage over underground piping of 5'-0" or to be below local frost level.
  3. Excess excavation below required level shall be backfilled at Contractor's expense with earth, sand, or gravel as directed by Engineer. Tamp ground thoroughly.

4. Ground adjacent to all excavations shall be graded to prevent water running into excavated areas.

B. Backfill pipe trenches and allow for settlement.

1. Backfill shall be mechanically compacted to same density as surrounding undisturbed earth.
2. Cinders shall not be used in backfilling where steel or iron pipe is used.
3. No backfilling shall be done until installation has been approved by the Engineer.

### 3.6 COOPERATION

A. Cooperate with other crafts in coordination of work. Promptly respond when notified that construction is ready for installation of work under Division 23000. Contractor will be held responsible for any delays which might be caused by his negligence or failure to cooperate with the other Contractors or crafts.

### 3.7 SUPERVISION

A. Provide a competent superintendent in charge of the work at all times. Anyone found incompetent shall be removed at once and replaced by someone satisfactory, when requested by the Architect.

### 3.8 INSTALLATION CHECK:

A. An experienced, competent, and authorized representative of the manufacturer or supplier of each item of equipment indicated in the equipment schedule shall visit the project to inspect, check, adjust if necessary, and approve the equipment installation. In each case, the equipment supplier's representative shall be present when the equipment is placed in operation. The equipment supplier's representative shall revisit the project as often as necessary until all trouble is corrected and the equipment installation and operation is satisfactory to the Engineer.

B. Each equipment supplier's representative shall furnish to the Owner, through the Engineer, a written report certifying the following:

1. Equipment has been properly installed and lubricated.
2. Equipment is in accurate alignment.
3. Equipment is free from any undue stress imposed by connecting piping or anchor bolts.
4. Equipment has been operated under full load conditions.
5. Equipment operated satisfactorily.

C. All costs for this installation check shall be included in the prices quoted by equipment suppliers.

### 3.9 CLEANING EQUIPMENT AND PREMISES

A. Properly lubricate equipment before Owner's acceptance.

B. Clean exposed piping, ductwork, equipment, and fixtures. Repair damaged finishes and leave everything in working order.

C. Remove stickers from fixtures and adjust flush valves.

- D. At date of Substantial Completion, air filters shall be new, clean, and approved by Owner's representative.
- E. Trap elements shall be removed during cleaning and flushing period. Replace trap elements and adjust after cleaning and flushing period.

### 3.10 TESTS

- A. No piping work, fixtures, or equipment shall be concealed or covered until they have been inspected and approved by the inspector. Notify inspector when the work is ready for inspection.
- B. All work shall be completely installed, tested as required by Contract Documents and the city and county ordinances and shall be leak-tight before the inspection is requested.
- C. Tests shall be repeated to the satisfaction of those making the inspections.
- D. Water piping shall be flushed out, tested at 100 psi and left under pressure of supply main or a minimum of 40 psi for the balance of the construction period.

### 3.11 WARRANTY

- A. Contractor shall guarantee work under Division 23 to be free from inherent defects for a period of one year from acceptance.
  - 1. Contractor shall repair, revise or replace any and all such leaks, failure or inoperativeness due to defective work, materials, or parts free of charge for a period of one year from final acceptance, provided such defect is not due to carelessness in operation or maintenance.
  - 2. In addition, the Contractor shall furnish all refrigeration emergency repairs, emergency service and all refrigerant required due to defective workmanship, materials, or parts for a period of one year from final acceptance at no cost to the Owner, provided such repairs, service and refrigerant are not caused by lack of proper operation and maintenance.
- B. In addition to warranty specified in General Conditions, heating, cooling, and plumbing systems are to be free from noise in operation that may develop from failure to construct system in accordance with Contract Documents.

### 3.12 SYSTEM START-UP, OWNER'S INSTRUCTIONS

- A. Off-Season Start-up
  - 1. If Substantial Completion inspection occurs during heating season, schedule spring start-up of cooling systems. If inspection occurs during cooling season, schedule autumn start-up for heating systems.
  - 2. Notify Owner 7 days minimum before scheduled start-up.
  - 3. Time will be allowed to completely service, test, check, and off-season start systems. During allowed time, train Owner's representatives in operation and maintenance of system.
  - 4. At end of off-season start-up, furnish Owner with letter confirming that above work has been satisfactorily completed.



B. Owner's Instructions

1. Instruct building maintenance personnel and Owner Representative in operation and maintenance of mechanical systems utilizing Operation & Maintenance Manual when so doing.
2. Minimum instruction periods shall be as follows –
  - a. Mechanical - Four hours.
  - b. Temperature Control - Four hours.
  - c. Refrigeration - Two hours.
3. Instruction periods shall occur after Substantial Completion inspection when systems are properly working and before final payment is made.
4. None of these instructional periods shall overlap another.

3.13 PROTECTION

- A. Do not run heat pump, air handling units, fan coil units, or other pieces of equipment used for moving supply air without proper air filters installed properly in system.
- B. The mechanical systems are not designed to be used for temporary construction heat. If any equipment is to be started prior to testing and substantial completion, such equipment will be returned to new condition with full one year warranties, from date of substantial completion after any construction use. This includes, but is not necessarily limited to: Equipment, filters, ductwork, fixtures, etc.

3.14 COMMON HVAC REQUIREMENTS:

A. INSTALLATION

1. During installation, protect open ends of ducts by covering with plastic sheet tied in place to prevent entrance of debris and dirt.
2. Make necessary allowances and provisions in installation of sheet metal ducts for structural conditions of building. Revisions in layout and configuration may be allowed, with prior written approval of Architect. Maintain required airflows in suggesting revisions.
3. Hangers And Supports:
  - a. Install pair of hangers close to each transverse joint and elsewhere as required by spacing indicated in table on Drawings.
  - b. Install upper ends of hanger securely to floor or roof construction above by method shown on Drawings.
  - c. Attach strap hangers to ducts with cadmium-plated screws. Use of pop rivets or other means will not be accepted.
  - d. Where hangers are secured to forms before concrete slabs are poured, cut off flush all nails, strap ends, and other projections after forms are removed.
  - e. Secure vertical ducts passing through floors by extending bracing angles to rest firmly on floors without loose blocking or shimming. Support vertical ducts, which do not pass through floors, by using bands bolted to walls, columns, etc. Size, spacing, and method of attachment to vertical ducts shall be same as specified for hanger bands on horizontal ducts.

B. CLEANING

1. Clean interior of duct systems before final completion.

**END OF SECTION 23 0501**

## SECTION 23 0502 - DEMOLITION AND REPAIR

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

#### 1.2 SUMMARY

- A. Under this section remove obsolete piping and mechanical equipment and relocate, reconnect or replace existing piping affected by demolition or new construction. Remove concealed piping abandoned due to demolition or new construction, or cap piping flush with existing surfaces.

#### 1.3 DRAWINGS AND EXISTING CONDITIONS

- A. All relocations, reconnections and removals are not necessarily indicated on the drawings. As such, the Contractor shall make adequate allowance in his proposal for this work as no extra charges will be allowed for these items.

### PART 2 - NOT USED

### PART 3 - EXECUTION

#### 3.1 TEMPORARY CONNECTIONS

- A. Where existing piping must remain in service to supply occupied areas during construction, provide temporary piping, connections, and equipment to maintain service to such areas. All shall be performed in a neat and safe manner to prevent injury to the building or its occupants.

#### 3.2 EXISTING TO BE ABANDONED

- A. All required drilling, cutting, block-outs and demolition work required for the removal and/or installation of the mechanical system is the responsibility of this Contractor.
- B. No joists, beams, girders, trusses or columns shall be cut by any Contractor without written permission from the Architect.
- C. The patching, repair, and finishing to existing or new surfaces is the responsibility of this Contractor, unless specifically called for under sections of specifications covering these materials.
- D. Disconnect all equipment that is to be removed or relocated. Relocate any existing equipment that obstructs new construction.

#### 3.3 EXISTING TO REMAIN IN USE

- A. Where affected by demolition or new construction, relocate, replace, extend, or repair piping and equipment to allow continued use of same. Use methods and materials as

specified for new construction.

3.4 MATERIALS AND EQUIPMENT REMOVED

- A. All obsolete materials, piping, and equipment shall become the property of the Contractor and be removed from the site promptly.

**END OF SECTION 23 0502**

## **SECTION 23 0553 - IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

#### **1.2 SUMMARY**

- A. Furnish and install identification of equipment and piping as described in Contract Documents.
- B. Mechanical Contractor shall touch-up equipment where factory paint has been damaged. Repaint entire item where more than 20 percent of the surface is involved.
- C. Primary painting of walls, ceilings, ductwork, piping and plenums is covered in the general painting section of these Contract Documents.

### **PART 2 - PRODUCTS**

#### **2.1 PAINT**

- A. Benjamin Moore Impervo or equivalent by Paint Manufacturer approved in Section 09 900.
- B. Use appropriate primer.

#### **2.2 LABELS**

- A. Black Formica with white reveal on engraving.

#### **2.3 CODED BANDS**

- A. Using colored bands and arrows to indicate supply and return, with colored reflective tape, color code all piping installed in this contract at not more than 20-foot intervals, at equipment, at walls, etc., in accordance with ANSI Standards.
- B. Approved Manufacturers:
  - 1. Seton
  - 2. Craftmark

#### **2.4 PIPE IDENTIFICATION**

- A. In addition to the colored bands, stencil with black paint in 1/2 inch high letters a symbol and directional arrow for all fluids handled or use Seaton coded and colored pipe markers and arrows to meet ANSI Standards.

#### **2.5 EQUIPMENT IDENTIFICATION**

- A. Provide an engraved plastic plate for each piece of equipment stating the name of the

item, symbol number, area served, and capacity. Label all control components with plastic embossed mechanically attached labels. Sample:

1. Supply Fan SF-1 - North Classrooms
2. 10,000 CFM @ 2.5"

## 2.6 VALVE IDENTIFICATION

- A. Make a list of and tag all valves installed in this work.
  1. Valve tags shall be of brass, not less than 1"x2" size, hung with brass chains.
  2. Tag shall indicate plumbing or heating service.

## PART 3 - EXECUTION

### 3.1 APPLICATION

- A. Engraved Plates:
  1. Identify thermostats and control panels in mechanical rooms, furnaces, boilers and hot water heating specialties, duct furnaces, air handling units, electric duct heaters, and condensing units with following data engraved and fastened to equipment with screws –
    - a. Equipment mark noted on Drawings (i.e., SF-1)
    - b. Area served (i.e., North Classrooms)
    - c. Capacity (10,000 CFM @ 2.5)
- B. Stenciling:
  1. Locate identifying legends and directional arrows at following points on each piping system –
    - a. Adjacent to each item of equipment and special fitting.
    - b. At point of entry and exit where piping goes through wall.
    - c. On each riser and junction.
    - d. Every 50 feet on long continuous lines.
  2. Gas, & Valve Identification –
    - a. Identify specific pipe contents by stenciling pipe with written legend and placing of arrows to indicate direction of flow.
- C. Painting:
  1. Background Color - Provide by continuous painting of piping.

Symbol	Name	Color
HPS	Heat Pump Supply	Blue
HPR	Heat Pump Return	Blue
AIR	Air	Blue

2. Identification stenciling and flow arrows shall be following colors for proper contrast:

<u>Arrows &amp; ID Stenciling</u>	<u>Color Shade of Pipe</u>
White	Red, Grays, & black
Black	Yellows, Oranges, Greens, & White

**END OF SECTION 23 0553**

## SECTION 23 0593 - TESTING, ADJUSTING, AND BALANCING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Division 23 0501 - Common HVAC Requirements and Basic Mechanical Materials and Methods Sections apply to work of this section.

#### 1.2 SUMMARY SCOPE

- A. This Section includes TAB to produce design objectives for the following:
  - 1. Air Systems.
    - a. Heat Pumps.

#### 1.3 SUBMITTALS

- A. Agency Data:
  - 1. Submit proof that the proposed testing, adjusting, and balancing agency meets the qualifications specified below. The firm or individuals performing the work herein specified may not be the installing firm.
- B. Engineer and Technicians Data:
  - 1. Submit proof that the Test and Balance Engineer assigned to supervise the procedures, and the technicians proposed to perform the procedures meet the qualifications specified below.
- C. Procedures and Agenda: Submit a synopsis of the testing, adjusting, and balancing procedures and agenda proposed to be used for this project.
- D. Sample Forms: Submit sample forms, if other than those standard forms prepared by the AABC or NEBB are proposed.
- E. Certified Reports: Submit testing, adjusting, and balancing reports bearing the seal and signature of the Test and Balance Engineer. The reports shall be certified proof that the systems have been tested, adjusted, and balanced in accordance with the referenced standards; are an accurate representation of how the systems have been installed; are a true representation of how the systems are operating at the completion of the testing, adjusting, and balancing procedures; and are an accurate record of all final quantities measured, to establish normal operating values of the systems. Follow the procedures and format specified below.
  - 1. Draft Reports: Upon completion of testing, adjusting, and balancing procedures, prepare draft reports on the approved forms. Draft reports may be hand written, but must be complete, factual, accurate, and legible. Organize and format draft reports in the same manner specified for the final reports. Submit 2 complete sets of draft reports. Only 1 complete set of draft reports will be returned.
  - 2. Final Report: Upon verification and approval of draft reports, prepare final reports, type written, and organized and formatted as specified below. Submit 4 complete sets of final reports.
  - 3. Report Format: Report forms shall be those standard forms prepared by the referenced standard for each respective item and system to be tested, adjusted,

and balanced. Bind report forms complete with schematic systems diagrams and other data. Divide the contents of the binder into the below listed divisions, separated by divider tabs:

- a. General Information and Summary
- b. Air Systems
- c. Temperature Control System Verification.

- F. Report Contents: Provide the following minimum information, forms, and data:
1. General information and Summary: Inside cover sheet to identify testing, adjusting, balancing agency, Contractor, Owner, Engineer, and Project. Include addresses and contact names and telephone numbers. Also include a certification sheet containing the seal and name, address, telephone number, and signature of the Certified Test and Balance Engineer. Include in this division a listing of the instrumentation used for the procedures along with the instrument calibration sheet.
  2. The remainder of the report shall contain the appropriate forms containing as a minimum, the information indicated on the standard report forms prepared by the AABC or NEBB, for each respective item and system. Prepare a schematic diagram for each item of equipment and system to accompany each respective report form. The report shall contain the following information, and all other data resulting from the testing, adjusting, and balancing work:
    - a. All nameplate and specification data for all air handling equipment and motors.
    - b. Actual metered running amperage for each phase of each motor on all pumps and air handling equipment.
    - c. Actual metered voltage at air handling equipment (phase-to-phase for all phases).
    - d. Fan RPM for each piece of air handling equipment.
    - e. Total actual CFM being handled by each piece of air handling equipment.
    - f. Actual CFM of systems by rooms.
  3. Certify that all smoke and fire dampers operate properly and can be reset under actual system operating conditions.
- G. Calibration Reports:
1. Submit proof that all required instrumentation has been calibrated to tolerances specified in the referenced standards, within a period of six months prior to starting the project.

#### 1.4 CERTIFICATION

- A. Agency Qualifications:
1. Employ the services of a certified testing, adjusting, and balancing agency meeting the qualifications specified below, to be the single source of responsibility to test, adjust, and balance the building mechanical systems identified above, to produce the design objectives. Services shall include checking installations for conformity to design, measurement, and establishment of the fluid quantities of the mechanical systems as required to meet design specifications, recording and reporting the results, and operation of all systems to demonstrate satisfactory performance to the owner.
  2. The testing, adjusting, and balancing agency certified by National Environmental Balancing Bureau (NEBB) or Associated Air Balance Council (AABC) in those testing and balancing disciplines required for this project, and having at least one

person certified by NEBB or AABC as a Test and Balance supervisor, and a registered professional mechanical engineer, licensed in the state where the work will be performed.

- B. Codes and Standard:
  - 1. NEBB: "Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems."
  - 2. AABC: "National Standards for Total System Balance."
  - 3. ASHRAE: ASHRAE Handbook, 1984 Systems Volume, Chapter 37, Testing, Adjusting, and Balancing.

## 1.5 PROJECT CONDITIONS

- A. Systems Operation: Systems shall be fully operation and clean prior to beginning procedures.

## 1.6 SEQUENCING AND SCHEDULING

- A. Test, adjust, and balance the air systems before hydronic, steam, and refrigerant systems within +10% to -5% of contract requirements.
- B. The report shall be approved by the Engineer. Test and balance shall be performed prior to substantial completion.

## PART 2 - NOT USED

## PART 3 - EXECUTION

### 3.1 PRELIMINARY PROCEDURES FOR AIR SYSTEM BALANCING

- A. Before operating the system, perform these steps.
  - 1. Obtain design drawings and specifications and become thoroughly acquainted with the design intent.
  - 2. Obtain copies of approved shop drawings of all air handling equipment, outlets (supply, return, and exhaust) and temperature control diagrams.
  - 3. Compare design to installed equipment and field installations.
  - 4. Walk the system from the system air handling equipment to terminal units to determine variations of installation from design.
  - 5. Check filters for cleanliness and to determine if they are the type specified.
  - 6. Check dampers (both volume and fire) for correct and locked position. Check automatic operating and safety controls and devices to determine that they are properly connected, functioning, and at proper operating setpoint.
  - 7. Prepare report test sheets for both fans and outlets. Obtain manufacturer's outlet factors and recommended procedures for testing. Prepare a summation of required outlet volumes to permit a cross-check with required fan volumes.
  - 8. Determine best locations in main and branch ductwork for most accurate duct traverses.
  - 9. Place outlet dampers in the full open position.
  - 10. Prepare schematic diagrams of system "As-Built" ductwork and piping layouts to facilitate reporting.
  - 11. Lubricate all motors and bearings.
  - 12. Check fan belt tension.



13. Check fan rotation.

### 3.5 MEASUREMENTS

- B. Provide all required instrumentation to obtain proper measurements, calibrated to the tolerances specified in the referenced standards. Instruments shall be properly maintained and protected against damage.
- C. Provide instruments meeting the specifications of the referenced standards.
- D. Use only those instruments which have the maximum field measuring accuracy and are best suited to the function being measured.
- E. Apply instrument as recommended by the manufacturer.
- F. Use instruments with minimum scale and maximum subdivisions and with scale ranges proper for the value being measured.
- G. When averaging values, take a sufficient quantity of readings which will result in a repeatability error of less than 5%. When measuring a single point, repeat readings until 2 consecutive identical values are obtained.
- H. Take all readings with the eye at the level of the indicated value to prevent parallax.
- I. Use pulsation dampeners where necessary to eliminate error involved in estimating average of rapidly fluctuation readings.
- J. Take measurements in the system where best suited to the task.

### 3.6 PERFORMING TESTING, ADJUSTING, AND BALANCING

- K. Perform testing and balancing procedures on each system identified, in accordance with the detailed procedures outlined in the referenced standards. Balancing of the air systems and hydronic systems shall be achieved by adjusting the automatic controls, balancing valves, dampers, air terminal devices, and the fan/motor drives within each system.
- L. Cut insulation, ductwork, and piping for installation of test probes to the minimum extent necessary to allow adequate performance of procedures.
- M. Patch insulation, ductwork, and housings, using materials identical to those removed.
- N. Seal ducts and piping, and test for and repair leaks.
- O. Seal insulation to re-establish integrity of the vapor barrier.
- P. Adjust timing relays of environmental equipment motor reduced voltage starters to the optimum time period for the motor to come up to the maximum reduced voltage speed and then transition to the full voltage speed to prevent damage to motor, and to limit starting current spike to the lowest possible and practical.
- Q. Mark equipment settings, including damper control positions, valve indicators, fan speed control levers, and similar controls and devices, to show final settings. Mark

with paint or other suitable, permanent identification materials.

- R. Retest, adjust, and balance systems subsequent to significant system modifications, and resubmit test results.

### 3.7 RECORD AND REPORT DATA

- S. Record all data obtained during testing, adjusting, and balancing in accordance with, and on the forms recommended by the referenced standards, and as approved on the sample report forms.
- T. Prepare report of recommendations for correcting unsatisfactory mechanical performances when system cannot be successfully balanced.
- U. Report shall be certified and stamped by a registered professional mechanical engineer employed by the agency and licensed in the state where the work will be performed.
- V. Engineer is to provide a floor plan and test and balance contractor to include the plan in test and balance report and identify actual cfm on drawing or number the diffusers to match report.

### 3.8 DEMONSTRATION

- W. If requested, testing, adjusting, and balancing agency shall conduct any or all of the field tests in the presence of the engineer.
- X. Agency shall include a maximum of one (1) call back to the project within the one year warranty period to make additional adjustments if requested by the engineer.

**END OF SECTION 23 0593**

**SECTION 23 0712 - MECHANICAL INSULATION AND FIRE STOPPING**

**PART 1 - GENERAL**

**1.1 RELATED DOCUMENTS**

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

**1.2 SUMMARY**

- A. Furnish and install mechanical insulation and fire stopping as described in Contract Documents including but not limited to the following:
  - 1. Ductwork Insulation
  - 2. Fire Stopping

**1.3 QUALITY ASSURANCE**

- A. Insulation shall have composite (insulation, jacket or facing and adhesive used to adhere facing or jacket to insulation) fire and smoke hazard ratings as tested by Procedure ASTM E-84, NFPA 255 and UL 723 not exceeding: Flame Spread of 25 and Smoke Developed of 50.
- B. Insulation Contractor shall certify in writing, prior to installation, that all products to be used will meet the above criteria.
- C. Accessories, such as adhesives, mastics, cements, and tapes, for fittings shall have the same component ratings as listed above.
- D. Products, or their shipping cartons, shall bear a label indicating that flame and smoke ratings do not exceed above requirements.
- E. Any treatment of jacket or facings to impart flame and smoke safety shall be permanent.
- F. The use of water-soluble treatments is prohibited.

**END OF SECTION 23 0712**

## **SECTION 23 0716 - DUCTWORK INSULATION**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, and Section 23 0501 apply to this Section.

#### **1.2 SUMMARY**

- A. Furnish and install insulation on air ducts outside building insulation envelope as described in Contract Documents.
- B. Furnish and install insulation on fresh air ducts and combustion air ducts within building insulation envelope as described in Contract Documents.
- C. Furnish and install insulation on other air ducts where indicated on Drawings.

### **PART 2 - PRODUCTS**

#### **2.1 INSULATION**

- A. 1-1/2 inch thick fiberglass with aluminum foil scrim kraft facing and have a density of one lb/cu ft.
- B. Approved Manufacturers:
  - 1. Manville Microlite FSK
  - 2. CSG Type IV standard duct insulation
  - 3. Owens-Corning FRK
  - 4. Knauf (Duct Wrap FSK)

### **PART 3 - EXECUTION**

#### **3.1 INSTALLATION**

- A. Install duct wrap in accordance with Manufacturer's recommendations.
- B. Do not compress insulation except in areas of structural interference.
- C. Completely seal joints.

**END OF SECTION 23 0716**

## **SECTION 23 0717 – ROUND SUPPLY DUCT INSULATION**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

#### **1.2 SUMMARY**

- A. Furnish and install round supply duct insulation as described in Contract Documents.

#### **1.3 QUALITY ASSURANCE**

- A. Insulation shall be UL rated with FSK (foil-skrim-kraft) facing.

### **PART 2 - PRODUCTS**

#### **2.1 MANUFACTURED UNITS**

- A. Fiberglass blanket insulation
- B. Approved Manufacturers:
  1. Johns-Manville R-4 Microlite (R-4 does not include the vapor barrier material).
  2. Owens-Corning faced duct wrap insulation FRK-25 ED-150
  3. Certainteed Standard Duct Wrap.

### **PART 3 - EXECUTION**

#### **3.1 INSTALLATION**

- A. Insulate round air supply ducts.
- B. Facing shall overlap 2" at joints and shall be secured with outward clinch staples on 4" centers.
- C. Ducts over 30" in width shall have spot application of adhesive, weld pins or metal screws and caps on not more than 18" centers applied to underside.
- D. 3" wide vapor barrier paper shall be applied over seams and sealed with vapor barrier adhesive.
- E. Insulate attenuators.
- F. Insulate high and low pressure flex ducts.

**END OF SECTION 23 0717**

## SECTION 23 0718 - DUCT LINING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, and Section 23 0501 apply to this Section.

#### 1.2 SUMMARY

- A. Furnish and install acoustic lining in following above ground metal ductwork as described in Contract Documents unless detailed otherwise:
  1. Outside air
  2. Supply air
  3. Return air
  4. Mixed air
  5. Transfer air
  6. Relief air

#### 1.3 SYSTEM DESCRIPTION

- A. Duct dimensions shown on Drawings are for free area inside insulation. Allowance must be made for insulation, where applicable.

#### 1.4 RATINGS:

- A. Material shall have maximum air friction correction factor of 1.10 at 1000 FPM velocity and have a minimum sound absorption coefficient NRC of .60.

### PART 2 - PRODUCTS

#### 2.1 DUCT LINER

- A. One inch thick, 1-1/2 lb density fiberglass, factory edge coated.
- B. Duct lining materials are to meet the requirements of UL 181 for mold, humidity, and erosion resistance.
- C. Approved Manufacturers:
  1. Certainteed Ultralite 150 Certa Edge Coat
  2. Knauf - Type M
  3. Manville - Lina-Coustic
  4. Owen Corning Fiberglas - Aeroflex

#### 2.2 ADHESIVE

- A. Water Base Type:
  1. Cain - Hydrotak
  2. Duro Dyne - WSA
  3. Kingco - 10-568

4. Miracle - PF-101
5. Mon-Eco - 22-67
6. Techno Adhesive - 133

B. Solvent Base (non-flammable) Type:

1. Cain - Safetak
2. Duro Dyne - FPG
3. Kingco - 15-137
4. Miracle - PF-91
5. Mon-Eco - 22-24
6. Techno Adhesive - 'Non-Flam' 106

C. Solvent Base (flammable) Type:

1. Cain - HV200
2. Duro Dyne - MPG
3. Kingco - 15-146
4. Miracle - PF-96
5. Mon-Eco - 22-22
6. Techno Adhesive - 'Flammable' 106

## 2.3 FASTENERS

A. Adhesively secured fasteners not allowed.

B. Approved Manufacturers:

1. AGM Industries Inc - "DynaPoint" Series DD-9 pin
2. Cain
3. Duro Dyne
4. Omark dished head "Insul-Pins"
5. Grip nails may be used if each nail is installed by "Grip Nail Air Hammer" or by "Automatic Fastener Equipment" in accordance with Manufacturer's recommendations.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Install mat finish surface on air stream side. Secure insulation to cleaned sheet metal duct with continuous 100% coat of adhesive and with 3/4 inch long mechanical fasteners 12 inches on center maximum unless detailed otherwise on Drawings. Pin all duct liner.
- B. Accurately cut liner and thoroughly coat ends with adhesive. Butt joints tightly. Top and bottom sections of insulation shall overlap sides. If liner is all one piece, folded corners shall be tight against metal. Ends shall butt tightly together.
- C. In casings and plenums further contain insulation with wire mesh.

### 3.2 FIELD QUALITY CONTROL

- A. If insulation is installed without longitudinal and end joints butted together, installation will be rejected and work removed and replaced with work that conforms to this

Specification.

- B. Insulation shall be installed in accordance with Duct Liner Application Standard SMACNA Manual 15.

### 3.3 ADJUSTING, CLEANING

- A. Keep duct liner clean and free from dust. At completion of project, vacuum duct liner if it is dirty or dusty.

**END OF SECTION 23 0718**



## **SECTION 23 0800 – FIRE STOPPING**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

#### **1.2 SUMMARY**

- A. Furnish and install fire stopping as described in Contract Documents.

#### **1.3 QUALITY ASSURANCE**

- A. Fire stopping material shall meet ASTM E814, E84 and be UL listed.

### **PART 2 - PRODUCTS**

#### **2.1 MANUFACTURED UNITS**

- A. Material shall be flexible, long lasting, intumescent acrylic seal to accommodate vibration and building movement.
- B. Caulk simple penetrations with gaps of 1/4" or less with:
  - 1. Dow Corning Fire Stop Sealant
  - 2. Pensil 300
- C. Caulk multiple penetrations and/or penetrations with gaps in excess of 1/4" with:
  - 1. Dow Corning Fire Stop Foam
  - 2. Pensil 200
  - 3. IPC flame safe FS-1900
  - 4. Tremco "Tremstop 1A"

### **PART 3 - EXECUTION**

#### **3.1 INSTALLATION**

- A. Follow manufacturer's installation instructions explicitly.
- B. Seal penetrations of ductwork, piping, and other mechanical equipment through one-hour and two-hour rated partitions as shown on Architectural and Mechanical Drawings.
- C. Install fire stopping material on clean surfaces to assure adherence.

**END OF SECTION 23 0800**

## SECTION 23 2113 - HYDRONIC PIPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes piping, special-duty valves, makeup water for these systems; blowdown drain lines; and condensate drain piping.

#### 1.3 DEFINITIONS

- A. CPVC: Chlorinated polyvinyl chloride.
- B. PVC: Polyvinyl chloride.

#### 1.4 SUBMITTALS

- A. Product Data: For each type of special-duty valve indicated. Include flow and pressure drop curves based on manufacturer's testing for diverting fittings, calibrated balancing valves, and automatic flow-control valves.
- B. Shop Drawings: Detail fabrication of pipe anchors, hangers, special pipe support assemblies, alignment guides, expansion joints and loops, and their attachment to the building structure. Detail location of anchors, alignment guides, and expansion joints and loops.
- C. Welding Certificates: Copies of certificates for welding procedures and personnel.
- D. Field Test Reports: Written reports of tests specified in Part 3 of this Section. Include the following:
  - 1. Test procedures used.
  - 2. Test results that comply with requirements.
  - 3. Failed test results and corrective action taken to achieve requirements.
- E. Maintenance Data: For hydronic specialties and special-duty valves to include in maintenance manuals specified in Division 23.
- F. Water Analysis: Submit a copy of the water analysis to illustrate water quality available at Project site.

#### 1.5 QUALITY ASSURANCE

- A. Welding: Qualify processes and operators according to the ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications."
- B. ASME Compliance: Comply with ASME B31.9, "Building Services Piping," for materials, products, and installation. Safety valves and pressure vessels shall bear the

appropriate ASME label. Fabricate and stamp air separators and expansion tanks to comply with the ASME Boiler and Pressure Vessel Code, Section VIII, Division 1.

- C To assure uniformity and compatibility of piping components in grooved end piping systems, all grooved products utilized shall be supplied by a single manufacturer. Grooving tools shall be supplied by the same manufacturer as the grooved components.

## 1.6 COORDINATION

- A. Coordinate layout and installation of hydronic piping and suspension system components with other construction, including light fixtures, HVAC equipment, fire-suppression-system components, and partition assemblies.
- B. Coordinate pipe sleeve installations for foundation wall penetrations.
- C. Coordinate piping installation with roof curbs, equipment supports, and roof penetrations.
- D. Coordinate pipe fitting pressure classes with products specified in related Sections.
- E. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into base. Concrete, reinforcement, and formwork requirements are specified in Division 3 Sections.
- F. Coordinate installation of pipe sleeves for penetrations through exterior walls and floor assemblies. Coordinate with requirements for firestopping specified in Division 7 Section "Through-Penetration Firestop Systems" for fire and smoke wall and floor assemblies.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Grooved Mechanical-Joint Fittings and Couplings:
    - a. Central Sprinkler Company; Central Grooved Piping Products.
    - b. Grinnell Mechanical Products.
    - c. Victaulic Company of America.
  - 2. Calibrated Balancing Valves:
    - a. Armstrong Pumps, Inc.
    - b. Flow Design, Inc.
    - c. Gerand Engineering Company.
    - d. Griswold Controls.
    - e. ITT Bell & Gossett; ITT Fluid Technology Corp.
    - f. Taco, Inc.
    - g. Tour Andersson supplied by Victaulic

3. Automatic Flow-Control Valves:
  - a. Flow Design, Inc.
  - b. Griswold Controls.

## 2.2 PIPING MATERIALS

- A. General: Refer to Part 3 "Piping Applications" Article for applications of pipe and fitting materials.

## 2.3 COPPER TUBE AND FITTINGS

- A. Drawn-Temper Copper Tubing: ASTM B 88, Type L.
- B. Annealed-Temper Copper Tubing: ASTM B 88, Type K.
- C. DWV Copper Tubing: ASTM B 306, Type DWV.
- D. Wrought-Copper Fittings: ASME B16.22.
- E. Wrought-Copper Unions: ASME B16.22.
- F. Solder Filler Metals: ASTM B 32, 95-5 tin antimony.
- G. Brazing Filler Metals: AWS A5.8, Classification BAg-1 (silver).

## 2.4 STEEL PIPE AND FITTINGS

- A. Steel Pipe, NPS 2 and Smaller: ASTM A 53, Type S (seamless) or Type F (furnace-butt welded), Grade B, Schedule 40, black steel, plain ends.
- B. Steel Pipe, NPS 2-1/2 through NPS 12: ASTM A 53, Type E (electric-resistance welded), Grade B, Schedule 40, black steel, plain ends.
- C. Steel Pipe, NPS 14 through NPS 18: ASTM A 53, Type E (electric-resistance welded) or Type S (seamless), Grade B, Schedule 30, black steel, plain ends.
- D. Steel Pipe, NPS 20: ASTM A 53, Type E (electric-resistance welded) or Type S (seamless), Grade B, Schedule 20, black steel, plain ends.
  1. Steel Pipe Nipples: ASTM A 733, made of ASTM A 53, Schedule 40, black steel; seamless for NPS 2 and smaller and electric-resistance welded for NPS 2-1/2 and larger.
- E. Cast-Iron Threaded Fittings: ASME B16.4; Classes 125 and 250.
- F. Malleable-Iron Threaded Fittings: ASME B16.3, Classes 150 and 300.
- G. Malleable-Iron Unions: ASME B16.39; Classes 150, 250, and 300.
- H. Cast-Iron Pipe Flanges and Flanged Fittings: ASME B16.1, Classes 25, 125, and 250; raised ground face, and bolt holes spot faced.
- I. Wrought-Steel Fittings: ASTM A 234/A 234M, wall thickness to match adjoining pipe.

- J. Wrought Cast- and Forged-Steel Flanges and Flanged Fittings: ASME B16.5, including bolts, nuts, and gaskets of the following material group, end connections, and facings:
1. Material Group: 1.1.
  2. End Connections: Butt welding.
  3. Facings: Raised face.
- K. Grooved Mechanical-Joint Fittings: ASTM A 536, Grade 65-45-12 ductile iron; ASTM A 47, Grade 32510 malleable iron; ASTM A 53, Type F, E, or S, Grade B fabricated steel; or ASTM A 106, Grade B steel fittings with grooves or shoulders designed to accept grooved end couplings.
- L. **Standard Mechanical Couplings, 2 inch through 12 inch:** Manufactured in two segments of cast ductile iron, conforming to ASTM A-536, Grade 65-45-12. Gaskets shall be pressure-responsive synthetic rubber, grade to suit the intended service, conforming to ASTM D-2000. (Gaskets used for potable water applications shall be UL classified in accordance with ANSI/NSF-61 for potable water service.) Mechanical Coupling bolts shall be zinc plated (ASTM B-633) heat treated carbon steel track head conforming to ASTM A-449 and ASTM A-183, minimum tensile strength 110,000 psi (758450 kPa).
- a. **Rigid Type:** Coupling housings with offsetting, angle-pattern bolt pads shall be used to provide system rigidity and support and hanging in accordance with ANSI B31.1, B31.9, and NFPA 13.
    1. 2 inch through 12 inch: Installation ready rigid coupling for direct stab installation without field disassembly. Gasket shall be Grade EPDM compound designed for operating temperatures from -30 deg F to +250 deg F. Gasket temperature rating shall be met without the use of special lubricants.
  - b. **Flexible Type:** Use in locations where vibration attenuation and stress relief are required. Flexible couplings may be used in lieu of flexible connectors at equipment connections. Three couplings, for each connector, shall be placed in close proximity to the vibration source.
    1. 2" through 8": Installation-ready flexible coupling for direct stab installation without field disassembly. Gasket shall be grade EPDM compound designed for operating temperatures from -30 deg F to +250 deg F. Gasket temperature rating shall be met without the use of special lubricants.
    2. 10" through 12": Standard flexible couplings. Gasket shall be Grade "E" EPDM compound designed for operating temperatures from -30 deg F to +230 deg F.
- M. Flexible Connectors: Stainless-steel bellows with woven, flexible, bronze, wire-reinforcing protective jacket; 150-psig minimum working pressure and 250 deg F maximum operating temperature. Connectors shall have flanged or threaded-end connections to match equipment connected and shall be capable of 3/4-inch misalignment.
- N. Spherical, Rubber, Flexible Connectors: Fiber-reinforced rubber body with steel flanges drilled to align with Classes 150 and 300 steel flanges; operating temperatures up to 250 deg F and pressures up to 150 psig.
- O. Packed, Slip, Expansion Joints: 150-psig minimum working pressure, steel pipe fitting consisting of telescoping body and slip-pipe sections, packing ring, packing, limit rods,

flanged ends, and chrome-plated finish on slip-pipe telescoping section.

- P. Welding Materials: Comply with Section II, Part C, of the ASME Boiler and Pressure Vessel Code for welding materials appropriate for wall thickness and for chemical analysis of pipe being welded.
- Q. Gasket Material: Thickness, material, and type suitable for fluid to be handled; and design temperatures and pressures.

## 2.5 VALVES

- A. Gate, globe, check, ball, and butterfly valves are specified in Division 23 Section "Valves."
- B. Grooved-End Butterfly Valves
  - 1. 2" through 12" Sizes: 300 psi CWP suitable for bidirectional and dead-end service at full rated pressure. Body shall be grooved end black enamel coated ductile iron conforming to ASTM A536. Disc shall be electroless nickel plated ductile iron with blowout proof 416 stainless steel stem. Disc shall be offset from the stem centerline to allow full 360 degree circumferential seating. Seat shall be pressure responsive EPDM. Valve bearings shall be TFE lined fiberglass, and stem seals shall be of the same grade elastomer as the valve seat. Valve shall be complete with ISO flange for actuation mounting. Valve operators shall be lever handle or gear operator, available with memory stop feature, locking device, chainwheel, or supplied bare. (Valve with EPDM seat is UL classified in accordance with ANSI/NSF-61.)
- C. Grooved-End Check Valves
  - 1. 2 inch through 12 inch sizes: Spring Assisted: Black enamel coated ductile iron body, ASTM A-536, Grade 65-45-12, elastomer encapsulated ductile iron disc suitable for intended service, stainless steel spring and shaft, welded-in nickel seat, 300 psi. Valve with pre-tapped ports as available option.
- D. Refer to Part 3 "Valve Applications" Article for applications of each valve.
- E. Calibrated Balancing Valves, NPS 2 and Smaller: Bronze body, ball type, 125-psig working pressure, 250 deg F maximum operating temperature, and having threaded ends. Valves shall have calibrated orifice or venturi, connections for portable differential pressure meter with integral seals, and be equipped with a memory stop to retain set position.
- F. Calibrated Balancing Valves, NPS 2-1/2 and Larger: Cast-iron or steel body, ball type, 125-psig working pressure, 250 deg F maximum operating temperature, and having flanged or grooved connections. Valves shall have calibrated orifice or venturi, connections for portable differential pressure meter with integral seals, and be equipped with a memory stop to retain set position.
- G. Pressure-Reducing Valves: Diaphragm-operated, bronze or brass body with low inlet pressure check valve, inlet strainer removable without system shutdown, and noncorrosive valve seat and stem. Select valve size, capacity, and operating pressure to suit system. Valve shall be factory set at operating pressure and have capability for field adjustment.

- H. Safety Valves: Diaphragm-operated, bronze or brass body with brass and rubber, wetted, internal working parts; shall suit system pressure and heat capacity and shall comply with the ASME Boiler and Pressure Vessel Code, Section IV.
- I. Automatic Flow-Control Valves: Gray-iron body, factory set to maintain constant flow with plus or minus 5 percent over system pressure fluctuations, and equipped with a readout kit including flow meter, probes, hoses, flow charts, and carrying case. Each valve shall have an identification tag attached by chain, and be factory marked with the zone identification, valve number, and flow rate. Valve shall be line size and one of the following designs:
  - 1. Gray-iron or brass body, designed for 175 psig at 200 deg F with stainless-steel piston and spring.
  - 2. Brass or ferrous-metal body, designed for 300 psig at 250 deg F with corrosion-resistant, tamperproof, self-cleaning, piston-spring assembly easily removable for inspection or replacement.
  - 3. Combination assemblies, including bronze ball valve and brass alloy control valve, with stainless-steel piston and spring, fitted with pressure and temperature test valves, and designed for 300 psig at 250 deg F.

## 2.6 HYDRONIC SPECIALTIES

- A. Manual Air Vent: Bronze body and nonferrous internal parts; 150-psig working pressure; 225 deg F operating temperature; manually operated with screwdriver or thumbscrew; with NPS 1/8 discharge connection and NPS 1/2 inlet connection.
- B. Automatic Air Vent: Designed to vent automatically with float principle; bronze body and nonferrous internal parts; 150-psig working pressure; 240 deg F operating temperature; with NPS 1/4 discharge connection and NPS 1/2 inlet connection.
- C. Y-Pattern Strainers: 125-psig working pressure; cast-iron body (ASTM A 126, Class B), flanged ends for NPS 2-1/2 and larger, threaded connections for NPS 2 and smaller, bolted cover, perforated stainless-steel basket, and bottom drain connection.
- D. Grooved Y-Pattern Strainer: 2 inch through 18 inch sizes, 300 PSI Y-Type Strainer shall consist of ductile iron body, ASTM A-536, Grade 65-45-12, Type 304 stainless steel perforated metal removable baskets with 1/16" (1,6mm) diameter perforations 2"-3" strainer sizes, 1/8" (3,2mm) diameter perforations 4"-12" strainer sizes, and 0.156" (4mm) diameter perforations 14" -18" strainer sizes. Strainer basket shall be accessed by removal of mechanical coupling.
- E. Basket Strainers: 125-psig working pressure; high-tensile cast-iron body (ASTM A 126, Class B), flanged-end connections, bolted cover, perforated stainless-steel basket, and bottom drain connection.
- F. T-Pattern Strainers: 750-psig working pressure; ductile-iron or malleable-iron body, grooved-end connections, stainless-steel basket with 57 percent free area; removable access coupling and end cap for strainer maintenance.
- N. Grooved T-Pattern Strainer: 2" through 12" sizes, 300 PSI T-Type Strainer shall consist of ductile iron (ASTM A-536, Grade 65-45-12) body, Type 304 stainless steel frame and mesh removable basket with No. 12 mesh, 2"-3" strainer sizes, or No. 6 mesh, 4"-12" strainer sizes, 57% free open area. Strainer basket shall be accessed by

removal of mechanical coupling.

- O. Flexible Connectors: Stainless-steel bellows with woven, flexible, bronze, wire-reinforcing protective jacket; 150-psig minimum working pressure and 250 deg F maximum operating temperature. Connectors shall have flanged- or threaded-end connections to match equipment connected and shall be capable of 3/4-inch misalignment.

## PART 3 - EXECUTION

### 3.1 PIPING APPLICATIONS

- A. Heat Pump Water, NPS 2 and Smaller: Aboveground, use Type L drawn-temper copper tubing with soldered joints or Schedule 40 steel pipe with threaded joints. Belowground or within slabs, use Type K annealed-temper copper tubing with soldered joints. Use the fewest possible joints belowground and within floor slabs.
- B. Heat Pump Water, NPS 2-1/2 and Larger: Schedule 40 steel pipe with welded and flanged joints.
- C. Condensate Drain Lines: Type L drawn-temper copper tubing with soldered joints or Schedule 40, PVC pipe with solvent-welded joints.

### 3.2 VALVE APPLICATIONS

- A. General-Duty Valve Applications: Unless otherwise indicated, use the following valve types:
  - 1. Shutoff Duty: Gate, ball, and butterfly valves.
  - 2. Throttling Duty: Globe, ball, and butterfly valves.
- B. Install shutoff duty valves at each branch connection to supply mains, at supply connection to each piece of equipment, unless only one piece of equipment is connected in the branch line. Install throttling duty valves at each branch connection to return mains, at return connections to each piece of equipment, and elsewhere as indicated.
- C. Install calibrated balancing valves in the return water line of each heating or cooling element and elsewhere as required to facilitate system balancing.
- D. Install check valves at each pump discharge and elsewhere as required to control flow direction.
- E. Install safety valves on hot-water generators and elsewhere as required by the ASME Boiler and Pressure Vessel Code. Install safety-valve discharge piping, without valves, to floor. Comply with the ASME Boiler and Pressure Vessel Code, Section VIII, Division 1, for installation requirements.
- F. Install pressure-reducing valves on hot-water generators and elsewhere as required to regulate system pressure.



### 3.3 PIPING INSTALLATIONS

- A. Refer to Division 23 Section "Basic Mechanical Materials and Methods" for basic piping installation requirements.
- B. Install groups of pipes parallel to each other, spaced to permit applying insulation and servicing of valves.
- C. Install drains, consisting of a tee fitting, NPS 3/4 ball valve, and short NPS 3/4 threaded nipple with cap, at low points in piping system mains and elsewhere as required for system drainage.
- D. Install piping at a uniform grade of 0.2 percent upward in direction of flow.
- E. Reduce pipe sizes using eccentric reducer fitting installed with level side up.
- F. Unless otherwise indicated, install branch connections to mains using tee fittings in main pipe, with the takeoff coming out the bottom of the main pipe. For up-feed risers, install the takeoff coming out the top of the main pipe.
- G. Install strainers on supply side of each control valve, pressure-reducing valve, solenoid valve, in-line pump, and elsewhere as indicated. Install NPS 3/4 nipple and ball valve in blowdown connection of strainers NPS 2 and larger. Match size of strainer blowoff connection for strainers smaller than NPS 2.
- H. Anchor piping for proper direction of expansion and contraction.

### 3.4 HANGERS AND SUPPORTS

- A. Hanger, support, and anchor devices are specified in Division 23 Section "Hangers and Supports." Comply with requirements below for maximum spacing of supports.
- B. Install the following pipe attachments:
  - 1. Adjustable steel clevis hangers for individual horizontal piping less than 20 feet long.
  - 2. Adjustable roller hangers and spring hangers for individual horizontal piping 20 feet or longer. cal runs at roof, at each floor, and at 10-foot intervals between floors.

### 3.5 PIPE JOINT CONSTRUCTION

- A. Refer to Division 23 Section "Basic Mechanical Materials and Methods" for joint construction requirements for soldered and brazed joints in copper tubing; threaded, welded, and flanged joints in steel piping; and solvent-welded joints for PVC and CPVC piping.

### 3.6 HYDRONIC SPECIALTIES INSTALLATION

- A. Install manual air vents at high points in piping, at heat-transfer coils, and elsewhere as required for system air venting.
- B. Install automatic air vents in mechanical equipment rooms only at high points of system piping, at heat-transfer coils, and elsewhere as required for system air venting.

- C. Install dip-tube fittings in boiler outlet. Install piping to expansion tank with a 2 percent upward slope toward tank. Connect boiler-outlet piping.
- D. Install in-line air separators in pump suction lines. Install piping to compression tank with a 2 percent upward slope toward tank. Install drain valve on units NPS 2 and larger.
- E. Install combination air separator and strainer in pump suction lines. Install piping to compression tank with a 2 percent upward slope toward tank. Install blowdown piping with gate valve; extend to nearest drain.
- F. Install bypass chemical feeders in each hydronic system where indicated, in upright position with top of funnel not more than 48 inches above floor. Install feeder in bypass line, off main, using globe valves on each side of feeder and in the main between bypass connections. Pipe drain, with ball valve, to nearest equipment drain.
- G. Install expansion tanks above air separator. Install gage glass and cocks on end of tank. Install tank fitting in tank bottom and charge tank. Use manual vent for initial fill to establish proper water level in tank.
  - 1. Support tank from floor or structure above with sufficient strength to carry weight of tank, piping connections, and fittings, plus weight of a full tank of water. Do not overload building components and structural members.
- H. Install expansion tanks on floor. Vent and purge air from hydronic system, and ensure tank is properly charged with air to suit system design requirements.

### 3.7 TERMINAL EQUIPMENT CONNECTIONS

- A. Size for supply and return piping connections shall be same as for equipment connections.
- B. Install control valves in accessible locations close to connected equipment.
- C. Install bypass piping with globe valve around control valve. If multiple, parallel control valves are installed, only one bypass is required.
- D. Install ports for pressure and temperature gages at coil inlet connections.

### 3.8 FIELD QUALITY CONTROL

- A. Prepare hydronic piping according to ASME B31.9 and as follows:
  - 1. Leave joints, including welds, uninsulated and exposed for examination during test.
  - 2. Provide temporary restraints for expansion joints that cannot sustain reactions due to test pressure. If temporary restraints are impractical, isolate expansion joints from testing.
  - 3. Flush system with clean water. Clean strainers.
  - 4. Isolate equipment from piping. If a valve is used to isolate equipment, its closure shall be capable of sealing against test pressure without damage to valve. Install blinds in flanged joints to isolate equipment.

5. Install safety valve, set at a pressure no more than one-third higher than test pressure, to protect against damage by expanding liquid or other source of overpressure during test.
6. Grooved pipe ends shall be clean and free from indentations, projections and roll marks in the area from pipe end to groove for proper gasket sealing.
7. The grooved couplings gasket style and elastomeric material (grade) shall be verified as suitable for the intended service as specified.
8. Grooved couplings installation shall be complete when visual metal-to-metal contact is reached.

### 3.9 GROOVED PIPING TRAINING

- A. A factory trained representative (direct employee) of the grooved coupling supplier shall provide on-site training for contractor's field personnel in the use of grooving tools, application of groove, and product installation.

## PART 4 - TESTING

- A. Perform the following tests on hydronic piping:
  1. Use ambient temperature water as a testing medium unless there is risk of damage due to freezing. Another liquid that is safe for workers and compatible with piping may be used.
  2. While filling system, use vents installed at high points of system to release trapped air. Use drains installed at low points for complete draining of liquid.
  3. Check expansion tanks to determine that they are not air bound and that system is full of water.
  4. Subject piping system to hydrostatic test pressure that is not less than 1.5 times the design pressure. Test pressure shall not exceed maximum pressure for any vessel, pump, valve, or other component in system under test. Verify that stress due to pressure at bottom of vertical runs does not exceed either 90 percent of specified minimum yield strength or 1.7 times "SE" value in Appendix A of ASME B31.9, "Building Services Piping."
  5. After hydrostatic test pressure has been applied for at least 10 minutes, examine piping, joints, and connections for leakage. Eliminate leaks by tightening, repairing, or replacing components and repeat hydrostatic test until there are no leaks.
  6. Prepare written report of testing.

### 4.8 ADJUSTING

- A. Mark calibrated nameplates of pump discharge valves after hydronic system balancing has been completed, to permanently indicate final balanced position.
- B. Perform these adjustments before operating the system:
  1. Open valves to fully open position. Close coil bypass valves.
  2. Check pump for proper direction of rotation.
  3. Set automatic fill valves for required system pressure.
  4. Check air vents at high points of system and determine if all are installed and operating freely (automatic type), or bleed air completely (manual type).
  5. Set temperature controls so all coils are calling for full flow.
  6. Check operation of automatic bypass valves.

7. Check and set operating temperatures of boilers, chillers, and cooling towers to design requirements.
8. Lubricate motors and bearings.

#### 4.9 CLEANING

- A. Flush hydronic piping systems with clean water. Remove and clean or replace strainer screens. After cleaning and flushing hydronic piping systems, but before balancing, remove disposable fine-mesh strainers in pump suction diffusers.

**END OF SECTION 23 2113**

## **SECTION 23 2200 - WATER SOURCE HEAT PUMP SYSTEM**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, and Section 23 0501 apply to this Section.

#### **1.2 SUMMARY**

- A. Furnish and install water source heat pump system as described in Contract Documents.

#### **1.3 QUALITY ASSURANCE**

- A. Units of the type furnished shall have been in successful operation at least five years.
- B. Units shall be UL listed and ARI certified, and shall be in accordance with the Canadian Standards Association (CSI).
- C. The units shall have ARI, UL, and CSI labels.
- D. All units shall be factory tested under normal operation conditions and normal water flow rates. Units that are tested without water flow are not acceptable.
- E. Units shall be Climate Master, Trane or Mammoth.

#### **1.4 WARRANTY**

- A. Compressors shall be provided with five-year warranties.

### **PART 2 - PRODUCTS**

#### **2.1 GENERAL**

- A. System shall consist of water-to-air reverse cycle air conditioning units of the type, size, capacity, and style scheduled on the drawings.
- B. Units shall be interconnected thru a non-refrigerated central water system, maintained within an approximate temperature range of 40 degrees F. to 110 degrees F. by means of a supplementary heat source and closed circuit evaporative type water cooler.
- C. Piping system shall be two-pipe reverse-return as shown on the plans complete with primary and standby circulating pumps.
- D. Individual room temperature control including necessary safety and operating controls shall be furnished as integral or accessory parts of the air conditioning units.

#### **2.2 ELECTRO-HYDRONIC WATER SOURCE HEAT PUMPS**

- A. Refrigeration Circuit:

1. Units shall have a sealed refrigerant circuit including:
    - a. A hermetic compressor.
    - b. A refrigerant metering device.
    - c. A finned tube refrigerant to air heat exchanger.
    - d. A reversing valve.
    - e. A coaxial (tube in tube) refrigerant to water heat exchanger.
    - f. Safety controls including a high pressure switch, a low pressure sensor, and a low water temperature (thermostat) switch.
  2. Access fittings shall be factory installed on high and low pressure refrigerant lines to facilitate field service.
  3. Activation of any safety device shall prevent compressor operation via a lock out relay. The lockout relay shall be reset at the thermostat or at the contract furnished disconnect switch. Units which may be reset at the disconnect switch only are not acceptable.
  4. Hermetic compressors shall be internally sprung, externally isolated, with thermal overload protection and shall be located in an insulated compartment to minimize sound transmission. Units above 15,000 BTUH shall have the compressor mounted on spring isolators to reduce noise and vibration transmission. Rubber mounts for these larger units are not acceptable.
  5. Refrigerant to air heat exchangers shall utilize enhanced aluminum fins and rifled copper construction rated to withstand 425 psi refrigerant working pressure.
  6. Refrigerant to water heat exchangers shall be of copper inner water tube and steel refrigerant outer tube design, rated to withstand 450 psi working refrigerant pressure and 400 psi working water pressure.
  7. Refrigerant metering shall be accomplished by capillary tubes for units intended for use in standard operating ranges, or expansion valves for units intended for use in expanded operating ranges.
  8. Reversing valves shall be four-way solenoid activated refrigerant valves which shall fail to heating operation should the solenoid fail to function.
- B. Fan and Motor Assembly:
1. Units rated 60,000 BTUH and under shall have a direct drive centrifugal fan. The fan motor shall be 3-speed permanently lubricated, PSC type with thermal overload protection. Units supplied without permanently lubricated motors must provide external oilers for easy service. The fan motor shall be isolated from the fan housing by torsionally flexible isolation. Units 72,000 BTUH and above shall have a belt drive fan assembly. The assembly shall include a forward curved fan wheel, housing, solid steel fan shaft encased in ball bearings, fan pulley and adjustable motor sheave. The motor shall be a three phase, open type with external thermal overload protection. The motor shall be mounted on an adjustable base for proper belt tension. The fan and motor assembly must be capable of overcoming the external static pressures as shown on the schedule. External static pressure rating of the unit shall be based on a wet coil. Ratings based on dry coil shall not be acceptable.
- C. Electrical:
1. A control box shall be located within the unit and shall contain a transformer, controls for compressor, reversing valve and fan motor operation and shall have a terminal block for low voltage field wiring connections. Open controls in the air stream will not be acceptable. Units shall be name plated for use with time delay fuses or HACR circuit breakers. Unit controls shall be 24 volts and shall provide heating or cooling as required by the wall thermostat. Two compressor units

shall have a solid state time delay to prevent both compressors from starting simultaneously. Provide integral interface for DDC control.

D. Solid State Control System:

1. Units shall have a solid state control system. The control shall interface with any type of wall thermostat mechanical or electronic. The control system shall have the following features:
  - a. Anti-short cycle time delay on compressor operation, time delay shall be five (5) minutes minimum.
  - b. Random start on power up mode or return from night setback.
  - c. Minimized reversing valve operation for extended life and quiet operation.
  - d. Night setback override from low temperature thermostat.
  - e. Two (2) hour override initiated by a signal from wall thermostat.
  - f. Low voltage protection.
  - g. High voltage protection.
  - h. Ability to work with any thermostat.
  - i. Single grounded wire to initiate night setback, demand load shed, or emergency shutdown.
  - j. Unit shutdown on high or low refrigerant pressures.
  - k. Unit shutdown on low water temperature.
  - l. Option to reset unit at thermostat or disconnect.
  - m. Automatic intelligent reset. Unit shall automatically reset the unit 10 minutes after trip if the fault has cleared. Should a fault re-occur within 30 minutes after reset, the permanent lockout will occur.
  - n. Ability to defeat time delays for servicing.
  - o. Light emitting diodes (LED) to indicate high pressure, low pressure, low voltage, high voltage, freeze protection, condensate overflow and control voltage status.
  - p. Control logic shall only move the reversing valve when cooling is called for the first time. The reversing valve shall be held in this position until the first call for heating. This scheme ensures quiet operation and increased valve life. Only control schemes that provide this reduced reversing valve operation will be accepted.
  - q. Control board shall have an eight (8) pin plug to allow the future addition of RS485 DDC circuitry. Control boards that cannot be upgraded to DDC by plugging in a module shall not be allowed.
  - r. Control board shall allow up to three (3) units to be operated from one thermostat without any auxiliary controls.
  - s. Optional 24 volt relay shall be required to provide dry contact alarm when used with a DDC system.

E. Basic Construction:

1. Horizontal units shall be fabricated from heavy gauge (GS90) galvanized sheet metal. All interior surfaces shall be lined with 1/2 inch, 1 1/2 lb. acoustic type glass fiber insulation. All fiberglass shall be coated and have exposed edges tucked under flanges to prevent the introduction of glass fibers into the airstream. All insulation must be NFPA 90A. Vertical unit shall be as above except the cabinet will have a painted baked enamel finish.
2. All units must have an insulated panel separating the fan compartment from the compressor compartment. Units with the compressor in the airstream are not acceptable. Cabinets shall have separate holes and knockouts for entrance of line voltage and low voltage control wiring. Supply and return water connections

shall be copper FPT fittings and shall be securely mounted flush to the cabinet allowing for connection to a flexible hose without the use of a back-up wrench. Water connections which protrude through the cabinet or require the use of a backup wrench shall not be allowed.

3. To facilitate installation in minimal space requirements, units rated 30,000 BTUH and under shall have all electrical and water connections on the end of the cabinet opposite the duct connections. Contractor shall be responsible for any extra costs involved in the installation of units which do not have this feature. Contractor must also ensure that non-specified units can be easily removed for servicing and coordinate locations of electrical conduit and lights with the electrical contractor.
  4. Units shall have the air flow arrangements as shown on plans.
  5. Sound attenuation:
    - a. All units 15,000 BTUH and up must have a compressor discharge muffler.
    - b. Compressor side panels and base pan must have closed cell insulation rated at 5 lb/cu. ft. density.
    - c. All reciprocating compressors must have high density damping material applied to the compressor shell.
    - d. All units 15,000 BTUH and up shall have the compressors mounted on springs.
- F. Air Filters:
1. Units shall have a factory installed two (2) inch thick filter bracket for side filter removal. Units shall have a two (2) inch thick pleated 30% efficient filter. Contractor shall be furnished one (1) set of spare filters to be turned over to Owner on completion of start-up. Filters shall be standard filter sizes. If units utilize non-standard filter sizes, then the contractor shall provide 4 spare sets of filters for each unit.
- G. Units shall be furnished with a condensate overflow switch.
- H. Each individual horizontal or vertical heat pump will have a minimum EER of 10.5 or higher, and a heating COP of 3.8 or higher.

### 2.3 PIPING, PUMPS AND ACCESSORIES

- A. Water piping system shall be installed in accordance with the accompanying drawings to provide a self-balancing two-pipe reverse return arrangement.
- B. Piping shall be graded to prevent air pockets and to enable any entrained air to rise in the direction of flow. Provide air vents where there is a possibility of collecting air.
- C. Provide supply and return connections at each air conditioning unit location shown, plus any possible future locations as shown, to permit expansion or normal relocation and remodeling requirements.
- D. Provide and install two system pumps of capacity and head scheduled on the drawings; one for continuous operation with the other on standby.
- E. Hose Kits:
  1. All units 120,000 BTUH and below shall be connected with hoses. The hoses shall be two (2) feet long, metal braided and fire rated to meet UL 94. Non fire



rated hoses are not acceptable. The hose on the supply side of the unit will be complete with a ball valve and strainer. The hose on the return side will be complete with a ball valve and flow control valve that encompasses in one assembly an automatic flow control valve that will guarantee the specified flow rate plus or minus 5% over a wide pressure differential without having any external adjustments. The hose kit and flow control assembly shall be Griswold or Autoflow.

- F. Provide PVC hose or insulated copper condensate connection of each air conditioner to pitched condensate drain system. Connect copper to unit with flexible connection.
- G. Provide water makeup expansion tank, air separator, etc., as shown in Contact Documents.

## 2.4 CONTROLS

- A. Manufacturer of electro-hydraulic system components shall furnish the minimum list of system operating and safety controls.
- B. System Safety and Operating Controls:
  - 1. Solid-state components
  - 2. Factory-mounted and wired within a NEMA 1 enclosure with a locking front panel.
  - 3. Controls will monitor the system water loop and protect against malfunction, requiring field installation of just one temperature sensor plus a flow switch.
  - 4. The panel shall include:
    - a. Indicator lights
    - b. Temperature gage
    - c. Control relays
    - d. Alarm with silencer switch
    - e. Terminal board for convenient connection of all field wiring
    - f. Pump selector switch to equalize wear by interchanging operation of the primary pump and the standby pump.
  - 5. Controls shall automatically start the standby pump upon failure of the primary pump, with a pilot light indicating that the standby pump is operating.
  - 6. An alarm and pilot light will indicate loss of flow or extreme high or low system water temperature
  - 7. A contact shall open which can be used in a control circuit to interrupt operation of the heat pumps.
  - 8. Three stages of control shall be included to operate the heat rejecter in order to maintain a maximum system water temperature of approximately 90 deg. F.
  - 9. The four stages of control shall be included to operate the water heater as required to maintain a minimum supply temperature to the heat pumps of 60 deg. F.
- C. The individual room thermostats shall be furnished and installed by the control contractor. The thermostats shall be integrated with the existing BAS System and be two-stage heating and two-stage cooling with seven-day programmable system designed for heat pumps.
- D. Use heavy steel gym guards in Gym areas.

## PART 3 - EXECUTION

### 3.1 FIELD QUALITY CONTROL

- A. Complete system shall be installed in accordance with manufacturer's approved instructions and shall be equipped with necessary system operating and safety controls as detailed elsewhere in these specifications.
- B. It is **ESSENTIAL** that the finished piping system be thoroughly flushed free of foreign material and construction debris.
  - 1. Install strainer in system line at pump section.
  - 2. Flush system prior to final connection to any electro-hydraulic conditioner by means of loop bypass between supply to return at each unit location.
  - 3. The hoses for final connection may first be used for the loop bypass.
- C. Provide factory start-up of each heat pump and factory system operation check out of complete system.

**END OF SECTION 23 2200**

## SECTION 23 2600- CONDENSATE DRAIN PIPING

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Includes But Not Limited To:
  - 1. Furnish and install condensate drain piping as described in Contract Documents.
- B. Related Requirements:
  - 1. Section 23 0501: Common HVAC Requirements.

#### 1.2 REFERENCES

- A. Reference Standards:
  - 1. ASTM International:
    - a. ASTM B 88-03, 'Standard Specification for Seamless Copper Water Tube.'

### PART 2 - PRODUCTS

#### 2.1 SYSTEMS

- A. Materials:
  - 1. Condensate Drains:
    - a. Schedule 40 PVC for condensate drains from furnace combustion chambers and furnace cooling coils, and auxiliary drain pans.

### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Condensate Drains:
  - 1. Support piping and protect from damage.
  - 2. Do not combine PVC condensate drain piping from furnace combustion chamber with copper condensate drain piping from cooling coil.
  - 3. Do not combine auxiliary drain pan piping with furnace / Cooling Coil Condensate drain piping.

**END OF SECTION 23 2600**

## SECTION 23 3114 - LOW-PRESSURE STEEL DUCTWORK

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

#### 1.2 SUMMARY

- A. Furnish and install above-grade ductwork and related items as described in Contract Documents.

### PART 2 - PRODUCTS

#### 2.1 DUCTS

- A. Fabricate of zinc-coated lockforming quality steel sheets meeting requirements of ASTM 653A/653M, "Specification for Sheet Steel Zinc-Coated (Galvanized) by the Hot-Dip Process, Lock Forming Quality", with G 60 coating.
- B. Use of aluminum, non-metallic, or round ducts is not permitted. [Specification writer: Use of aluminum ducts in areas with high chlorine content (eg.: ventilation for pools, spas, etc.) should be considered on a per job basis.]

#### 2.2 DUCT JOINTS

- A. Ducts with sides up to and including 36 inches shall be as detailed in the SMACNA manual.
- B. Duct sizes over 36 inches shall be fabricated using SMACNA T-24 flange joints or pre-fabricated systems as follows:
  - 1. Ducts with sides over 36 inches to 48 inches:
    - a. transverse duct joint system by Ductmate/25, Nexus, Ward, or WDCI (Lite) (SMACNA "E" or "G" Type connection).
  - 2. Ducts 48 inches & larger:
    - a. Ductmate/35, Nexus, or WDCI (Heavy) (SMACNA "J" Type connection).
  - 3. Approved Manufacturers:
    - a. Ductmate Industries Inc, 10760 Bay Meadows Drive, Sandy, UT 84092 (801) 571-5308
    - b. Nexus, Exanno Corp, P O Box 729, Buffalo, NY 14206 (716) 849-0545
    - c. Ward Industries Inc, 1661 Lebanon Church Road, Pittsburg, PA 15236 (800) 466-9374
    - d. WDCI, P O Box 10868, Pittsburg, PA 15236 (800) 245-3188

#### 2.3 FLEXIBLE EQUIPMENT CONNECTIONS

- A. 30 oz closely woven UL approved glass fabric, double coated with neoprene.
- B. Fire retardant, waterproof, air-tight, resistant to acids and grease, and withstand constant temperatures of 250 deg F.

- C. Approved Manufacturers:
  - 1. Cain - N-100
  - 2. Duro Dyne - MFN
  - 3. Elgen - ZLN
  - 4. Ventfabrics - Ventglas

## 2.4 VOLUME DAMPERS

- A. In Main Ducts:
  - 1. 16 gauge galvanized steel, opposed blade type with 3/8 inch pins and end bearings. Blades shall have 1/8 inch clearance all around.
  - 2. Damper shall operate within acoustical duct liner.
  - 3. Provide channel spacer equal to thickness of duct liner.
  - 4. Approved Manufacturers:
    - a. Air Balance - Model AC-2
    - b. Air Control Products - CD-OB
    - c. American Warming - VC-2-AA
    - d. Greenheck - VCD-1100
    - e. NCA, Safe Air
    - f. Vent Products - 5100
- B. In Sheet Metal Branch Ducts:
  - 1. Extruded aluminum, opposed blade type. When in open position, shall not extend beyond damper frame.
  - 2. Maximum blade length 12 inches.
  - 3. Damper Regulator shall be concealed type with operation from bottom or with 90 deg miter gear assembly from side.
  - 4. Approved Manufacturers:
    - a. Air Control Products - TCD-OB
    - b. Air Guide - OB
    - c. Arrow - OBDAF-207
    - d. CESCO - CDA
    - e. Reliable Metals - OBD-RO
    - f. Tuttle & Bailey - A7RDDM
    - g. Safe Air
    - h. Young - 820-AC
- C. Dampers above removable ceiling and in Mechanical Rooms shall have locking quadrant on bottom or side of duct. Otherwise, provide concealed ceiling damper regulator and cover plate.

## 2.5 BACKDRAFT DAMPER

- A. Backdraft blades shall be nonmetallic and shall be neoprene coated fiberglass.
- B. Stop shall be galvanized steel screen or expanded metal, 1/2 inch mesh.
- C. Frame shall be galvanized steel or extruded aluminum alloy.
- D. Approved Models & Manufacturers:
  - 1. Air Control Products - FBD
  - 2. American Warming - BD-15

3. CESCO - FBD 101
4. Ruskin - NMS2
5. Safe Air

## 2.6 DUCT HANGERS

- A. 1" x 18 gauge galvanized steel straps or steel rods as shown on Drawings, and spaced not more than 8 feet apart. Do not use wire hangers.
- B. Attaching screws at trusses shall be 1-1/2 inch No. 10 round head wood screws. Nails not allowed.

## 2.7 DUCT SEALER

- A. Cain - Duct Butter or Butter Tak
- B. Design Polymerics - DP 1010
- C. DSC - Stretch Coat
- D. Duro Dyne - S2
- E. Hardcast - #601 Iron-Grip or Peel-N-Seal Tape
  1. Kingco - 15-325
  2. Mon-Eco - 44-41
  3. Trans-Continental Equipment Co - Multipurpose Duct Sealant
  4. United - Sheet Metal duct-sealer

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Ducts:
  1. Straight and smooth on inside with joints neatly finished unless otherwise directed.
  2. Duct panels through 48 inch dimension having acoustic duct liner need not be crossbroken or beaded.
  3. Crossbreak unlined ducts and duct panels larger than 48 inch or bead 12 inches on center.
  4. Securely anchor ducts to building structure with specified duct hangers attached with screws. Do not hang more than one duct from a duct hanger.
  5. Brace and install ducts so they shall be free of vibration under all conditions of operation.
  6. Ducts shall not bear on top of structural members.
  7. Make duct take-offs to branches, registers, grilles, and diffusers as detailed on Drawings.
  8. Ducts shall be large enough to accommodate inside acoustic duct liner. Dimensions shown on Drawings are net clear inside dimensions after duct liner has been installed.
  9. Properly flash where ducts protrude above roof.
  10. Install internal ends of slip joints in direction of flow. Make joints air tight using specified duct sealer.

11. Cover horizontal and longitudinal joints on exterior ducts with two layers of Hardcast tape installed with Hardcast HC-20 adhesive according to Manufacturer's recommendations.
  12. Paint ductwork visible through registers, grilles, and diffusers flat black.
- B. Install flexible inlet and outlet duct connections to each furnace, fan, fan coil unit, and air handling unit.
- C. Install concealed ceiling damper regulators.
1. Paint cover plates to match ceiling tile.
  2. Damper regulators will not be required for dampers located directly above removable ceilings or in Mechanical Rooms.
- D. Provide each take-off with an adjustable volume damper to balance that branch.
1. Anchor dampers securely to duct.
  2. Install dampers in main ducts within insulation.
  3. Dampers in branch ducts shall fit against sheet metal walls, bottom and top of duct, and be securely fastened. Cut duct liner to allow damper to fit against sheet metal.
  4. Where concealed ceiling damper regulators are installed, provide a cover plate.
- E. Install grilles, registers, and diffusers. Level floor registers and anchor securely into floor.
- F. Air Turns:
1. Permanently installed, consisting of single thickness curved metal blades with one inch straight trailing edge to permit air to make abrupt turn without appreciable turbulence, in 90 degree elbows of above ground supply and return ductwork.
  2. 4-1/2 inch wide minimum vane rail. Do not use junior vane rails.
  3. Double thickness vanes not acceptable.
  4. Quiet and free from vibration when system is in operation. See SMACNA Manual

**END OF SECTION 23 3114**

## SECTION 23 3346 - FLEX DUCT

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

#### 1.2 SUMMARY

- A. Furnish and install supply air branch duct runouts to diffusers as described in Contract Documents.

### PART 2 - PRODUCTS

#### 2.1 DUCTS

- A. Formable, flexible, circular duct which shall retain its cross-section, shape, rigidity, and shall not restrict air flow after bending.
- B. Nominal 1-1/2 inches thick, 3/4 lb/cu ft density fiberglass insulation with air-tight, polyethylene or polyester core, sheathed in seamless vapor barrier jacket factory installed over flexible assembly.
- C. Assembly, including insulation and vapor barrier, shall meet Class I requirement of NFPA 90A and be UL 181 rated, with flame spread of 25 or less and smoke developed rating of 50 or under.
- D. Length of flexible ductwork shall not exceed 8'-0".

#### 2.2 APPROVED MANUFACTURERS

- A. ANCO-FLEX - 4625
- B. Flex-Aire - PF/UPC #090
- C. Hart & Cooley - F114
- D. Thermaflex - G-KM

### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Install duct in fully extended condition free of sags and kinks.
- B. Make duct connections by coating exterior of duct collar for 3 inches with duct sealer and securing duct in place over sheet metal collar with 1/2 inch wide metal cinch bands and sheet metal screws.

**END OF SECTION 23 3346**



## SECTION 23 3713 - AIR OUTLETS & INLETS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings, General Provisions of Contract, including General and Supplementary Conditions and Section 23 0501 apply to this Section.

#### 1.2 SUMMARY

- A. Furnish and install wall supply registers, transfer grilles, return air grilles, soffit grilles, ceiling diffusers, louvers connected to ductwork, and registers as described in Contract Documents.

### PART 2 - PRODUCTS

#### 2.1 GRILLES & REGISTERS

- A. Approved Manufacturers:
  - 1. Price
  - 2. Anemostat
  - 3. Krueger
  - 4. Titus
  - 5. Tuttle & Bailey

#### 2.2 SPIN-IN FITTINGS

- A. Low pressure round take-offs to diffusers shall be made with spin-in fittings. They shall incorporate a manual balancing damper. The damper shall be spring loaded and a positive locking wing nut shall secure the damper position.
- B. Approved Manufacturers:
  - 1. Sheet metal fittings: Genflex DB-1DEL, Hercules

### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Anchor securely into openings.
- B. Install with screws to match color and finish of grilles and registers.
- C. Touch-up any scratched finish surfaces.
- D. Install in accordance with manufacturer's instructions.
- E. Check location of outlets and inlets and make necessary adjustments in position to conform with architectural features, symmetry, and lighting arrangement.
- F. Install diffusers to ductwork with air tight connection.

- G. Provide balancing dampers on duct take-off to diffusers, and grilles and registers, despite whether dampers are specified as part of the diffuser, or grille and register assembly.
- H. Paint ductwork visible behind air outlets and inlets matte black. Refer to Section 09 9000.

**END OF SECTION 23 3713**

**END OF DIVISION**